

CITY OF PORT HURON, MICHIGAN

**Dye Testing and
Private Property Inflow Source
Investigation**

SEVENTH AND NINTH STREETS

January 2001

CONTENTS

	Page
LIST OF TABLES AND FIGURES	iv
SUMMARY AND CONCLUSIONS	vi
INTRODUCTION	1
DYE TESTING	2
PRIVATE I/I INVESTIGATION	4
 APPENDICES	
APPENDIX A	PROPERTIES IDENTIFIED FOR DYE TESTING
APPENDIX B	PROPERTIES NOT NEEDING DYE TESTING
APPENDIX C	PROPERTIES WITH SUSPECTED IMPROPER CONNECTIONS

LIST OF TABLES AND FIGURES

Table	Page
1 Percentage of Buildings Identified for Dye Testing	2
2 Dye Testing Results	3
3 Occurrences of Suspected Inflow Sources	4
4 Improper Connections	5
5 Proper Connections	10

Figure

Figure (following text)

- 1 Project Area Map.
- 2 Sample Private I/I and Dye Testing Form.
- 3 Sample Letter Mailed to Residents.
- 4 Ameritech, 919 & 923 6th Street; and Masonic Temple, 927 6th Street
- 5 Port Huron Senior Center, 821 7th Street; Blue Water Food Center, 729 Howard Street; Active Lounge, 708, 710 & 712 Lapeer Ave.; Cut-Rite Barber shop, 714 Lapeer Ave.; Antiques Shop, 716 Lapeer Ave.; Shallcross Optical, 736 Lapeer Ave.
- 6 Port Huron Housing Commission, 920 8th Street, 735 Pine Street, 721 Pine Street, 919 7th Street, 705 Pine Street and 905 7th Street.
- 7 Grandview Towers, 1016 7th Street.
- 8 Flagship Federal Credit Union, 1814 10th Street.
- 9 Woodrow Wilson Elementary School, 834 Chestnut Street.
- 10 AAA Insurance, 933 Lapeer Ave. and Kimball Appliance, 945 Lapeer Ave.
- 11 American Red Cross, 615 Pine Street.
- 12 First Federal Savings Bank, 600 Water Street.
- 13 920 7th Street (Office) and Ruff Floral, 924 7th Street.
- 14 Mike's Beer * Liquor * Wine, 1928 Bancroft Street
- 15 Tom Manis Restaurant, 1232 10th Street
- 16 First United Methodist Church, 828 Lapeer Ave.

17 Pollack-Randall Funeral Home, 912 Lapeer Ave. and Big One Carpet Factory Outlet, 930 Lapeer Ave..

Attachments

Project Location Map with Dye Test Results

SUMMARY AND CONCLUSIONS

Private Inflow/Infiltration (I/I) Inspection and Dye Testing are conducted to identify connectivity of existing storm and sanitary service lead connections for the purpose of future sewer design. Future sewers would be designed to remove inflow from the sanitary sewer system, and to remove illicit sanitary connections from storm sewers.

This study/investigation includes the area bounded by Lapeer Street to the north, Division Street to the south, Sixth Street to the east and Tenth Street to the west. This investigation was performed by TTMPs field staff between May and October of 2000.

Objectives of Site Investigations:

- Determine connectivity of private property storm and sanitary service lead to the existing sewers.
- Identify buildings, which share service leads for purpose of providing separate service leads and sewer for future connection.
- Inspect for inflow sources connected to the sanitary sewer.

Buildings were selected to be dye tested based on the number and type of sewers surrounding the property. Properties with more than one sanitary or combined sewer surrounding the building were dye tested.

There are 542 properties in the study area. Of these, 224 properties, or 41%, were selected for dye testing. For additional information refer to Table 1.

Of the 224 buildings, 179 were dye tested with 45 buildings not dye tested due to denied access, no one home, traffic concerns, or no water service to property. For further information refer to Table 2.

Private I/I inspection was performed on all properties in the area. A total of 97 properties were suspected to have improper connections. For additional information, refer to Table 3.

Further investigation of the properties, through dye testing and/or sound testing, revealed four properties that have separate storm and sanitary sewer connections, while 86 properties had improper connections. Of these 86 properties, 62 properties had disappearing downspouts. Refer to Table 3 for further information.

INTRODUCTION

This report presents information regarding existing storm and sanitary connections. The information will help eliminate illicit connections to storm sewers and inflow sources to sanitary sewers.

The field investigation includes the area bounded by Lapeer Street to the north, Division Street to the south, Sixth Street to the east, and Tenth Street to the west.

The field investigation area is shown in Figure 1.

This study/investigation was performed by TTMPs staff between May and October of 2000. The fieldwork consisted of private I/I inspection of all homes, industries and commercial buildings and dye testing of selected buildings. Private I/I inspection included visual investigation of the interior/exterior of the property for existing drains (e.g., floor drains, roof drains, disappearing downspouts, etc). Dye testing involved tracing dye poured down the sanitary drain and observing the dye in a manhole downstream of the building.

A sample form of the private I/I and dye testing inspection form is shown in Figure 2.

The City of Port Huron Dye Testing and Private Source Investigation will assist in the elimination or adequate treatment of combined sewer outfalls. The investigations will help to adequately separate the combined area.

DYE TESTING

Buildings were selected for dye testing based on the number of sewers surrounding the property. Properties with more than one sanitary or combined sewer surrounding the building were selected for dye testing.

The following procedure was carried out for dye testing prior to entering the property:

- Letters were mailed to residents informing them of the pending investigations on their property. Refer to Figure 3 for a sample letter.
- Dye was premixed in a ratio of about three tablespoons powder dye to one-quart water.
- The manhole(s) which were most likely to be where dye would appear needed to be located, exposed and opened. Proper traffic control and personal safety measures were observed for manholes in roadways.

Percentage of properties identified for dye testing is listed in Table 1 below.

Table 1
Percentage of Buildings Identified for Dye Testing

	Buildings	Percentage of Buildings (%)
Total number of buildings in the area	540	100
Buildings identified for dye testing	204	38
Buildings eliminated from dye testing	336	62

Of the 204 buildings identified for dye testing, a certain percentage of the buildings were confirmed. The results of the dye tests are shown below in Table 2.

Table 2
Dye Testing Results

	Buildings	Percentage of Buildings (%)
Total Number of Buildings Identified for Dye Testing	204	100
Dye Test Confirmed	149	73
Dye Test Unconfirmed	17	8
Denied Access	1	0.5
No One Home	31	15
No Water Service	1	0.5
No Manhole Access (due to traffic)	5	3

For a detailed list of properties dye tested, refer to Appendix A. For a map of the dye test results, refer to Attachment A. The map shows the sewer to which the properties discharge. It should not be interpreted as confirming the route of the connection. Shared leads may be located in this area.

A similar list for properties not dye tested is included in Appendix B.

Some reasons for unconfirmed dye test are debris in sewers, septic tanks on property, or unidentified sewers in the area.

PRIVATE I/I INVESTIGATION

Private inflow/infiltration (I/I) inspection was performed on all properties in the area. A total of 97 properties were identified with possible improper connections (disappearing downspouts, surface drainage, sump pumps, etc.) on the property. The number of occurrences of each type of suspected improper connection is summarized below in Table 3.

Table 3
Occurrences of Suspected Inflow Sources

Type of Suspected Improper Connection	Number of Occurrences
Roof Drain (disappearing downspouts)	77
Window Well Drain	7
Patio Drain	1
Stairwell Drain	2
Catch Basin	17
Clean Out Caps Not Intact	9
Total # of Properties with Potential Private I/I Source	97*

After further investigation of the 97 sites, identified as having disappearing downspouts, surface drainage and/or sump pumps on the property, five sites were found to be connected properly. The remaining 85 sites were identified as having improper stormwater connections or the connection was not able to be determined.

Table 4 identifies those properties that were found to have improper stormwater connections and/or unknown connection.

* Some properties contain more than one suspected improper connection.

Table 4
Improper Connections

Property	Description of Improper Connection	Recommended Action
919 and 923 6th Street (Ameritech)	Disappearing downspouts, refer to Figure 4.	Owner of property must determine connection of disappearing downspout.
927 6th Street (Masonic Temple)	Disappearing downspout, refer to Figure 4.	Owner of property must determine connection disappearing downspout.
1213 6th Street (Episcopal Church)	Stairwell drain on property.	Owner must hire plumber to determine connection.
1433 6th Street	Disappearing downspouts	Disconnect downspouts
821 7 th Street (Port Huron Senior Center)	Catch basin on property, internal roof drain and stairwell drain, refer to Figure 5.	Building is scheduled to be demolished.
729 Howard Street (Blue Water Food Center)	Catch basin in parking lot and disappearing downspout, refer to Figure 5.	City to provide storm lead to parking lot either from Lapeer St. or 8 th Street. Owner must investigate disconnect downspouts. The building has an illicit connection.
<ol style="list-style-type: none"> 1. 708, 710 & 712 Lapeer Ave. (Active Lounge) 2. 714 Lapeer Ave. (Cut-Rite Barber Shop) 3. 716 Lapeer Ave. (Antiques) 4. 	Catch basins in parking lot, refer to Figure 5.	Owner to determine CB connection. City to provide storm lead to parking lot CBs.
736 Lapeer Ave. (Shallcross Optical)	Catch basins in parking lot, refer to Figure 5.	City to provide storm lead to parking lot CBs.
905 & 919 7 th Street; 705, 721, 735 Pine Street; 920 8 th Street. (Port Huron Housing Commission Office)	Catch basin in parking lot and disappearing downspout on property; refer to Figure 6.	City to provide storm or sanitary lead to building on 7 th Street. Owner must determine disappearing downspout and CB connections. Owner must separate private combined lines.

Property	Description of Improper Connection	Recommended Action
1013 7 th Street (St. Johns United Church of Christ).	Basement window well drain & internal drains.	Owner must hire plumber to determine connections.
1021 7 th Street	Disappearing downspouts	Disconnect downspouts
1208 7 th Street	Disappearing downspouts	Disconnect downspouts
1229 7 th Street (Victorian Inn).	Disappearing downspouts	Disconnect downspouts
1304 7 th Street	Disappearing downspouts	Disconnect downspouts
1317 7 th Street (St. Joseph Catholic Church)	Basement window well drain, disappearing downspouts and internal roof drains.	Owner must hire plumber to determine drain connections and disconnect downspouts.
1331 7 th Street (St Joseph Parish Family).	Disappearing downspouts	Disconnect downspouts
1402 7 th Street	Basement window well drain.	Owner must hire plumber to determine drain connection.
1408 7 th Street (Four Apts.)	Disappearing downspouts	Disconnect downspouts
1428 7 th Street	Disappearing downspouts	Disconnect downspouts
1521 7 th Street	Disappearing downspouts	Disconnect downspouts
821 8 th Street	Disappearing downspouts	Disconnect downspouts
825 8 th Street	Disappearing downspouts	Disconnect downspouts
913 8 th Street	Disappearing downspouts	Disconnect downspouts
1033 8 th Street (First Presbyterian Church).	Disappearing downspouts	Disconnect downspouts
1215 8 th Street	Disappearing downspouts	Disconnect downspouts
1225 8 th Street	Disappearing downspouts	Disconnect downspouts
1315 8 th Street	Disappearing downspouts	Disconnect downspouts
1330 8 th Street	Disappearing downspouts	Disconnect downspouts
1406 8 th Street	Disappearing downspouts and possible internal drain	Disconnect downspouts and owner must hire plumber to determine connection for internal roof drain.
1418 8 th Street	Disappearing downspouts	Disconnect downspouts
1524 8 th Street	Disappearing downspouts	Disconnect downspouts
1609 8 th Street	Basement window well drain.	Owner must hire plumber to determine drain connection.
920 9 th Street	Disappearing downspouts	Disconnect downspouts
1512 9 th Street	Disappearing downspouts	Disconnect downspouts

Property	Description of Improper Connection	Recommended Action
1819 9 th Street	External clean out not properly capped	Ower must cap cleanout properly
1823 9 th Street	External clean out not properly capped	Ower must cap cleanout properly
916 10 th Street	Disappearing downspouts	Disconnect downspouts
1122 10 th Street	Basement window well drain.	Owner must hire plumber to determine drain connection.
1304 10 th Street	External clean out not properly capped	Ower must cap cleanout properly
1308 10 th Street	Disappearing downspouts	Disconnect downspouts
1814 10 th Street (Flagship Federal Credit Union).	Manhole on property, refer to Figure 8.	Owner must hire plumber to determine connection.
1914 10 th Street	Disappearing downspout	Disconnect downspout
921 Bancroft Street	Disappearing downspouts	Disconnect downspouts
727 Chestnut Street	Disappearing downspouts	Disconnect downspout
805 Chestnut Street (St. Martins Lutheran Church).	Basement window well drain and disappearing downspouts	Owner must hire plumber to determine drain connections and disconnect downspouts.
834 Chestnut St. (Woodrow Wilson Elementary School)	Catch basin and disappearing downspout, refer to Figure 9.	City investigated CBs on property and determined the CBs to be connected to old sewer under school. City might need to provide storm lead to catch basins in front of school on Chestnut Street. City must also provide storm lead to CB in playground. Owner must hire plumber to determine disappearing downspout connections.
925 Chestnut Street	Disappearing downspouts	Disconnect downspout
722 Court Street	Disappearing downspouts	Disconnect downspouts
801 Court Street (Four apts.).	Disappearing downspouts	Disconnect downspouts
803 Court Street	Disappearing downspouts	Disconnect downspout
809 Court Street	Disappearing downspouts	Disconnect downspouts
819 Court Street	Disappearing downspouts	Disconnect downspout
822 Court Street	Disappearing downspouts	Disconnect downspouts

Property	Description of Improper Connection	Recommended Action
833 Court Street	Disappearing downspouts	Disconnect downspouts
903 Court Street (Community Bible Fellowship).	Disappearing downspouts	Disconnect downspouts
911 Court Street	Disappearing downspouts	Disconnect downspout
921 Court Street	Disappearing downspouts	Disconnect downspouts
603 Griswold Street (commercial)	Disappearing downspouts	Disconnect downspout
622 Griswold Street	Disappearing downspouts	Disconnect downspout
636 Griswold Street	Disappearing downspouts	Disconnect downspouts
731 Griswold Street	External clean out not properly capped	Ower must cap cleanout properly.
802 Griswold Street	Disappearing downspouts	Disconnect downspout
812 Griswold Street	Disappearing downspouts	Disconnect downspouts
942 Howard Street	Disappearing downspouts	Disconnect downspouts
802 Lapeer Ave.	Disappearing downspouts	Disconnect downspouts
930 Lapeer Ave. (Big 1 Carpet Factory Outlet)	Driveway drain and disappearing downspouts	City to provide storm lead from 9 th Street; owner to disconnect downspouts.
933 Lapeer Ave. (AAA Insurance)	Catch basins and disappearing downspouts, refer to Figure 10.	Owner to disconnect downspouts and hire plumber to investigate CB connections.
945 Lapeer Ave. (Kimball Appliance)	atch basin and disappearing downspout, refer to Figure 10.	Owner to disconnect downspouts and hire plumber to investigate CB connections.
615 Pine Street (American Red Cross).	Catch basins, patio drain and disappearing downspouts on property, refer to Figure 11.	According to site plans, storm and sanitary are separate. City to provide storm lead to parking lot. Owner to disconnect disappearing downspouts and hire plumber to determine connection for CB near patio drain.
710 Pine Street	Disappearing downspouts	Disconnect downspouts
811 Pine Street	Disappearing downspouts	Disconnect downspouts
815 Pine Street	Disappearing downspouts	Disconnect downspouts
821 Pine Street	Disappearing downspouts	Disconnect downspouts
940 Pine Street	Disappearing downspouts	Disconnect downspouts
620 Union Street	Disappearing downspouts	Disconnect downspouts

Property	Description of Improper Connection	Recommended Action
719 Union Street.	Basement window well drain and disappearing downspouts.	Owner to hire plumber to investigate basement window well drain connection and disconnect downspouts.
720 Union Street	Disappearing downspouts	Disconnect downspouts
729 Union Street	Disappearing downspouts	Disconnect downspouts
811 Union Street	Disappearing downspouts	Disconnect downspouts
816 Union Street	Disappearing downspouts	Disconnect downspout
827 Union Street	Disappearing downspouts	Disconnect downspout
828 Union Street	External clean out not properly capped	Ower must cap cleanout properly.
917 Union Street	Disappearing downspouts	Disconnect downspout
729 Wall Street	Disappearing downspouts	Disconnect downspout
735 Wall Street	Disappearing downspouts	Disconnect downspout
904 Wall Street	Disappearing downspouts	Disconnect downspout
913 Wall Street	External clean out not properly capped	Ower must cap cleanout properly.
600 Water Street (First Federal Savings Bank)	Catch basins on property and internal roof drain, refer to Figure 12.	City to provide storm lead for parking lot CBs and owner to hire plumber to investigate C.B. connections.
709 White Street	Disappearing downspouts	Disconnect downspouts
733 White Street	Disappearing downspouts	Disconnect downspout
737 White Street	External clean out not properly capped	Ower must cap cleanout properly.
814 White Street	Disappearing downspouts	Disconnect downspouts

Table 5 below identifies those sites with drains on the property and are connected properly.

Table 5
Proper Connections

Property	Description of Drains on Property.	Recommended Action
1016 7 th Street (Grandview Towers)	Catch basins on property and internal roof drains, refer to Figure 7.	All CBs on property were investigated by city. Results of investigation concludes internal roof drains connect to CBs, refer to Figure 7. All other piping in CBs is for subsurface drainage. The buildings sanitary lead connect to a sanitary sewer, verified through dye testing. City to provide storm sewer from 7 th Street to pick up CB in NW and SW parking lot (this project). City to provide storm sewer on Sixth Street to pick up CB in the NE parking lot (future project).
920 (Office) and 924 (Ruff Floral) 7 th Street	Catch basin on property and possible internal roof drain, refer to Figure 13.	According to site plan, building is separated. City to provide either sanitary or storm sewer in alley to pick up leads.
1928 10 th Street (Mike's Beer * Liquor* Wine).	Catch Basin on property, refer to Figure 14.	Owner must hire plumber to determine CB connection.
1232 10th Street (Tom Manis Restaurant)	Catch basins on property, refer to Figure 15.	Catch Basins in parking lot connect to city CB in street.
828 Lapeer Ave. (First United Methodist Church)	Catch basins on property, refer to Figure 16.	According to site plans, storm and sanitary are separate. City to provide either storm or sanitary to building. City to also provide storm lead to parking lot CBs.
912 Lapeer Ave. (Pollack-Randall Funeral Home)	Catch basins on property, refer to Figure 17.	City to provide storm lead for CBs in parking lot.

A detailed list of all properties with drains, disappearing downspouts or sump pumps are included in Appendix C.

FIGURES

DESIGNED:



TETRA TECH MPS

DATE: 10/25/00


PROJECT AREA MAP



CITY OF PORT HURON, MICHIGAN
SEWER SEPARATION AND
INFRASTRUCTURE IMPROVEMENTS
7TH & 9TH STREET AREA
PRIVATE SOURCE
INVESTIGATION

FIGURE

1



PORT HURON CSO CONCEPTUAL DESIGN ON-SITE INSPECTION FORM

BUILDING ADDRESS: _____

CSO AREA: _____

Building type: _____ No. of Households: _____

VISIT DATE/TIME: _____

R = residential, A = apartments

INSPECTOR(S): _____

C = commercial, I = industrial No. of Toilets: _____

WEATHER: _____

I/I ISSUE: _____

DYE TESTING

DOP #1 Result:	_____ *	in MH _____	Dir. _____;	MH's observed _____	_____	_____	_____	_____
DOP #2 Result:	_____ *	in MH _____	Dir. _____;	MH's observed _____	_____	_____	_____	_____
DOP #3 Result:	_____ *	in MH _____	Dir. _____;	MH's observed _____	_____	_____	_____	_____
DOP #4 Result:	_____ *	in MH _____	Dir. _____;	MH's observed _____	_____	_____	_____	_____
DOP #5 Result:	_____ *	in MH _____	Dir. _____;	MH's observed _____	_____	_____	_____	_____

ROOF DRAINAGE

Pitched Roof _____	Flat Roof _____						
Internal: _____	Disappear: _____	Run on Ground: _____	Missing: _____	If on ground, no. < 5' _____			
External: _____	Disappear: _____	Run on Ground: _____	Missing: _____	If on ground, no. < 5' _____			

AREA DRAINAGE

Y	N	Window Well Drains: _____	Stairwell Drains: _____	Driveway Drains: _____	
Patio Drains: _____		Catch Basins: _____	Investigation Results: _____		

BASEMENT

Basement:	Y	N	Depth below ground: _____	(Measured from bottom of windowsill down to basement floor.) Note location on sketch.	
			(in ft.)		
Any flooding history?	Y	N	If yes, no. of times per year: _____		
Sanitary service to basement?	Y	N			
Sump Pump?	Y	N	Discharges on ground?	Y	N (Show on sketch.)

SERVICE LEADS

Total number of leads from property: _____	No. Sanitary: _____	No. Storm: _____	No. Combined: _____	No. Unkn: _____
Does the building have any external clean out?	Y	N	If yes, is cap intact and properly connected? Y N	

RENOVATIONS

Have there been renovations?	Y	N		
If yes, any new service leads?	Y	N		
Have there been any service lead repairs, cleanings, and/or replacements? (If yes, describe in comments)	Y	N		

COMMENTS/NOTES:

* N = Not Needed
 O = Occupants Not Home
 D = Denied Access
 U = Unconfirmed
 C = Confirmed



City of Port Huron

100 MCMORAN BLVD.

PORT HURON, MI 48060

MUNICIPAL OFFICE CENTER

FAK: (810) 982-7872

Office of the City Engineer (810) 984-9730

May 15, 2000

Dear Property Owner/Lessee:

The City of Port Huron's representatives are currently working to separate the combined sewer system and to design the new sewers in the area. To ensure proper service to your home or business, they need to perform a site investigation. This investigation requires entrance to your home or business for the following activities:

1. Dye tests (putting dye down your drains or toilets) to determine which sanitary sewer you are currently served by.
2. Determination of your service lead depth by locating the position of your sewer pipe as it leaves your home or business. This measurement must be taken inside your home or business.
3. Perform an investigation to determine connection of downspouts and lawn, driveway or parking lot drains.


It is imperative that this investigation is performed so that your home or business can be properly connected to the new sewers.

This work is planned for May through December 2000. Inspectors will come to your home or business to perform the required investigations. These inspectors will have identification badges. Although you may not know it, discharging storm or ground water to the City's sanitary sewers is a violation of the City's Sewer Services Ordinance. The inspectors will assist you in identifying any violation of this ordinance and can advise you on how to resolve it.

Please refer to the enclosed information sheet for further explanation of the combined sewer separation project and instructions on identifying and removing inflow sources on your property. If you have any further questions regarding this work, please contact the City's Inflow Information Line at 984-4919.

We thank you for your cooperation.

Sincerely,



Robert E. Clegg, P.E.

REC/cil

What is a Combined Sewer System?

A combined sewer is one which collects both sewage from toilets, sinks and showers in homes and businesses (sanitary flow) as well as rainwater, which runs off lawns, roofs and streets into catch basins (storm flow).

What is the problem with a Combined Sewer System?

During heavy rains or as the snow melts in the spring the volume of rain water or snow melt which runs off the ground and the roofs into the combined sewer is much more than the sewer pipe and the wastewater treatment plant can handle. When this occurs, the sewers can backup through the sewer pipes connected to homes causing combined sewage and storm water to enter basements. To avoid some of these backups, the combined sewer has overflow points throughout the city (Combined Sewer Overflow (CSO's)), which allow the combined sewage to enter the Black and St. Clair Rivers.

What is the Solution?

The solution is to "separate" the sewer system. A "separated" system is one in which the sanitary sewage is collected in a piping network all by itself and is routed directly to the wastewater treatment plant and the storm water is collected in a different, "separate", piping network and directed to the river.

What is the City doing?

Port Huron's Public Works Department is undertaking a massive effort called Combined Sewer Overflow Control, which will separate the sewer system. This project has already begun in some of the city's neighborhoods and will continue until 2012, at which time the city's entire sanitary sewer system will be separated from its storm water system.

We need Your Help!

The residents and property owners of Port Huron are key to the success of this separation effort. Property owners are responsible for insuring that all sewage and storm water runoff from their property is directed to the correct piping system. City ordinances require that all sources of groundwater and storm water runoff be removed from the sanitary sewage system. Storm water or groundwater, which enters the sanitary sewage system, is called "inflow". Common private property inflow sources are lawn drains, driveway drains, gutters and downspouts. These inflow sources must be disconnected from the sanitary sewage pipe and either allowed to flow onto the ground, or be reconnected to the storm sewer. Once the new separate system is in place, illegally connected inflow sources will lead to basement flooding, since this new sanitary system will not have an outlet to the river for excess flow.

Timeline for Removal.

A city representative will inspect your property for compliance with the city ordinances in the next few weeks. **Compliance is mandatory.** All inflow source must be removed from your property in order to be in compliance. If the inspectors identify an improper connection to the sanitary sewer on your property, you will be responsible for removing them prior to sewer construction in your area. If the sources are not removed promptly, you could potentially risk basement flooding in your home or your neighbor's home. If you need assistance removing a source or have questions about possible sources, please call the number below and a city representative will assist you.

Inflow removal costs

The cost for removal of inflow sources to comply with the city ordinances is your responsibility. You may remove inflow sources yourself, or hire a contractor to assist you depending on the complexity of the removal. Doing it yourself, however, may save you money.

CSO Information Line

For additional information and assistance please call the City's Inflow Information Line at 984-4919.

CORRECTIONAL ACTIVITIES

Downspout Disconnection

Materials needed:

Downspout elbow
Concrete splash block
Wire tie
2ft. by 2ft. piece of metal screening
or chicken wire

Downspout extension
#12 Gage wire (two metal coat
hangers will work)
Newspaper
Concrete mix

1. Using the downspout elbow, downspout extension, and the splash block, redirect the downspout flow to the ground surface as illustrated in Figure 1. Note: Redirecting downspout may involve cutting off the bottom portion of the existing downspout to allow for the elbow and extension pieces. Remember to use the proper safety equipment while cutting metal, i.e., protective gloves and safety glasses. Downspout flow should be directed at least 4 feet away from the foundation.

2. Using the #12 gage steel wire (or coat hanger) form two, 1 foot deep "U" shaped stirrups. The width of the "U" should equal the width of your downspout at the point which it enters the ground (the downspout lead). The ends of the "U" should have hooks, which will wrap all of the way around the top of your downspout lead. Figure 1.

3. Place the two stirrups so that the bottom of the "U"'s form a plus (+) sign and use the wire tie to fasten them together at the point which they cross.

4. Place the stirrups in the downspout lead as shown in Figure 2. Make sure that the hooks at the top of the stirrups are over the edge of the downspout lead.

5. Insert the metal screen so that it lines the inside of the downspout lead and forms a basket inside the stirrups. Figure 2.

6. Tightly pack newspaper in the bottom 6 inches of the wire screen basket inside the downspout lead. It is very important that the paper plug is tight to prevent the concrete from entering the sanitary lead for the house.




Figure 1 - Relocated Downspout and Plugged Riser Pipe




Figure 2 - Wire Basket Assembly

7. Mix a "stiff" mix of concrete following the instructions on the bag of concrete. The concrete should be mixed such that if you scoop out a portion with a cup and dump it out onto a board, the concrete should not lose the cup shape or spread out (run) on the board.

Figure 3. (For existing plugs see Fig. 4)

8. Scoop the concrete into the downspout lead on top of the newspapers filling the lead to the top (about 6 inches of concrete). (Immediately wash off any concrete that comes in contact with skin or clothes)

The above procedure can also be used to plug a hole in an existing downspout plug.

Cleanout Problems

If your cleanout for your sewer lead is located outside, rainwater may enter the sanitary system through a broken or leaking sanitary system through a broken or missing cleanout cap. A new cap can be purchased at most local hardware stores. Figure 5.

Other Connection Problems

Figures 6 and 6A illustrate some of the other, less common sources of inflow into the sanitary sewers. The solutions to these problems are more complex and vary according to the individual situation. If you think you have one of these inflow sources on your property, please call the combined sewer information line for individual guidance.




Figure 3 - Plug Detail




Figure 4 - New Plug Detail for Existing Concrete Seal




Figure 5 - Cleanout Problem







Figure 6 - Connected Downspouts

Figure 6A - Typical Rainwater Sources



NOTE:
723 COURT STREET – FIRST
CONGREGATIONAL CHURCH –



TETRA TECH MPS

DESIGNED:


DATE: 4/13/04

- DYE TEST RESULTS**
- DYE TEST CONFIRMED
 - DYE TEST UNCONFIRMED
 - NO ACCESS
 - CONNECTIONS OBTAINED FROM SITE PLANS
- DAP = DYE APPLICATION POINT
DOP = DYE OBSERVATION POINT

- UNKNOWN – ASSUMED CONNECTION
- DIRECT CONNECTION
- DDS = DISAPPEARING DOWNSPOUT



CITY OF PORT HURON, MICHIGAN
SEWER SEPARATION AND
INFRASTRUCTURE IMPROVEMENTS
7TH & 9TH STREET AREA
PRIVATE SOURCE
INVESTIGATION



NOTE:

BLUE WATER FOOD CENTER - RESTROOM DYE TESTED TO NEW SEWER GOING TO SANITARY SEWER ON 7TH STREET.

708-716 LAPEER - LEAD NOT FOUND FOR 708-712. ROWE LEFT LEAD IN ALLEY AND LAPEER FOR FUTURE CONNECTION. 714-716 LEAD FOUND AND CONNECTED IN LAPEER.

SHALLCROSS OPTICAL SITE FOUND OK.

MEETING MINUTES 11-29-01

821 7TH STREET - ROOF SUMPS SOUND TESTED TO THE SANITARY SEWER ON 7TH STREET. SWD UNKNOWN.

DESIGNED: **TETRA TECH MPS**

DATE: 10/25/00

DYE TEST RESULTS

- DYE TEST CONFIRMED
- DYE TEST UNCONFIRMED
- NO ACCESS
- CONNECTIONS OBTAINED FROM SITE PLANS


DAP = DYE APPLICATION POINT
DOP = DYE OBSERVATION POINT


----- UNKNOWN - ASSUMED CONNECTION
----- DIRECT CONNECTION
o DDS = DISAPPEARING DOWNSPOUT

CITY OF PORT HURON, MICHIGAN
SEWER SEPARATION AND
INFRASTRUCTURE IMPROVEMENTS

7TH & 9TH STREET AREA
PRIVATE SOURCE
INVESTIGATION

FIGURE
5



DESIGNED:  TETRA TECH MPS

DATE: 10/25/00

DYE TEST RESULTS

- DYE TEST CONFIRMED
- DYE TEST UNCONFIRMED
- NO ACCESS
- CONNECTIONS OBTAINED FROM SITE PLANS


DAP = DYE APPLICATION POINT
DOP = DYE OBSERVATION POINT

----- UNKNOWN - ASSUMED CONNECTION
----- DIRECT CONNECTION
○ DDS = DISAPPEARING DOWNSPOUT

CITY OF PORT HURON, MICHIGAN
SEWER SEPARATION AND
INFRASTRUCTURE IMPROVEMENTS
7TH & 9TH STREET AREA
PRIVATE SOURCE
INVESTIGATION

FIGURE
6

NOTE:
TMPS TO PROVIDE LETTER OUTLINING
ISSUES. ROWE LEFT LEADS FOR
FUTURE CONNECTION. (MEETING
MINUTES 11-29-01)

DESIGNED:  TETRA TECH MPS

DATE: 10/25/00

DYE TEST RESULTS


- DYE TEST CONFIRMED
- DYE TEST UNCONFIRMED
- NO ACCESS
- CONNECTIONS OBTAINED FROM SITE PLANS

DAP = DYE APPLICATION POINT
DOP = DYE OBSERVATION POINT

UNKNOWN - ASSUMED CONNECTION


DIRECT CONNECTION


DDS = DISAPPEARING DOWNSPOUT



CITY OF PORT HURON, MICHIGAN
SEWER SEPARATION AND
INFRASTRUCTURE IMPROVEMENTS
7TH & 9TH STREET AREA
PRIVATE SOURCE
INVESTIGATION

FIGURE
7



DESIGNED:  **TETRA TECH MPS**


DATE: 10/25/00

DYE TEST RESULTS

- DYE TEST CONFIRMED
- DYE TEST UNCONFIRMED
- NO ACCESS
- CONNECTIONS OBTAINED FROM SITE PLANS

DAP = DYE APPLICATION POINT
DOP = DYE OBSERVATION POINT


--- UNKNOWN - ASSUMED CONNECTION
--- DIRECT CONNECTION
--- DDS = DISAPPEARING DOWNSPOUT



NOTE:
 TMPS TO RE-CHECK PROPERTY TO DETERMINE CONNECTIONS OF CATCH BASINS. (MEETING MINUTES 11-29-01)

CITY OF PORT HURON, MICHIGAN
 SEWER SEPARATION AND INFRASTRUCTURE IMPROVEMENTS
 7TH & 9TH STREET AREA
 PRIVATE SOURCE INVESTIGATION

FIGURE 8




DESIGNED: **TE** TETRA TECH MPS
 DATE: 10/25/00


DYE TEST RESULTS
 ● DAP = DYE APPLICATION POINT
 ● DOP = DYE OBSERVATION POINT
 --- UNKNOWN - ASSUMED CONNECTION
 --- DIRECT CONNECTION
 ○ DDS = DISAPPEARING DOWNSPOUT

CITY OF PORT HURON, MICHIGAN
 SEWER SEPARATION AND INFRASTRUCTURE IMPROVEMENTS
 7TH & 9TH STREET AREA
 PRIVATE SOURCE INVESTIGATION

FIGURE 9



NOTE:
 TMPS TO DYE TEST DISAPPEARING DOWNSPOUTS TO VERIFY CONNECTION TO SITE STORM AND CATCH BASINS TO VERIFY CONNECTION TO CENTRAL STORM. (MEETING MINUTES 11-29-01)

DESIGNED:  TETRA TECH MPS

DATE: 10/25/00

DYE TEST RESULTS

- Red circle: DYE TEST CONFIRMED
- Green circle: DYE TEST UNCONFIRMED
- Blue circle: NO ACCESS
- Orange circle: CONNECTIONS OBTAINED FROM SITE PLANS


DAP = DYE APPLICATION POINT
 DDP = DYE OBSERVATION POINT


--- UNKNOWN - ASSUMED CONNECTION
 --- DIRECT CONNECTION
 o DDS = DISAPPEARING DOWNSPOUT



CITY OF PORT HURON, MICHIGAN
 SEWER SEPARATION AND
 INFRASTRUCTURE IMPROVEMENTS
 7TH & 9TH STREET AREA
 PRIVATE SOURCE
 INVESTIGATION

FIGURE 10




DESIGNED:  TETRA TECH MPS

DATE: 10/25/00

- DYE TEST RESULTS**
- DYE TEST CONFIRMED
 - DYE TEST UNCONFIRMED
 - NO ACCESS
 - CONNECTIONS OBTAINED FROM SITE PLANS
- DAP = DYE APPLICATION POINT
DOP = DYE OBSERVATION POINT

- UNKNOWN - ASSUMED CONNECTION
- DIRECT CONNECTION
- DDS = DISAPPEARING DOWNSPOUT




CITY OF PORT HURON, MICHIGAN
SEWER SEPARATION AND
INFRASTRUCTURE IMPROVEMENTS
7TH & 9TH STREET AREA
PRIVATE SOURCE
INVESTIGATION

FIGURE
11

DESIGN NOTES PER ROWE:
SANITARY TO REMAIN
STORM TO BE ADDED

TO BRICK SEWER BY VIDEO



NOTE:
 DAP #1 - CB DYE TESTED, DYE OBSERVED IN COMBINED MANHOLE IN WATER STREET.
 DAP #2 - RESTROOM DYE TESTED, DYE OBSERVED IN COMBINED MANHOLE IN WATER STREET.
 DAP #3 - ROOF SUMP DYE TESTED, DYE OBSERVED IN COMBINED MANHOLE IN WATER STREET.

DESIGNED: **TETRA TECH MPS**

DATE: 10/25/00

- DYE TEST RESULTS**
- DYE TEST CONFIRMED
 - DYE TEST UNCONFIRMED
 - NO ACCESS
 - CONNECTIONS OBTAINED FROM SITE PLANS
- DAP = DYE APPLICATION POINT
 DOP = DYE OBSERVATION POINT

- UNKNOWN - ASSUMED CONNECTION
- DIRECT CONNECTION
- DDS = DISAPPEARING DOWNSPOUT



CITY OF PORT HURON, MICHIGAN
 SEWER SEPARATION AND
 INFRASTRUCTURE IMPROVEMENTS
 7TH & 9TH STREET AREA
 PRIVATE SOURCE
 INVESTIGATION

DESIGNED:



TETRA TECH MPS

DATE: 10/25/00

- DYE TEST CONFIRMED
- DYE TEST UNCONFIRMED
- NO ACCESS
- CONNECTIONS OBTAINED FROM SITE PLANS

DYE TEST RESULTS


- DAP = DYE APPLICATION POINT
- DOP = DYE OBSERVATION POINT


- UNKNOWN - ASSUMED CONNECTION
- DIRECT CONNECTION
- o DDS = DISAPPEARING DOWNSPOUT





CITY OF PORT HURON, MICHIGAN
SEWER SEPARATION AND
INFRASTRUCTURE IMPROVEMENTS
7TH & 9TH STREET AREA
PRIVATE SOURCE
INVESTIGATION

FIGURE
13







DESIGNED:  TETRA TECH MPS

DATE: 10/25/00

DYE TEST RESULTS

- DYE TEST CONFIRMED
- DYE TEST UNCONFIRMED
- NO ACCESS
- CONNECTIONS OBTAINED FROM SITE PLANS


DAP = DYE APPLICATION POINT
DOP = DYE OBSERVATION POINT

--- UNKNOWN - ASSUMED CONNECTION
 --- DIRECT CONNECTION
 ○ DDS = DISAPPEARING DOWNSPOUT



CITY OF PORT HURON, MICHIGAN
 SEWER SEPARATION AND
 INFRASTRUCTURE IMPROVEMENTS
 7TH & 9TH STREET AREA
 PRIVATE SOURCE
 INVESTIGATION

FIGURE
15




NOTE:
828 LAPEER - UNITED
METHODIST CHURCH

DESIGNED:  TETRA TECH MPS
DATE: 10/25/00

- DYE TEST RESULTS**
- DYE TEST CONFIRMED
 - DYE TEST UNCONFIRMED
 - NO ACCESS
 - CONNECTIONS OBTAINED FROM SITE PLANS
- DAP = DYE APPLICATION POINT
DOP = DYE OBSERVATION POINT


- UNKNOWN - ASSUMED CONNECTION
- DIRECT CONNECTION
- DDS = DISAPPEARING DOWNSPOUT



CITY OF PORT HURON, MICHIGAN
SEWER SEPARATION AND
INFRASTRUCTURE IMPROVEMENTS
7TH & 9TH STREET AREA
PRIVATE SOURCE
INVESTIGATION

NOTE:

TMPS TO DYE TEST ALL STORM SYSTEMS TO DETERMINE CONNECTIONS. STORM LEAD TO BE PROVIDED ON 9TH ST. (PER MEETING MINUTES 11-29-01)



LAPEER AVE

930
BIG I CARPET FACTORY OUTLET

912
POLLOCK-RANDALL FUNERAL HOME

9TH STREET
PROPOSED STORM

DAP#1

DAP#2

DDP#1

DDP#2

DDS

DRIVEWAY DRAIN
SUMP PUMP

INTERNAL ROOF DRAINS ON PROPERTY

C.B.

C.B.

C.B.

C.B.

C.B.

C.B.

M.H.

DESIGNED:  TETRA TECH MPS

DATE: 10/25/00

DYE TEST RESULTS

- DYE TEST CONFIRMED
- DYE TEST UNCONFIRMED
- NO ACCESS
- CONNECTIONS OBTAINED FROM SITE PLANS

DAP = DYE APPLICATION POINT
DOP = DYE OBSERVATION POINT

----- UNKNOWN - ASSUMED CONNECTION


----- DIRECT CONNECTION

○ DDS = DISAPPEARING DOWNSPOUT

CITY OF PORT HURON, MICHIGAN
SEWER SEPARATION AND
INFRASTRUCTURE IMPROVEMENTS

7TH & 9TH STREET AREA
PRIVATE SOURCE
INVESTIGATION

FIGURE 17



DYE TEST LEGEND

- CONFIRMED
- NOT TESTED (TV TAPERS)
- UNCONFIRMED
- NO ACCESS



TETRA TECH MAPS

REV	DESCRIPTION	BY	DATE	CHKD
1				
2				
3				
4				
5				


DATE: 11/14/2018

CIVIL

MAP OF 7TH & 9TH STREET
DYE TESTING

DIVISION	CONTRACT	SHEET
		1 of 1

NOTE:
1229 7TH STREET --



THIS LINE NEEDS TO BE TELEVISED TO LOCATE WEST-END. FIELD CREW CHECK AGAIN FOR THIS LINE

UNION STREET


7TH STREET

719

711

1229

SMITH FUEL



TETRA TECH MPS

- DYE TEST UNCONFIRMED
- DYE TEST UNCONFIRMED
- NO ACCESS
- CONNECTIONS OBTAINED FROM SITE PLANS

DYE TEST RESULTS


- DAP = DYE APPLICATION POINT
- DOP = DYE OBSERVATION POINT
- UNKNOWN - ASSUMED CONNECTION
- DIRECT CONNECTION
- DDS = DISAPPEARING DOWNSPOUT



CITY OF PORT HURON, MICHIGAN
SEWER SEPARATION AND INFRASTRUCTURE IMPROVEMENTS
7TH & 9TH STREET AREA
PRIVATE SOURCE INVESTIGATION

DESIGNED: DATE: 07/18/05

NOTE:
1122 10TH STREET -



TETRA TECH MPS

DESIGNED: DATE: 07/18/05

- DYE TEST RESULTS**
- DYE TEST CONFIRMED
 - DYE TEST UNCONFIRMED
 - NO ACCESS CONNECTIONS
- DAP = DYE APPLICATION POINT
DOP = DYE OBSERVATION POINT
- UNKNOWN - ASSUMED CONNECTION
 - DIRECT CONNECTION
 - DDS = DISAPPEARING DOWNSPOUT



CITY OF PORT HURON, MICHIGAN
SEWER SEPARATION AND
INFRASTRUCTURE IMPROVEMENTS
7TH & 9TH STREET AREA
PRIVATE SOURCE
INVESTIGATION

FIGURE

APPENDIX A
Properties identified for dye testing

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix A

Properties Identified for Dye Testing

Street Name and No.	Inspect. Date	Site Access		Roof Drainage						Area Drainage			Basement		Cleanout		Possible Improper Source or Lead Connection	Comments/Notes		
		DA	NCH	DTC	IRD	ERD	DDS	DDG	MDS	BWWD	DWD	SWD	PD	CB	TD	Base-ment Flooding			History of Sump Pump Discharges on the Ground	External Cleanout
10TH ST	702	9/18/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	2	0	1	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	COMMERCIAL SITE. DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 997.
10TH ST	718	9/18/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	2	0	2	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	COMMERCIAL SITE. DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 997.
10TH ST	722	8/23/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 997. PIPES CLEANED 2X WITHIN THE PAST 5 YEARS.
10TH ST	726	8/23/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 997. PIPES CLEANED 2X WITHIN THE PAST 5 YEARS FOR ROOT REMOVAL.
10TH ST	812	8/23/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	5	0	5	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	COMBINED WITH 812.5 10TH ST. DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 997. 8/22/00 LEFT LETTER.
10TH ST	812.5	8/23/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>						<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	REFER TO 812 10TH ST.
10TH ST	814	9/18/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	2	0	2	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	9/19/00 NEIGHBOR ADVISES THAT HOME IS VACANT. 8/22/00 LEFT LETTER.

DA = Denied Access
NCH = No One Home
DTC = Dye Test Confirmed
IRD = Interior Roof Drain
ERD = Exterior Roof Drain

DDS = Disappearing Downspouts
DDG = Downspout Discharge on Ground
MDS = Missing Downspouts
JMWYD = Basement Window Weel Drain
DWD = Driveway Drain

SWD = Slatwell Drain
PD = Patio Drain
CB = Catch Basin
TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix A

Properties Identified for Dye Testing

Site Address	Site Access	Roof Drainage							Area Drainage				Basement	Sump Pump Discharges on the Ground	External Cleanout	Clean-out Cap Intact	Possible Improper Source or Lead Connection	Comments/Notes	
		DA	NOH	DTC	IRD	ERD	DDS	DDG	MDS	BWWD	DWD	SWD							PD
10TH ST 1008	10/9/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 16269 PIPES CLEANED EVERY SIX MONTHS. OCCUPANT ADMINISTERED DYE. 10/4/00 LEFT LETTER.
10TH ST 1020		<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO ONE HOME. 10/9/00, 10/4/00 AND 9/22/00 LEFT LETTER.
10TH ST 1022		<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO ONE HOME. 10/4/00 AND 9/22/00 LEFT LETTER. VACANT FOR SALE BY CENTURY 21 985-5490
10TH ST 1024	9/22/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	TWO APARTMENTS. DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 16269. TENANT ADMINISTERED DYE. NO ACCESS TO BASEMENT AND TENANT HAD NO KNOWLEDGE OF FLOODING HISTORY, ETC.
10TH ST 1208	9/12/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	COMMERCIAL SITE COMBINED WITH 946 COLURT ST. DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 16893. CHRISTEN BELLOWSHIP BOOKSTORE HOME AND BUSINESS ARE TIED TOGETHER. BOTH BUILDINGS WERE DYE TESTED.

DA = Banded Access
NOH = No One Home
DTC = Dye Test Confirmed
IRD = Interior Roof Drain
ERD = Exterior Roof Drain

DDS = Disappearing Downspouts
DDG = Downspout Discharge on Ground
MDS = Missing Downspouts
BWWD = Basement Window Well Drain
DWD = Downspout Drain

SWD = Stairwell Drain
PD = Patio Drain
CB = Catch Basin
TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix A

Properties Identified for Dye Testing

Site Address	Site Access	Roof Drainage	Area Drainage	Basement	Basement Sump Pump Dis- charges on the Ground	Cleanout	Clean- out Cap Intact	Possible Improper Lead Connection	Comments/Notes							
Street Name and No.	Inspect. Date	DA NOH	DTC	IRD	ERD	DDS	DDG	MDS	BWWD	DWD	SWD	PD	CB	TD		
10TH ST 1702	8/8/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	CITY PERFORMED FIRST DYE TEST WHICH RESULTED IN "OUT FRONT TO SEWER IN BLVD". RETEST DYE OBSERVED DISCHARGING FROM 4" EAST PIPE INTO MH 3802. THIS 4" PIPE IS A DIRECT LEAD FROM THE HOME TO THE MANHOLE.
10TH ST 1710	8/8/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 2925.
10TH ST 1714	7/27/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	2	0	2	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM WEST PIPE INTO MH 2925.
10TH ST 1814	8/8/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	6	0	6	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	CITY PERFORMED FIRST DYE TEST WITH RESULTS OF "SEWER ON DIVISION ST". RETEST DYE OBSERVED DISCHARGING FROM SOUTH PIPE INTO MH 7727.
10TH ST 1824	7/27/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 2424.
10TH ST 1904	4/4/00	<input checked="" type="checkbox"/>	<input type="checkbox"/>	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO ONE HOME. 7/27/00 LEFT LETTER.

DA = Denied Access
 NOH = No One Home
 DTC = Dye Test Confirmed
 IRD = Interior Roof Drain
 ERD = Exterior Roof Drain
 DDS = Disappearing Downspouts
 DDG = Downspout Discharge on Ground
 MDS = Missing Downspouts
 BWWD = Basement Window Well Drain
 DWD = Driveway Drain
 SWD = Sashwell Drain
 PD = Pado Drain
 CB = Catch Basin
 TD = Todd Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix A

Properties Identified for Dye Testing

Site Address	Site Access	Roof Drainage	Area Drainage	Basement	Sump Pump Discharges on the Ground	Cleanout	Clean-out Cap Intact	Possible Improper Source or Lead Connection	
10TH ST 1928 7/27/00	DA <input type="checkbox"/> NOH <input type="checkbox"/> DTC <input checked="" type="checkbox"/>	IRD <input type="checkbox"/> ERD <input type="checkbox"/> DBS <input type="checkbox"/> DDG <input type="checkbox"/> MDS <input type="checkbox"/>	BWWD <input type="checkbox"/> DWD <input type="checkbox"/> SWD <input type="checkbox"/> PD <input type="checkbox"/> CB <input type="checkbox"/> TD <input checked="" type="checkbox"/>	Base-ment <input type="checkbox"/>	History of Sump Flooding <input type="checkbox"/>	Pump on Ground <input type="checkbox"/>	External Cleanout <input type="checkbox"/>	Clean-out Intact <input type="checkbox"/>	<input checked="" type="checkbox"/> Possible Improper Source or Lead Connection
6TH ST 919 10/13/00	DA <input type="checkbox"/> NOH <input type="checkbox"/> DTC <input checked="" type="checkbox"/>	IRD <input type="checkbox"/> ERD <input type="checkbox"/> DBS <input type="checkbox"/> DDG <input type="checkbox"/> MDS <input type="checkbox"/>	BWWD <input type="checkbox"/> DWD <input type="checkbox"/> SWD <input type="checkbox"/> PD <input type="checkbox"/> CB <input type="checkbox"/> TD <input checked="" type="checkbox"/>	Base-ment <input type="checkbox"/>	History of Sump Flooding <input type="checkbox"/>	Pump on Ground <input type="checkbox"/>	External Cleanout <input type="checkbox"/>	Clean-out Intact <input type="checkbox"/>	<input checked="" type="checkbox"/> Possible Improper Source or Lead Connection
6TH ST 923 6/12/00	DA <input type="checkbox"/> NOH <input type="checkbox"/> DTC <input checked="" type="checkbox"/>	IRD <input type="checkbox"/> ERD <input type="checkbox"/> DBS <input type="checkbox"/> DDG <input type="checkbox"/> MDS <input type="checkbox"/>	BWWD <input type="checkbox"/> DWD <input type="checkbox"/> SWD <input type="checkbox"/> PD <input type="checkbox"/> CB <input type="checkbox"/> TD <input type="checkbox"/>	Base-ment <input type="checkbox"/>	History of Sump Flooding <input type="checkbox"/>	Pump on Ground <input type="checkbox"/>	External Cleanout <input type="checkbox"/>	Clean-out Intact <input type="checkbox"/>	<input checked="" type="checkbox"/> Possible Improper Source or Lead Connection

COMMERCIAL SITE. CITY PERFORMED FIRST DYE TEST WITH THE RESULT OF "BRANCKOFT ST. SEWER". RETEST DONE AND DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 1176. INFLOW INVESTIGATION PERFORMED AND FOUND THAT CATCH BASIN IS IN EXTREMELY POOR CONDITION, FILLED WITH DEBRIS UNKNOWN CONNECTION. CATCH BASIN APPEARS TO BE AN OLD FLOOR DRAIN FROM A RECENTLY DEMOLISHED PORTION OF THE BUILDING. GRATE DRAIN LOCATED NEXT TO THE NORTH SIDE OF BUILDING IS FILLED WITH DEBRIS, UNKNOWN CONNECTION. ADVISED OWNER OF POOR CONDITION OF CATCH BASIN.

COMMERCIAL SITE. CONTACTED AMERITECH SECURITY TO GAIN ACCESS WITH NO SUCCESS. CATCH BASIN LOCATED AT THE NORTH SIDE OF SITE. WEST WALL OF CATCH BASIN HAS A 6" LEAD WITH UNIDENTIFIED CONNECTION.

REFER TO 919 6TH ST.

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix A

Properties Identified for Dye Testing

Site Address	Site Access	Roof Drainage				Area Drainage				Basement		Cleanout	Possible Improper Source of Lead	Connection Comments/Notes								
Street Name and No.	Inspect. Date	DA	NOH	DTC	IRD	ERD	DDS	DDG	MDS	BMW	DWD	SWD	PD	CB	TD	History of Sump Pump Flooding	Sump Pump Discharges on the Ground	External Cleanout	Clean-out Cap Intact			
6TH ST	927	11/1/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	1	1	1	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 7868. SPOKE WITH PAUL AND SHIRLEE WHO ADVISE THAT SEVERAL YEARS AGO AND EVERYTHING HAD TO BE REDONE - ALL PLUMBING GOES TO SAME LEAD. DISAPPEARING DOWNSPOUT NEEDS TO BE CHECKED.
6TH ST	1029	11/7/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	14	0	14	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	CHURCH DAP #1 DYE OBSERVED DISCHARGING FROM THE NORTH PIPE INTO MH 1739. DAP #2 DYE OBSERVED DISCHARGING FROM THE NORTH PIPE INTO MH 1739. DAP #1 IS LOCATED IN POST-1930 SECTION OF BUILDING. DAP #2 IS LOCATED IN PRE-1930 SECTION OF BUILDING.
6TH ST	1115	9/19/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	MUSEUM COMBINED WITH 621 COURT ST. DYE OBSERVED DISCHARGING FROM THE SOUTHEAST PIPE INTO MH 17393.
6TH ST	1213	11/7/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	3	0	3	0	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	CHURCH DYE OBSERVED DISCHARGING FROM THE NORTH PIPE INTO MH 17019. ALL FACILITIES WERE PUT IN AT THE SAME TIME. STAIRWELL DRAINS IS FILLED WITH DEBRIS.

DA = Denied Access
 NOH = No One Home
 DTC = Dye Test Confirmed
 IRD = Interior Roof Drain
 ERD = Exterior Roof Drain
 DDS = Downspout Discharge on Ground
 DDG = Downspout Discharge on Ground
 MDS = Missing Downspouts
 BMWWD = Basement Window Wall Drain
 DWD = Downspout
 SWD = Stairwell Drain
 PD = Patio Drain
 CB = Catch Basin
 TD = Tidal Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix A

Properties Identified for Dye Testing

Site Address	Site Access	Roof Drainage	Area Drainage	Basement	Basement History of Sump Pump Flooding	Sump Pump Discharges on the Ground	Cleanout	Cleanout Intact	Possible Improper Source or Lead Connection	Comments/Notes
Street Name and No.	Inspect Date	DA NOH DTC	IRD ERD DDS DDG MDS	BWWD DWD SWD PD CB TD	Basement History of Sump Pump Flooding	Sump Pump Discharges on the Ground	Cleanout	Cleanout Intact	Possible Improper Source or Lead Connection	Comments/Notes
7TH ST 905	10/3/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0 4 1 3 0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	COMMERCIAL SITE COMBINED WITH 911 7TH ST. DYE TESTED BOTH SETS OF FACILITIES AND DYE WAS OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH17857. CATCH BASINS AND DISAPPEARING DOWNSPOUT NEEDS TO BE CHECKED.
7TH ST 911	10/3/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	REFER TO 905 7TH ST.
7TH ST 919	10/5/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	REFER TO 721 PINE ST.

DA = Denial Access
 NOH = No One Home
 DTC = Dye Test Confirmed
 IRD = Interior Roof Drain
 ERD = Exterior Roof Drain
 DDS = Disappearing Downspouts
 DDG = Downspout Discharge on Ground
 MDS = Missing Downspouts
 BWWD = Basement Window Well Drain
 DWD = Driveway Drain
 SWD = Stairwell Drain
 PD = Patio Drain
 CB = Catch Basin
 TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix A

Properties Identified for Dye Testing

Street Name and No.	Inspect. Date	DA	NOH	DTC	IRD	ERD	DDS	DDG	MDS	BWWD	DWD	SWD	PD	CB	TD	Basement	History of Sump	Basement Flooding	Sump Pump Discharges on the Ground	Cleanout	External out Cap Intact	Possible Improper Source or Lead Connection	Comments/Notes	
7TH ST	1016	11/20/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	1	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	4	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	A TOTAL OF 6 DYE TESTS WERE PERFORMED. DAP #1 - #4 DYE OBSERVED DISCHARGING FROM THE NORTH PIPE INTO MAH 17393. DAP #5, #6 DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MAH LOCATED IN PARKING LOT AT SOUTHEAST SHS OF SITE. CATCH BASINS ON EAST PROPERTY CONNECT, WITH ONE CATCH BASIN HAVING AN EAST LEAD WITH UNKNOWN CONNECTION. 2 CATCH BASINS (WITH MULTIPLE LEADS) LOCATED ON THE SOUTH SIDE OF SITE. CONNECT AND FLOWS TO MAH ON 7TH ST. 2 CATCH BASINS (WITH MULTIPLE LEADS) AT NORTH SIDE OF PROPERTY CONNECT TO MAH ON 7TH ST.
7TH ST	1103	9/28/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>						<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>								<input type="checkbox"/>	REFER TO 73 COURT ST.
7TH ST	1205	6/9/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	VACANT AND UNDER RENOVATION.

DA = Banked Access
NOH = No One Home
DTC = Dye Test Confirmed
IRD = Interior Roof Drain
ERD = Exterior Roof Drain
DDS = Disappearing Downspouts
DDG = Downspout Discharge on Ground
MDS = Missing Downspouts
BWWD = Basement Window Well Drain
DWD = Driveway Drain
SWD = Stairwell Drain
PD = Patio Drain
CB = Catch Basin
TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix A

Properties Identified for Dye Testing

Site Address	Site Access	Roof Drainage	Area Drainage	Basement	Sump Pump Discharges on the Ground	Cleanout	Clean-out Cap Intact	Possible Improper Source or Lead Connection	Comments/Notes	
7TH ST 1229	Inspect: DA <input type="checkbox"/> NOH <input type="checkbox"/> DTC <input checked="" type="checkbox"/>	IRD <input type="checkbox"/> ERD <input type="checkbox"/> DDS <input type="checkbox"/> DDG <input type="checkbox"/> MDS <input type="checkbox"/>	BWWD <input type="checkbox"/> DWD <input type="checkbox"/> SWD <input type="checkbox"/> PD <input type="checkbox"/> CB <input type="checkbox"/> TD <input type="checkbox"/>	Base-ment <input type="checkbox"/>	History of Sump Pump Flooding <input type="checkbox"/>	History of Sump Pump on the Ground <input type="checkbox"/>	External Cleanout <input checked="" type="checkbox"/>	Clean-out Cap Intact <input checked="" type="checkbox"/>	Possible Improper Source or Lead Connection <input checked="" type="checkbox"/>	COMMERCIAL SITE. DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 6436. PIPES HAVE BEEN CLEANED IN WITHIN THE PAST 5 YEARS FOR ROOT REMOVAL. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.
7TH ST 1230	9/19/00 <input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	9	0	9	0	<input checked="" type="checkbox"/>	COMMERCIAL SITE. DYE OBSERVED DISCHARGING FROM THE EAST PIPE INTO MH 6436.
7TH ST 1304	6/9/00 <input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	5	2	5	0	<input type="checkbox"/>	APARTMENTS. 9/19/00 AND 8/10/00 LEFT LETTER. TENANT DENIED ACCESS. DISCONNECTED. DISAPPEARING DOWNSPOUT IS NOT PROPERLY CAPPED.
7TH ST 1305	6/9/00 <input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	0	0	0	0	0	<input type="checkbox"/>	APARTMENTS. 9/19/00 AND 8/10/00 LEFT LETTER. 9/19/00 ALTHOUGH APARTMENT WAS OCCUPIED, NO ONE WOULD ANSWER THE DOOR.
7TH ST 1331	10/13/00 <input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	9	11	1	0	<input checked="" type="checkbox"/>	CHURCH BUILT IN 1889. INSPECTORS CALLED 985-9616 TO GAIN ACCESS TO CHURCH. DYE TEST UNCONFIRMED IN MH 6491, MH 6435 AND MH 6436. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.

DA = Denied Access
 NOH = No One Home
 DTC = Dye Test Confirmed
 IRD = Interior Roof Drain
 ERD = Exterior Roof Drain
 DDS = Disappearing Downspouts
 DDG = Downspout Discharge on Ground
 MDS = Missing Downspouts
 BWWD = Basement Window Well Drain
 DWD = Driveway Drain
 SWD = Stairwell Drain
 PD = Patio Drain
 CB = Catch Basin
 TD = Total Drain

**City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix A**

Properties Identified for Dye Testing

Street Name and No.	Inspect. Date	Site Access					Roof Drainage					Area Drainage					Basement		Sump Pump Discharges on the Ground	External Cleanout	Clean-out Cap Intact	Possible Improper Source or Lead Connection	Comments/Notes		
		DA	NOH	DTC	IRD	ERD	DDS	DDG	MDS	BWWD	DWD	SWD	PD	CB	TD	ment	History of Flooding Pump								
7TH ST 1402	8/14/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	0	4	0	4	0	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE EAST PIPE INTO MH 6491. PIPES CLEANED YEARLY
7TH ST 1408	6/12/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	5	2	3	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	APARTMENTS. NO ONE HOME. 10/300, 8/8/00 AND 8/24/00 LEFT LETTER. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED	
7TH ST 1414	10/13/00	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	3	0	3	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	2 APARTMENTS CURRENTLY VACANT. DYE TEST UNCONFIRMED IN MH 6491. ALL NEW PLUMBING 2/00. 10/300, 8/18/00 AND 8/24/00 LEFT LETTER.	
7TH ST 1420	8/24/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 6315. PIPES HAVE BEEN CLEANED OUT TX WITHIN THE PAST 5 YEARS. 8/18/00 LEFT LETTER.	
7TH ST 1422	8/18/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	0	1	0	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 6315. RESIDENTS MOVED INTO THE HOME APPROXIMATELY 7/00	

DA = Denied Access
NOH = No One Home
DTC = Dye Test Confirmed
IRD = Interior Roof Drain
ERD = Exterior Roof Drain

DDS = Disappearing Downspouts
DDG = Downspout Discharge on Ground
MDS = Missing Downspouts
BWWD = Basement Window Wall Drain
DWD = Driveway Drain

SWD = Stairwell Drain
PD = Patio Drain
CB = Catch Basin
TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix A

Properties Identified for Dye Testing

Street Name and No.	Inspect Date	DA	NOH	DTC	Roof Drainage					Area Drainage					Basement	Sump Pump Discharges on the Ground	External Cleanout	Clean-out Cap Intact	Possible Improper Lead Connection	Comments/Notes		
					DDS	DDG	DDG	MDS	BWWD	DWD	SWD	PD	CB	TD							DDS	DDG
7TH ST	8/24/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	6	2	4	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 6315. NEW SEWER LEAD INSTALLED IN 1998. PIPES CLEANED EVERY SIX MONTHS FOR ROOT REMOVAL. 8/18/00 LEFT LETTER DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.
7TH ST	8/17/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE EAST PIPE INTO MH 4690. PIPES CLEANED YEARLY. 8/10/00 LEFT LETTER.
7TH ST	8/10/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 4690. PIPES CLEANED 3X EVERY YEAR.
7TH ST	8/18/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	5	5	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 4689. 8/10/00 LEFT LETTER. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.
7TH ST	8/10/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 4689.

DA = Denied Access
 NOH = No One Home
 DTC = Dye Test Confirmed
 IRD = Interior Roof Drain
 ERD = Exterior Roof Drain
 DDS = Disappearing Downspouts
 DDG = Downspout Discharge on Ground
 MDS = Missing Downspouts
 BWWD = Basement Window Weir Drain
 DWD = Driveway Drain
 SWD = Stairwell Drain
 PD = Patio Drain
 CB = Catch Basin
 TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix A

Properties Identified for Dye Testing

Site Address	Site Access	Roof Drainage	Area Drainage	Basement	Sump Pump Discharges on the Ground	Cleanout	Possible Improper Source or Lead Connection	Comments/Notes								
Street Name and No.	Inspect. Date	DA NOH DTC	IRD ERD DDS DDG MDS	BWWD DWD SWD PD CB TD	Basement Flooding	History of Sump Pump	External Cleanout	Clean out Cap Intact								
8TH ST	825	8/22/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	4	1	3	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE SOUTHEAST PIPE INTO MH 15328. DISAPPEARING DOWNSPOUT NEEDS TO BE CHECKED.
8TH ST	909	9/22/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	3	0	3	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 15328 MH 15897 WAS CHECKED NEGATIVE FOR DYE. RESIDENT HAS BEEN IN THE HOME 50 YEARS AND SAYS LEAD GOES TO ALLEY SEWER. 9/19/00, 8/23/00 AND 8/22/00 LEFT LETTER.
8TH ST	913	8/22/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	3	1	2	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE NORTH PIPE INTO MH 15897. DISAPPEARING DOWNSPOUT NRBDS TO BE CHECKED.
8TH ST	915	8/22/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	1	0	0	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE NORTH PIPE INTO MH 15897. RESIDENTS HAVE BEEN IN HOME SINCE 1998.
8TH ST	920	10/5/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>					<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	REFER TO 721 PINE ST.

DA = Limited Access
NOH = No One Home
DTC = Dye Test Confirmed
IRD = Interior Roof Drain
ERD = Exterior Roof Drain
DDS = Disappearing Downspouts
DDG = Downspout Discharge on Ground
MDS = Missing Downspouts
BWWD = Basement Window Weir Drain
DWD = Driveway Drain
SWD = Stairwell Drain
PD = Patio Drain
CB = Catch Basin
TD = Total Drain

City of Port Huron
7th and 9th Street
**Dye Testing and Private Property
Inflow Source Investigation**
Appendix A

Properties Identified for Dye Testing

Site Address	Site Access	Roof Drainage	Area Drainage	Basement	Basement	Sump	Cleanout	Clean-	Possible	Connection Comments/Notes
Street Name and No.	Inspect. Date	DA NOH DTC	ERD ERD DDS DDG MDS	BWWD DWD SWD PD CB TD	ment	History of Sump Pump on the Ground	External Cleanout	out Cap Intact	Improper Source or Lead	
8TH ST 1012	9/27/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0 1 0 1 0	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	APARTMENT DYE OBSERVED DISCHARGING FROM THE NORTHEAST BOTTOM PIPE INTO MH 7154 9/20/00 AND 8/9/00 LEFT LETTER
8TH ST 1014	9/27/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0 0 0 0 0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	APARTMENTS DYE OBSERVED DISCHARGING FROM THE EAST 6" PVC PIPE INTO MH 7154 9/20/00 AND 8/9/00 LEFT LETTER
8TH ST 1020	9/20/00	<input type="checkbox"/>	<input type="checkbox"/>	0 2 0 3 0	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	APARTMENT FIRST DYE TEST 8/9/00 UNCONFIRMED. RETEST UNCONFIRMED AT MH 7154
8TH ST 1024	5/18/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0 4 0 4 0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	COMBINED WITH 1026 8TH ST. NO ONE HOME. 10/11/00 LEFT LETTER
8TH ST 1026	8/21/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0 3 0 5 0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	REFER TO 1024 8TH ST.
8TH ST 1214	9/28/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0 3 0 5 0	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 17584 LEAD TIES IN WITH THE HOME ON THE CORNER OF 8TH ST. AND COURT ST. AND THEN CONTINUES TO THE SEWER LINE ON COURT ST. PIPES CLEANED YEARLY. 9/28/00 LEFT LETTER

DA = Denied Access
NOH = No One Home
DTC = Dye Test Confirmed
ERD = Exterior Roof Drain

DDS = Disappearing Downspouts
DDG = Downspout Discharge on Ground
MDS = Missing Downspouts
BWWD = Basement Window Well Drain
DWD = Driveway Drain

SWD = Stairwell Drain
PD = Patio Drain
CB = Catch Basin
TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix A

Properties Identified for Dye Testing

Site Address	Site Access	Roof Drainage					Area Drainage					Basement		Sump Pump Discharges on the Ground	External Cleanout	Clean-out Cap Intact	Possible Improper Source or Lead Connection	Comments/Notes	
		DA	NOH	DTC	IRD	ERD	DDS	DDG	MDS	BWWD	DWD	SWD	PD						CB
8TH ST 1218 9/28/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	APARTMENTS, DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 6436 9/28/00 LEFT LETTER
8TH ST 1225 10/13/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	3	4	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE EAST PIPE INTO MH 16893. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.
8TH ST 1302 8/10/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	3	0	3	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	COMBINED WITH 1304 8TH ST. DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 6436.
8TH ST 1303 5/24/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	2	0	0	2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO ONE HOME. 10/13/00 AND 9/13/00 LEFT LETTER.
8TH ST 1304 5/24/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>						<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	REFER TO 1302 8TH ST.
8TH ST 1307 9/28/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE EAST PIPE INTO MH 6271 9/13/00 LEFT LETTER.

DA = Denial Access
NOH = No One Home
DTC = Dye Test Confirmed
IRD = Interior Roof Drain
ERD = Exterior Roof Drain

DDS = Disappearing Downspouts
DDG = Downspout Discharge on Ground
MDS = Missing Downspouts
BWWD = Basement Window Well Drain
DWD = Driveway Drain

SWD = Stairwell Drain
PD = Patio Drain
CB = Catch Basin
TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix A

Properties Identified for Dye Testing

Site Address	Site Access	Roof Drainage	Area Drainage	Basement	Sump Pump Discharges on the Ground	Cleanout	Clean-out Cap Intact	Possible Improper Lead Connection	Comments/Notes
Street Name and No.	Inspect Date	DA NOH DTC	IRD ERD DDS DDG MDS	BWWD DWD SWD PD CB TD	Basement Flooding Pump	History of Sump Pump	External Cleanout	Connection	
8TH ST 1311	9/13/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0 0 0 0 0	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE EAST PIPE INTO MH 6271 SLIGHT FLOODING IN BASEMENT WHEN IT RAINS
8TH ST 1322	8/18/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0 1 0 1 0	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE NORTHEAST PIPE INTO MH 6728. RESIDENTS HAVE BEEN IN THIS HOME SINCE 11/99.
8TH ST 1326	8/18/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0 0 0 0 0	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE SOUTHEAST PIPE INTO MH 6728
8TH ST 1330	9/6/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0 2 1 1 0	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 6491. MH 5244 WAS NEGATIVE FOR DYE. 8/18/00 LEFT LETTER FRONT DISAPPEARING DOWNSPOUT NEEDS TO BE CHECKED.
8TH ST 1418	8/18/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0 6 1 5 0	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE NORTHEAST PIPE INTO MH 5312. PIPES ARE CLEANED 3X - 4X PER YEAR FOR ROOT REMOVAL. DISAPPEARING DOWNSPOUT NEEDS TO BE CHECKED.
8TH ST 1502	8/21/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	REFER TO 740 WHITE ST.

DA = Denied Access
 NOH = No One Home
 DTC = Dye Test Confirmed
 IRD = Interior Roof Drain
 ERD = Exterior Roof Drain
 DDS = Downspout Discharge on Ground
 DDG = Downspout Discharge on Ground
 MDS = Missing Downspouts
 BWWD = Basement Window Wall Drain
 DWD = Driveway Drain
 SWD = Stairwell Drain
 PD = Patio Drain
 CB = Catch Basin
 TD = Total Drain

City of Port Huron
7th and 9th Street
**Dye Testing and Private Property
Inflow Source Investigation**
Appendix A

Properties Identified for Dye Testing

Street Name and No.	Inspect Date	Site Access	Roof Drainage							Area Drainage				Basement	Sump Pump Discharges on the Ground	External Cleanout	Clean-out Cap Intact	Possible Improper Source or Lead Connection	Comments/Notes		
			DA	NOH	DTC	IRD	ERD	DDS	DDG	MDS	BWWD	DWD	SWD							PD	CB
8TH ST	1508	8/18/00	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	1	0	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	VACANT FOR A YEAR. SITE IS UNDER RENOVATIONS AND THERE IS NO WATER AT THIS TIME.
8TH ST	1523	9/14/00	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	1	0	3	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	VACANT SITE COMBINED WITH 803 GRSWOLD ST.	
8TH ST	1524	8/9/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	0	1	5	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	COMBINED WITH 735 GRSWOLD ST. DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 3791. UNUSED DISAPPEARING DOWNSPOUT NOT CAPPED.	
8TH ST	1609	10/10/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	0	0	0	0	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE EAST PIPE INTO MH 3879. 10/4/00 AND 9/25/00 LEFT LETTER. BASEMENT WINDOW WELL DRAIN NEEDS TO BE CHECKED.	
8TH ST	1611	5/25/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO ONE HOME. 10/4/00 AND 9/25/00 LEFT LETTER. HOME APPEARS VACANT.	
8TH ST	1615	5/25/00	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	9/21/00 BROKE WITH OWNER. HOME IS BEING RENOVATED AND THERE IS NO WATER SERVICE.	

DA = Denied Access
NOH = No One Home
DTC = Dye Test Confirmed
IRD = Interior Roof Drain
ERD = Exterior Roof Drain
DDS = Disappearing Downspouts
DDG = Downspout Discharge on Ground
MDS = Missing Downspouts
BWWD = Basement Window Well Drain
DWD = Driveway Drain
SWD = Stairwell Drain
PD = Patio Drain
CB = Catch Basin
TD = Toilet Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix A

Properties Identified for Dye Testing

Street Name and No.	Inspect Date	DA	NOH	DTC	Roof Drainage				IRD	ERD	DDS	DDG	MDS	Area Drainage				Sump Pump Discharges on the Ground	History of Flooding	Basement Pump	Cleanout	External out	Clean-out Cap Intact	Possible Improper Source or Lead Connection	Comments/Notes	
					DDG	MDS	DDG	MDS						PD	CB	TD	Basement									Basement
8TH ST 1616	10/9/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE EAST PIPE INTO MH 4333 VIA A DIRECT LEAD. 10/4/00 LEFT LETTER
8TH ST 1622	10/10/00	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	APARTMENTS. UNCONFIRMED IN MH 4229, MH 4230, MH 428, MH 4265 AND MH 4333. OCCUPANT DIRECTED TESTER TO A COMMUNITY FACILITY AND THEN LEFT. UNABLE TO ASK ANY QUESTIONS.
8TH ST 1623	9/25/00	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	UNCONFIRMED IN MH 2879.
8TH ST 1625	5/25/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO ONE HOME. 10/10/00 LEFT LETTER.
8TH ST 1704	5/25/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO ONE HOME. 10/9/00, 10/3/00 AND 9/21/00 LEFT LETTER.
8TH ST 1708	9/21/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE NORTH PIPE INTO MH 2373.
8TH ST 1714	10/3/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE NORTH PIPE INTO MH 2373 9/26/00 AND 9/21/00 LEFT LETTER.

DA = Denied Access
 NOH = No One Home
 DTC = Dye Test Confirmed
 HD = Interior Roof Drain
 ERD = Exterior Roof Drain
 DDG = Downspout Discharge on Ground
 MDS = Missing Downspouts
 BWWD = Basement Window Void Drain
 DWD = Driveway Drain
 SVD = Shallow Drain
 PD = Patio Drain
 CB = Catch Basin
 TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix A

Properties Identified for Dye Testing

Street Name and No.	Inspect Date	Site Access		Roof Drainage						Basement				Cleanout		Possible Improper Source or Lead Connection	Comments/Notes							
		DA	NOH	DTC	IRD	ERD	DDS	DDG	MDS	BWWD	DWD	SWD	PD	CB	TD			Base-ment	History of Sump Pump Discharges on the Ground	Flooding	Pump	External Cleanout	Cap Intact	
8TH ST	1718	5/25/00	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO ONE HOME. 10/3/00, 9/26/00 AND 9/21/00 LEFT LETTER.
8TH ST	1803	10/25/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	0	3	0	3	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO ONE HOME.
9TH ST	819	8/23/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	1	0	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	COMBINED WITH 819 S 9TH ST. DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MHI 15328.
9TH ST	911	8/23/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	REFER TO 819 9TH ST.
9TH ST	837	8/15/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MHI 15328. OCCUPANTS HAVE ONLY BEEN IN HOME SINCE 8/10/00. 8/15/00 LEFT LETTER.
9TH ST	911	8/21/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	3	0	3	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MHI 15328.
9TH ST	915	8/21/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MHI 16110. OCCUPANTS HAVE BEEN IN HOME SINCE 1999. 8/21/00 LEFT LETTER.

DA = Beaded Access
 NOH = No One Home
 DTC = Dye Test Confirmed
 IRD = Interior Roof Drain
 ERD = Exterior Roof Drain
 DDS = Disappearing Downspouts
 DDG = Downspout Discharge on Ground
 MDS = Missing Downspouts
 BWWD = Basement Window Well Drain
 DWD = Downspout Drain
 SWD = Stairwell Drain
 PD = Patio Drain
 CB = Catch Basin
 TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix A

Properties Identified for Dye Testing

Street Name and No.	Inspect Date	Site Access		Roof Drainage						Area Drainage			Basement		Sump Pump Discharges on the Ground	External Cleanout	Clean-out Cap Intact	Possible Improper Source or Lead Connection	Comments/Notes	
		DA	NOH	DTC	IRD	ERD	DDS	DDG	MDS	BWWD	DWD	SWD	PD	CB						TD
9TH ST 919	8/21/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH16110
9TH ST 925	8/21/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 16110 PIPES CLEANED EVERY SIX MONTHS. BASEMENT HAS FLOODED 4X SINCE 1900
9TH ST 927	8/15/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	REFER TO 903 PINE ST.
9TH ST 1002	8/15/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	REFER TO 832 PINE ST.
9TH ST 1015	8/25/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 16269
9TH ST 1021	9/21/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 16269. 9/11/00 AND 8/25/00 LEFT LETTER
9TH ST 1022	9/11/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 16269. 8/25/00 LEFT LETTER
9TH ST 1110	8/14/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	REFER TO 838 WALL ST.

DA = Banked Access
 NOH = No One Home
 DTC = Dye Test Confirmed
 IRD = Interior Roof Drain
 ERD = Exterior Roof Drain
 DDS = Disappearing Downspouts
 DDG = Downspout Discharge on Ground
 MDS = Missing Downspouts
 BWWD = Basement Window Well Drain
 DWD = Driveway Drain
 SWD = Stairwell Drain
 PD = Patio Drain
 CB = Catch Basin
 TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix A

Properties Identified for Dye Testing

Street Name and No.	Inspect Date	Roof Drainage					Area Drainage					Basement		Sump Pump Discharges on the Ground	External Cleanout Intact	Possible Imptoper Source of Lead Connection	Comments/Notes		
		DA	NOH	DTC	IRD	ERD	DDS	DDG	MDS	BWWD	DWD	SWD	PD					CB	TD
9TH ST 1111	8/14/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	REFER TO 904 WALL ST.
9TH ST 1215	8/25/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 16893 OCCUPANTS HAVE BEEN IN THE HOME SINCE 10/00 8/25/00 LEFT LETTER.
9TH ST 1217	8/25/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 16893 PIPES CLEANED YEARLY FOR ROOT REMOVAL. 8/25/00 LEFT LETTER.
9TH ST 1218	8/25/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE EAST PIPE INTO MH 16893
9TH ST 1219	9/20/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 16893 9/13/00 LEFT LETTER.
9TH ST 1227	8/11/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	REFER TO 905 UNION ST.
9TH ST 1310	9/13/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 16947
9TH ST 1315	5/23/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO ONE HOME 10/9/00, 10/3/00 AND 9/13/00 LEFT LETTER.

BA = Banded Access
 NOH = No One Home
 DTC = Dye Test Confirmed
 IRD = Interior Roof Drain
 ERD = Exterior Roof Drain
 DDS = Disappearing Downspouts
 DDG = Downspout Discharge on Ground
 MDS = Missing Downspouts
 BWWD = Basement Windows Vial Drain
 DWD = Driveway Drain
 SWD = Stairwell Drain
 PD = Patio Drain
 CB = Catch Basin
 TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix A

Properties Identified for Dye Testing

Street Name and No.	Inspect. Date	Site Access		Roof Drainage					Area Drainage			Basement		Sump Pump Discharges on the Ground	History of Flooding	Basement Pump	External Cleanup	Clean-out Cap Intact	Possible Improper Source or Lead Connection	Comments/Notes	
		DA	NOH	DTC	IPD	ERD	DDS	DDG	MDS	BWWD	DWD	SWD	PD								CB
9TH ST	1316	10/3/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE EAST PIPE INTO MH 6271. 9/13/00 LEFT LETTER.
9TH ST	1317	9/13/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 6271.
9TH ST	1318	9/13/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	3	0	3	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE EAST PIPE INTO MH 6271.
9TH ST	1319	9/13/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	2	0	0	2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 6271.
9TH ST	1504	5/26/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO ORB HOME. 10/9/00, 10/3/00 AND 8/11/00 LEFT LETTER.
9TH ST	1512	9/14/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	2	1	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE EAST PIPE INTO MH 5444. DISAPPEARING DOWNSPOUT NEED TO BE CHECKED.
9TH ST	1514	9/14/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE EAST PIPE INTO MH 5444.
9TH ST	1630	9/25/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	2	0	2	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE EAST PIPE INTO MH 2879.

DA = Denied Access
NOH = No One Home
DTC = Dye Test Confirmed
IPD = Interior Roof Drain
ERD = Exterior Roof Drain

DDS = Disappearing Downspouts
DDG = Downspout Discharge on Ground
MDS = Missing Downspouts
BWWD = Basement Window Well Drain
DYPD = Drywey Drain

SWD = Stairwell Drain
PD = Pado Drain
CB = Catch Basin
TD = Todd Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix A

Properties Identified for Dye Testing

Site Address	Site Access	Roof Drainage	Area Drainage	Basement	Sump Pump Discharges on the Ground	Cleanout	Clean-out Cap Intact	Possible Improper Source or Lead Connection	Comments/Notes
Street Name and No.	Inspect. Date	DA NOH DTC	IRD ERD DDS DDG MDS	BWWD DWD SWD PD CB TD	Base-ment Flooding	History of Sump Pump	External Cleanout		
9TH ST 1801	10/26/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0 5 0 5 0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 999. PIPES CLEANED YEARLY.
9TH ST 1809	10/26/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0 0 0 0 0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 999.
9TH ST 1813	10/26/00	<input checked="" type="checkbox"/>	<input type="checkbox"/>	0 0 0 0 0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO ONE HOME.
9TH ST 1815	10/26/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0 0 0 0 0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 999.
9TH ST 1819	10/26/00	<input checked="" type="checkbox"/>	<input type="checkbox"/>	0 3 0 3 0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	NO ONE HOME. EXTERNAL CLEANOUT CAP NOT PROPERLY CAPPED.
CHESTNUT ST 517	9/19/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	REFER TO 1394 6TH ST.
CHESTNUT ST 605	6/6/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0 4 0 4 0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	10/10/00 AND 9/19/00 LEFT LETTER. HOME APPEARS VACANT.
CHESTNUT ST 611	9/19/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0 2 0 2 0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE SOUTHEAST PIPE INTO MH 17027 PIPES CLEANED IN 8/00 FOR ROOT REMOVAL.

DA = Dead End Access
NOH = No One Home
DTC = Dye Test Confirmed
IRD = Interior Roof Drain
ERD = Exterior Roof Drain

DDS = Disappearing Downspouts
DDG = Downspout Discharge on Ground
MDS = Missing Downspouts
BWWD = Basement Window Well Drain
DWD = Driveway Drain

SWD = Stairwell Drain
PD = Patio Drain
CB = Catch Basin
TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix A

Properties Identified for Dye Testing

Site Address	Site Access	Roof Drainage	Area Drainage	Basement	Sump Pump Discharges on the Ground	Cleanout	Possible Improper Source or Lead Connection	Comments/Notes	
Street Name and No.	Inspect Date	DA NOH DTC	IRD ERD DDS DDC MDS	BWWD DWD SWD PD CB TD	Basement Flooding Pump	History of Sump Flooding	External Cleanout Intact		
COURT ST 805	9/13/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0 4 4 0 0	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	CHURCH DYE OBSERVED DISCHARGING FROM THE EAST PIPE INTO MH 6271. MR. CAMPBELL, FROM CHURCH, INDICATED THAT THE DISAPPEARING DOWNSPOUTS ARE CONNECTED TO THE SANITARY LEAD. THIS IS AS SO POSSIBLE Y THE CASE WITH THE BASEMENT WINDOW WELL DRAINS.
COURT ST 621	9/19/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	REFER TO 1115 6TH ST.
COURT ST 624	9/19/00	<input type="checkbox"/>	<input type="checkbox"/>	0 1 0 1 0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	UNCONFIRMED IN MH 17019. PIPES CLEANED YEARLY FOR ROOT REMOVAL.
COURT ST 715	9/28/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	REFER TO 723 COURT ST.

DA = Double Access
NOH = No One Home
DTC = Dye Test Confirmed
IRD = Interior Roof Drain
ERD = Exterior Roof Drain

DDS = Disappearing Downspouts
DDC = Downspout Discharge on Ground
MDS = Missing Downspouts
BWWD = Basement Window Well Drain
DWD = Driveway Drain

SWD = Stairwell Drain
PD = Patio Drain
CB = Catch Basin
TD = Tidal Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix A

Properties Identified for Dye Testing

Site Address	Site Access	Roof Drainage	Area Drainage	Basement	Sump Pump Discharges on the Ground	Cleanout	Possible Improper Source or Lead Connection	Comments/Notes	
COURT ST 723	9/28/00 <input type="checkbox"/>	DA <input type="checkbox"/> NOH <input type="checkbox"/> DTC <input checked="" type="checkbox"/>	IRD <input type="checkbox"/> ERD <input type="checkbox"/> DDS <input type="checkbox"/> DDG <input type="checkbox"/> MDS <input type="checkbox"/>	BWWD <input type="checkbox"/> DWD <input type="checkbox"/> SWD <input type="checkbox"/> PD <input type="checkbox"/> CB <input type="checkbox"/> TD <input type="checkbox"/>	Base-ment <input type="checkbox"/>	History of Sump Pump Flooding <input type="checkbox"/>	External Cleanout <input type="checkbox"/>	Intact <input type="checkbox"/>	CHURCH COMBINED WITH 715 COURT ST., 103 7TH ST. DYE ADMINISTERED TO FACILITY LOCATED AT THE EAST SIDE OF THE BUILDING AND DYE WAS OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 17686. DYE ADMINISTERED TO FACILITY LOCATED AT THE WEST SIDE OF THE BUILDING AND DYE WAS OBSERVED DISCHARGING FROM THE NORTH PIPE INTO MH 17584. DYE ADMINISTERED TO FACILITY LOCATED AT THE SOUTH SIDE OF THE BUILDING AND DYE WAS OBSERVED DISCHARGING FROM THE NORTH PIPE INTO MH 17584.
COURT ST 740	8/15/00 <input checked="" type="checkbox"/>	<input type="checkbox"/>	0 <input type="checkbox"/> 2 <input type="checkbox"/> 0 <input type="checkbox"/> 2 <input type="checkbox"/> 0 <input type="checkbox"/>	0 <input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	UNABLE TO DYE TEST BECAUSE WATER WAS SHOT OFF 8/16/00. PIPES CLEANED EVERY SIX MONTHS FOR ROOT REMOVAL. 8/15/00 LEFT LETTER.
COURT ST 801	6/1/00 <input checked="" type="checkbox"/>	<input type="checkbox"/>	0 <input type="checkbox"/> 4 <input type="checkbox"/> 3 <input type="checkbox"/> 1 <input type="checkbox"/> 0 <input type="checkbox"/>	0 <input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	NO ONE HOME. 9/22/00, 8/17/00 AND 8/10/00 LEFT LETTER. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.
COURT ST 804	6/1/00 <input checked="" type="checkbox"/>	<input type="checkbox"/>	0 <input type="checkbox"/> 2 <input type="checkbox"/> 0 <input type="checkbox"/> 2 <input type="checkbox"/> 0 <input type="checkbox"/>	0 <input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	4 APARTMENTS. NO ONE HOME. 10/11/00, 8/16/00 AND 8/15/00 LEFT LETTER.

DA = Dated Access
 NOH = No One Home
 DTC = Dye Test Confirmed
 IRD = Interior Roof Drain
 ERD = Exterior Roof Drain
 DDS = Disappearing Downspouts
 DDG = Downspout Discharge on Ground
 MDS = Missing Downspouts
 BWWD = Basement Window Weir Drain
 DWD = Driveway Drain
 SWD = Stairwell Drain
 PD = Patio Drain
 CB = Catch Basin
 TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix A

Properties Identified for Dye Testing

Site Address	Site Access	Root Drainage					Area Drainage					Basement		Cleanout	Possible Improper Source or Lead Connection	Comments/Notes						
Street Name and No.	Inspect. Date	DA	NOH	DTC	IRD	ERD	DBS	DDG	MDS	BWWD	DWD	SWD	PD	CB	TD	Basement Flooding	History of Sump Pump on the Ground	External Cleanout	Clean-out Cap Intact			
COURT ST 835	8/1/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	6	0	6	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 16584
COURT ST 838	8/1/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	1	0	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 16873 PIPES CLEANED 1X-2X PER YEAR FOR THE PAST 5 YEARS.
COURT ST 902	8/1/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	3	0	3	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM SOUTH PIPE INTO MH 16873. PIPES CLEANED 1X WITHIN THE PAST FIVE YEARS FOR ROOT REMOVAL.
COURT ST 903	6/2/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	0	4	4	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	CHURCH BUILDING. NO ONE HOME. 10/9/99, 10/4/00 AND 9/22/00 LFT LETTER. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.
COURT ST 910	8/25/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	2	0	2	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 16893. PIPES CLEANED 1X PER YEAR.
COURT ST 916	8/25/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 16893.

DA = Denied Access
NOH = No One Home
DTC = Dye Test Confirmed
IRD = Interior Roof Drain
EKD = Exterior Roof Drain

DDS = Disappearing Downspouts
DDG = Downspout Discharge on Ground
MDS = Missing Downspouts
BWWVD = Basement Windows With Drain
DWD = Downspout Drain

SWD = Stairwell Drain
PD = Patio Drain
CB = Catch Basin
TD = Total Drain

City of Port Huron
7th and 9th Street
**Dye Testing and Private Property
Inflow Source Investigation**
Appendix A

Properties Identified for Dye Testing

Site Address	Site Access	Roof Drainage					Area Drainage				Basement			Cleanout	Possible Improper Source or Lead Connection	Comments/Notes							
		DA	NOH	DTC	IRD	ERD	DDS	DDG	MDS	BWWD	DWD	SWD	PD				CB	TD	Basement Flooding	History of Sump Pump on the Ground	Charges Dis-	External Cleanout	Clean-out Cap Intact
COURT ST 920	10/3/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	0	3	0	3	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO AHH 16893 9/22/00, 9/12/00 AND 8/25/00 LEFT LETTER
COURT ST 924	9/12/00	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	4	0	4	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	UNCONFIRMED IN MH 16893. THIS SITE WAS DYED 2X, ONCE USING BLUE AND AGAIN USING GREEN, WITH NEGATIVE RESULTS BOTH TIMES. 8/25/00 LEFT LETTER
COURT ST 939	6/2/80	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	0	1	0	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO ONE HOME. 9/22/00, 9/12/00 AND 8/25/00 LEFT LETTER.
COURT ST 936	8/25/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO AHH 16893 PIPS CLEANED YEARLY
COURT ST 946	9/12/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	3	0	0	3	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	REFER TO 1208 10TH ST
DIVISION ST 731	9/26/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	3	0	0	3	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO AHH 3324 9/21/00 LEFT LETTER

DA = Denied Access
NOH = No One Home
DTC = Dye Test Confirmed
IRD = Interior Roof Drain
ERD = Exterior Roof Drain

DDS = Disappearing Downspouts
DDG = Downspout Discharge on Ground
MDS = Missing Downspouts
BWWD = Basement Window Well Drain
DWD = Downspout Drain

SWD = Sidelwell Drain
PD = Patio Drain
CB = Catch Basin
TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix A

Properties Identified for Dye Testing

Site Address	Site Access	Roof Drainage	Area Drainage	Basement	Sump Pump Discharges on the Ground	Cleanout	Clean-out Cap Intact	Possible Improper Source or Lead Connection	Comments/Notes	
Street Name and No.	Inspect. Date	DA NOH DTC	IRD ERD DBS DDC MDS	BWWD DWD SWD PD CB TD	Basement Flooding	History of Pump	External			
DIVISION ST 733	9/21/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0 3 0 2 1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	PIPES CLEANED 9/21/00 BEFORE DYE WAS ADMINISTERED PRIOR TO PIPE CLEANING. MODERN SEWER CLEANED PIPES. COULD NOT SEE THE VOLUME OF SEWAGE FLOW AFTER THE CLEANING. CONFIRMED FLOW/ DISCHARGING FROM THE NORTH PIPE INTO MH 2973
DIVISION ST 801	9/26/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0 2 0 1 1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE EAST PIPE INTO MH 2925
DIVISION ST 809	9/26/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0 3 0 3 0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE EAST PIPE INTO MH 2974. PIPES CLEANED YEARLY FOR ROOT REMOVAL.
DIVISION ST 814	10/25/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0 2 0 2 0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE EAST PIPE INTO MH 2974. PIPES CLEANED YEARLY FOR ROOT REMOVAL.
DIVISION ST 815	9/7/00	<input checked="" type="checkbox"/>	<input type="checkbox"/>	0 0 0 0 0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO ONE HOME. 10/9/00, 10/4/00 AND 9/26/00 LEFT LETTER. HOME IS FOR SALE WITH REAL ESTATE MASTERS 987-0364 X 114.

DA = Denied Access
 NOH = No One Home
 DTC = Dye Test Confirmed
 IRD = Interior Roof Drain
 ERD = Exterior Roof Drain

DDC = Disappearing Downspouts
 DDG = Downspout Discharge on Ground
 MDS = Missing Downspouts
 BWWD = Basement Window Wall Drain
 DWD = Driveway Drain

SWD = Stairwell Drain
 PD = Porch Drain
 CB = Catch Basin
 TD = Total Drain

City of Port Huron
7th and 9th Street
**Dye Testing and Private Property
Inflow Source Investigation**
Appendix A

Properties Identified for Dye Testing

Site Address	Site Access	Roof Drainage	Area Drainage	Basement	Sump Pump Discharges on the Ground	Cleanout	Clean-out Cap Intact	Possible Improper Source or Connection	Comments/Notes
Street Name and No.	Inspect. Date	DA NOH DTC	IRD ERD DDS DCG MDS	BWWD DWD SWD PD CB TD	Base-ment Flooding	History of Pump	External Cleanout	Connection	
DIVISION ST 821	10/4/00	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE TEST UNCONFIRMED IN MH 2925, MH 999, MH 2974 AND MH 3040. 9/26/00 LEFT LETTER.
DIVISION ST 825	9/21/00	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	UNCONFIRMED IN MH 2925. RESIDENT HAS BURN IN HOME 40 YEARS AND SAYS LEAD GOES TO ALLEY. PIPES CLEANED FOR ROOTS EVERY 2 YEARS.
DIVISION ST 828	10/26/00	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO ONE HOME. HOME IS FOR SALE AND THERE IS A WATER SHUT OFF NOTICE ON THE PORCH.
DIVISION ST 833	9/7/00	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO ONE HOME. 10/4/00, 9/26/00 AND 9/21/00 LEFT LETTER.
DIVISION ST 834	10/26/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE EAST PIPE INTO MH 3040.
DIVISION ST 836	10/26/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	APARTMENTS. DYE OBSERVED DISCHARGING FROM THE EAST PIPE INTO MH 3040.
DIVISION ST 837	9/26/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 2975. PIPES CLEANED YEARLY.

DA = Denied Access
 NOH = No One Home
 DTC = Dye Test Confirmed
 IRD = Interior Roof Drain
 ERD = Exterior Roof Drain
 DDS = Disappearing Downspouts
 DDC = Downspout Discharge on Ground
 MDS = Missing Downspouts
 BWWD = Basement Window Well Drain
 DWD = Driveway Drain
 SWD = Stairwell Drain
 PD = Patio Drain
 CB = Catch Basin
 TD = Todd Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix A

Properties Identified for Dye Testing

Site Address	Site Access	Roof Drainage	Area Drainage	Basement	Sump Pump Discharges on the Ground	Cleanout	Clean-out Cap Intact	Possible Improper Source or Lead Connection	Comments/Notes
901	<input checked="" type="checkbox"/>	0	0	0	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 2925. ALL NEW PLUMBING IN 1999. PIPES CLEANED YEARLY FOR ROOT REMOVAL.
907	<input checked="" type="checkbox"/>	0	3	0	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 2925.
913	<input checked="" type="checkbox"/>	0	0	0	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 2925.
914	<input checked="" type="checkbox"/>	0	3	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO ONE HOME.
919	<input checked="" type="checkbox"/>	0	0	0	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 2925. 9/21/00 LBS77 LETTER
920	<input checked="" type="checkbox"/>	0	6	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 999.
923	<input checked="" type="checkbox"/>	0	0	0	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 2925.
912	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	REFER TO 912 LAPPERR AVE.

DA = Denied Access
 NOH = No One Home
 DTC = Dye Test Confirmed
 IRD = Interior Roof Drain
 ERD = Exterior Roof Drain
 DDS = Disappearing Downspouts
 DDG = Downspout Discharge on Ground
 MDS = Missing Downspouts
 BWWD = Basement Window Weal Drain
 DWD = Driveway Drain
 SWD = Stairwell Drain
 PD = Patio Drain
 CB = Catch Basin
 TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix A

Properties Identified for Dye Testing

Site Address	Site Access	Roof Drainage					Area Drainage					Basement			Cleanout	Possible Improper Source or Lead Connection	Comments/Notes						
Street Name and No.	Inspect. Date	DA	NCH	DTC	IRD	ERD	DDS	DDG	MDS	BWWD	DWD	SWD	PD	CB	TO	Base-ment	History of Sump Flooding	Sump Pump Discharges on the Ground	External Cleanout	out-let Cap Intact			
GRISWOLD ST 603	10/11/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	2	1	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	COMMERCIAL SITE. DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 5614. PIPES CLEANED 10:00. DISAPPEARING DOWNSPOUT NEEDS TO BE CHECKED.
GRISWOLD ST 702	9/26/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	COMMERCIAL SITE. DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 4792. NO PLUMBING DETAILS ON PRINT.
GRISWOLD ST 718	9/26/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	COMMERCIAL SITE. DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 4792.
GRISWOLD ST 730	9/26/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	1	0	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	COMMERCIAL SITE COMBINED WITH APARTMENTS ADDRESSED AS 1605 IAY ST. DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 3889. ON MAP, MH 3589 IS LABELED AS A STORM MH.
GRISWOLD ST 735	8/23/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>						<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	REFER TO 1534 8TH ST.
GRISWOLD ST 736	9/26/00	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	2	0	1	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	COMMERCIAL SITE. UNCONFIRMED IN MH 4333, MH 5615 AND MH 3589. 9/26/00 LEFT LETTER.

DA = Denied Access
 NOH = No One Home
 DTC = Dye Test Confirmed
 IRD = Interior Roof Drain
 ERD = Exterior Roof Drain

DDS = Disappearing Downspouts
 DDG = Downspout Discharge on Ground
 MDS = Missing Downspouts
 BWWD = Basement Window Well Drain
 DWD = Driveway Drain

SWD = Stairwell Drain
 PD = Patio Drain
 CB = Catch Basin
 TD = Todd Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix A

Properties Identified for Dye Testing

Site Address	Site Access	Roof Drainage					Basement				Cleanout	Possible Improper Source or Lead Connection	Comments/Notes						
		DA	NOH	DTC	IRD	ERD	DDS	DDG	MDS	BWWD				DWD	SWD	PD	CB	TD	Basement History of Sump Pump on the Ground
GRISWOLD ST 803	9/14/00	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	REFER TO 1523 8TH ST.
GRISWOLD ST 830	9/23/00	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	1	0	3	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	COMMERCIAL SITE COMBINED WITH 834 GRISWOLD ST. AND 838 GRISWOLD ST. DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 3679. MH 2879 WAS CHECKED NEGATIVE FOR DYE.
GRISWOLD ST 834	8/23/00	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	REFER TO 830 GRISWOLD ST.
GRISWOLD ST 835	9/14/00	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	OCCUPANT ADMINISTERED DYE. DYE OBSERVED DISCHARGING FROM THE EAST PIPE INTO MH 5444
GRISWOLD ST 837	10/6/00	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	1	0	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	COMMERCIAL SITE. DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 5444. BASEMENT HAS 2" - 3" OF WATER AT ALL TIMES. 8/11/00 LEFT LETTER.
GRISWOLD ST 838	8/23/00	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	REFER TO 830 GRISWOLD ST.
GRISWOLD ST 903	8/11/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	2	0	0	2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 5444.

DA = Denied Access
 NOH = No One Home
 DTC = Dye Test Confirmed
 IRD = Interior Roof Drain
 ERD = Exterior Roof Drain
 DDS = Disappearing Downspouts
 DDG = Downspout Discharge on Ground
 MDS = Missing Downspouts
 BWWD = Basement Window Well Drain
 DWD = Downspout Drain
 SWD = Stairwell Drain
 PD = Patio Drain
 CB = Catch Basin
 TD = Total Drain

City of Port Huron
7th and 9th Street
**Dye Testing and Private Property
Inflow Source Investigation**
Appendix A

Properties Identified for Dye Testing

Site Address	Site Access	Roof Drainage	Area Drainage	Basement	Sump Pump Discharges on the Ground	Cleanout	Clean-out Cap Connection	Possible Improper Lead Connection	Comments/Notes	
Street Name and No.	Inspect Date	DA NOH DTC	IRD ERD DDS DDG MDS	BWWD DWD SWD PD CB TD	Basement Flooding	History of Pump	External Cleanout	Intact		
HOWARD ST 729	10/11/00	<input type="checkbox"/>	<input type="checkbox"/>	0 2 2 0 2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	COMMERCIAL SITE. VACANT BUILDING. DYE TESTING CANNOT BE PERFORMED BECAUSE OF TRAFFIC AT INTERSECTION OF LAPEER AVE. AND 7TH ST. CB #1 HAS A NORTHEAST LEAD WHICH IS JOINED BY CB #2 AND CONTINUING TO MH IN PARKING LOT. THIS MH FLOWS NORTH TO LAPEER
HOWARD ST 803	9/11/00	<input type="checkbox"/>	<input type="checkbox"/>	0 1 0 0 1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE UNCONFIRMED IN MH 13328. MH 15443, MH 15897, MH 15544, MH 15511 AND MH 15449 PIPES CLEANED 2X SINCE 1997. 8/15/00, 8/22/00 LEFT LETTER
HOWARD ST 804	8/22/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0 0 0 0 0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	COMBINED WITH 806 HOWARD ST. DYE OBSERVED DISCHARGING FROM THE NORTH PIPE INTO MH 15897. PIPES HAVE BEEN CLEANED 2X WITHIN THE PAST 5 YEARS FOR ROOT REMOVAL. 8/15/00 LEFT LETTER
HOWARD ST 806	8/22/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	REFER TO 804 HOWARD ST.
HOWARD ST 807	5/17/00	<input type="checkbox"/>	<input type="checkbox"/>	0 0 0 0 0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	UNCONFIRMED IN MH 15328. PIPES HAVE BEEN CLEANED 5X WITHIN THE PAST 2 YEARS.

DA = Denied Access
 NOH = No One Home
 DTC = Dye Test Confirmed
 IRD = Interior Roof Drain
 ERD = Exterior Roof Drain
 DDS = Disappearing Downspouts
 DDG = Downspout Discharge on Ground
 MDS = Missing Downspouts
 BWWD = Basement Window Wall Drain
 DWD = Driveway Drain
 SWD = Slatwall Drain
 PD = Patio Drain
 CB = Catch Basin
 TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix A

Properties Identified for Dye Testing

Street Name and No.	Inspect Date	Roof Drainage							Basement			Cleanout		Possible Improper Source or Lead Connection	Comments/Notes					
		DA	NOH	DTC	RFD	ERD	DDS	DDG	MDS	BWWD	DWD	SWD	PD			CB	TD	ment	History of Sump Pump Flooding	Sump Pump Discharges on the Ground
HOWARD ST 811	8/22/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>		DYE OBSERVED DISCHARGING FROM THE SOUTHEAST PIPE INTO MH 15328. PIPES CLEANED 2X WITHIN THE PAST 5 YEARS FOR ROOT REMOVAL.
HOWARD ST 815	8/22/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE SOUTHEAST PIPE INTO MH 15328.
HOWARD ST 835	8/22/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	COMBINED WITH 837 HOWARD ST. DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 15328. OCCUPANTS HAVE BEEN IN HOME SINCE 1999. 8/15/00 LEFT LETTER.
HOWARD ST 837	8/22/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	REFER TO 835 HOWARD ST.
HOWARD ST 838	8/15/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 15328.
HOWARD ST 904	5/16/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO ONE HOME. 8/15/00 HOME IS VACANT.
HOWARD ST 909	8/21/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 997. OCCUPANTS HAVE BEEN IN THE HOME SINCE 1998.

DA = Decked Access
NOH = No One Home
DTC = Dye Test Confirmed
HSD = Interior Roof Drain
ERD = Exterior Roof Drain

DDS = Disappearing Downspouts
DDG = Downspout Discharge on Ground
MDS = Missing Downspouts
BWWD = Basement Window Weal Drain
DWD = Driveway Drain

SWD = Stairwell Drain
PD = Padle Drain
CB = Catch Basin
TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix A

Properties Identified for Dye Testing

Site Address	Site Access	Roof Drainage	Area Drainage	Basement	Basement Pump Discharges on the Ground	Cleanout	Clean-out Cap Intact	Possible Improper Source of Lead Connection	Comments/Notes
HOWARD ST 913	8/21/00 <input type="checkbox"/>	DA <input type="checkbox"/> NOH <input type="checkbox"/> DTC <input checked="" type="checkbox"/>	IRD <input type="checkbox"/> ERD <input type="checkbox"/> DDS <input type="checkbox"/> DDG <input type="checkbox"/> MDS <input type="checkbox"/>	BWWD <input type="checkbox"/> DWD <input type="checkbox"/> SWD <input type="checkbox"/> PD <input type="checkbox"/> CB <input type="checkbox"/> TD <input type="checkbox"/>	0	0	<input checked="" type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 997
HOWARD ST 915	8/21/00 <input type="checkbox"/>	DA <input type="checkbox"/> NOH <input type="checkbox"/> DTC <input checked="" type="checkbox"/>	IRD <input type="checkbox"/> ERD <input type="checkbox"/> DDS <input type="checkbox"/> DDG <input type="checkbox"/> MDS <input type="checkbox"/>	BWWD <input type="checkbox"/> DWD <input type="checkbox"/> SWD <input type="checkbox"/> PD <input type="checkbox"/> CB <input type="checkbox"/> TD <input type="checkbox"/>	0	3	0	0	DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 997. PIPES HAVE BEEN CLEANED IX
HOWARD ST 923	8/21/00 <input type="checkbox"/>	DA <input type="checkbox"/> NOH <input type="checkbox"/> DTC <input checked="" type="checkbox"/>	IRD <input type="checkbox"/> ERD <input type="checkbox"/> DDS <input type="checkbox"/> DDG <input type="checkbox"/> MDS <input type="checkbox"/>	BWWD <input type="checkbox"/> DWD <input type="checkbox"/> SWD <input type="checkbox"/> PD <input type="checkbox"/> CB <input type="checkbox"/> TD <input type="checkbox"/>	0	1	0	1	DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 997. PIPES CLEANED IX WITHIN THE PAST 2 YEARS FOR ROOT REMOVAL.
HOWARD ST 924	5/16/00 <input type="checkbox"/>	DA <input type="checkbox"/> NOH <input type="checkbox"/> DTC <input checked="" type="checkbox"/>	IRD <input type="checkbox"/> ERD <input type="checkbox"/> DDS <input type="checkbox"/> DDG <input type="checkbox"/> MDS <input type="checkbox"/>	BWWD <input type="checkbox"/> DWD <input type="checkbox"/> SWD <input type="checkbox"/> PD <input type="checkbox"/> CB <input type="checkbox"/> TD <input type="checkbox"/>	0	3	0	3	NO ONE HOME, 10/4/00 AND 8/21/00 LEFT LETTER.
HOWARD ST 930	8/21/00 <input type="checkbox"/>	DA <input type="checkbox"/> NOH <input type="checkbox"/> DTC <input checked="" type="checkbox"/>	IRD <input type="checkbox"/> ERD <input type="checkbox"/> DDS <input type="checkbox"/> DDG <input type="checkbox"/> MDS <input type="checkbox"/>	BWWD <input type="checkbox"/> DWD <input type="checkbox"/> SWD <input type="checkbox"/> PD <input type="checkbox"/> CB <input type="checkbox"/> TD <input type="checkbox"/>	0	0	0	0	DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 16110
HOWARD ST 934	8/21/00 <input type="checkbox"/>	DA <input type="checkbox"/> NOH <input type="checkbox"/> DTC <input checked="" type="checkbox"/>	IRD <input type="checkbox"/> ERD <input type="checkbox"/> DDS <input type="checkbox"/> DDG <input type="checkbox"/> MDS <input type="checkbox"/>	BWWD <input type="checkbox"/> DWD <input type="checkbox"/> SWD <input type="checkbox"/> PD <input type="checkbox"/> CB <input type="checkbox"/> TD <input type="checkbox"/>	0	2	0	2	DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 16110
HOWARD ST 940	8/21/00 <input type="checkbox"/>	DA <input type="checkbox"/> NOH <input type="checkbox"/> DTC <input checked="" type="checkbox"/>	IRD <input type="checkbox"/> ERD <input type="checkbox"/> DDS <input type="checkbox"/> DDG <input type="checkbox"/> MDS <input type="checkbox"/>	BWWD <input type="checkbox"/> DWD <input type="checkbox"/> SWD <input type="checkbox"/> PD <input type="checkbox"/> CB <input type="checkbox"/> TD <input type="checkbox"/>	0	1	0	1	DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 16110

DA = Denied Access
 NOH = No One Home
 DTC = Dye Test Confirmed
 IRD = Interior Roof Drain
 ERD = Exterior Roof Drain
 DDS = Disappearing Downspouts
 DDG = Downspout Discharge on Ground
 MDS = Missing Downspouts
 BWWD = Basement Window Weel Drain
 DWD = Driveway Drain
 SWD = Stairwell Drain
 PD = Patio Drain
 CB = Catch Basin
 TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix A

Properties Identified for Dye Testing

Street Name and No.	Inspect. Date	Site Access	Roof Drainage						Area Drainage				Basement	Sump Pump Discharges on the Ground	External Cleanout Intact	Possible Improper Source or Connection	Comments/Notes		
			DA	NOH	DTC	IRD	ERD	DDS	DDG	MDS	BWWD	DWD						SWD	PD
HOWARD ST	942 8/21/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	4	2	2	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO 14110. OCCUPANTS HAVE BEEN IN HOME ONE YEAR. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.
JAY ST	1605 9/26/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	REFER TO 730 GRISWOLD ST.
LAFERR AVE	708 9/27/00	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	6	0	8	1	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	1	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	COMMERCIAL SITE COMBINED WITH 710, 712, 714, 716 LAFERR AVE. CANNOT PERFORM DYE TEST BECAUSE OF TRAFFIC VOLUME AT THE INTERSECTION OF LAFERR AVE. AND 7TH ST. CATCH BASIN HAS A 4" NORTHEAST LEAD WITH UNKNOWN CONNECTION. INSPECTORS LEFT CARD W/BAKENDER AT ACTIVE LOUNGE. INSPECTORS SPOKE WITH OCCUPANT OF ANTIQUE STORE AND WERE ADVISED THAT HE ONLY RENTS THE SPACE AND HE DOES NOT HAVE ACCESS TO THE BASEMENT. CATCH BASIN NEEDS TO BE CHECKED.
LAFERR AVE	710 8/23/00	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	REFER TO 708 LAFERR AVE.
LAFERR AVE	712 9/27/00	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	REFER TO 708 LAFERR AVE.

DA = Deeded Access
 NOH = No One Home
 DTC = Dye Test Confirmed
 IRD = Interior Roof Drain
 ERD = Exterior Roof Drain

DDS = Disappearing Downspouts
 DDG = Downspout Discharge on Ground
 MDS = Missing Downspouts
 BWWD = Basement Window Well Drain
 DWD = Downspout Drain

SWD = Siltwell Drain
 PD = Patio Drain
 CB = Catch Basin
 TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix A

Properties Identified for Dye Testing

Site Address	Site Access	Roof Drainage							Basement		Sump Pump Discharges on the Ground	Cleanout	Clean-out Cap Intact	Possible Improper Source or Lead Connection	Comments/Notes			
		DA	NOH	DTC	IRD	ERD	DDS	DDG	MDS	BWWD						DWD	SWD	PD
LAPERER AVE 714	9/27/00	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	REFER TO 708 LAPERER ST.	
LAPERER AVE 716	9/27/00	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	REFER TO 708 LAPERER AVE.	
LAPERER AVE 802	8/23/00	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	2	2	0	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	COMMERCIAL SITE COMBINED WITH 804, 806, 808, 810 AND 812 LAPERER AVE. DYE TEST COULD NOT BE PERFORMED BECAUSE OF TRAFFIC VOLUME AT THE INTERSECTION OF 7TH ST. AND LAPERER AVE. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.
LAPERER AVE 804	8/23/00	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	REFER TO 802 LAPERER AVE.	
LAPERER AVE 806	8/23/00	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	REFER TO 802 LAPERER AVE.	
LAPERER AVE 808	8/23/00	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	REFER TO 802 LAPERER AVE.	
LAPERER AVE 810	8/23/00	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	REFER TO 802 LAPERER AVE.	
LAPERER AVE 812	8/23/00	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	REFER TO 802 LAPERER AVE.	

DA = Denied Access
 NOH = No One Home
 DTC = Dye Test Confirmed
 IRD = Interior Roof Drain
 ERD = Exterior Roof Drain
 DDS = Disappearing Downspouts
 DDG = Downspout Discharge on Ground
 MDS = Missing Downspouts
 BWWD = Basement Window Well Drain
 DWD = Downspout Drain
 SWD = Stairwell Drain
 PD = Patio Drain
 CB = Catch Basin
 TD = Total Drain

City of Port Huron
7th and 9th Street
**Dye Testing and Private Property
Inflow Source Investigation**
Appendix A

Properties Identified for Dye Testing

Site Address	Site Access	Roof Drainage	Area Drainage	Basement	Sump Pump Discharges on the Ground	Cleanout	Clean-out Cap In tact	Possible Improper Source or Lead Connection	Comments/Notes
LAPERR AVE 912	9/1/00 <input type="checkbox"/>	<input checked="" type="checkbox"/>	4 3 0 9 0	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	COMMERCIAL SITE COMBINED WITH 912 GILLET ST. DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MAH 15328. PRINT SHOWS THREE CBS, ALTHOUGH THERE ARE ACTUALLY FOUR CBS ON THE PROPERTY. ALL CBS JOIN TOGETHER AND EXIT THE PROPERTY VIA ONE LEAD/CONNECTING TO MAH 15328
LAPERR AVE 930	9/18/00 <input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	1 2 1 4 0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	COMMERCIAL SITE. DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MAH 997. ROOF DRAIN POSSIBLY CONNECTS TO MAH 997 FROM A DIRECT 3" LEAD. THIS NEEDS TO BE CHECKED.

DA = Decked Access
 NOH = No One Home
 DTC = Dye Test Confirmed
 IRD = Interior Roof Drain
 ERD = Exterior Roof Drain
 DHS = Disappearing Downspouts
 DDC = Downspout Discharge on Ground
 MDS = Missing Downspouts
 BWWD = Basement Window Well Drain
 DWWD = Driveway Drain
 SVD = Stairwell Drain
 PD = Patio Drain
 CB = Catch Basin
 TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix A

Properties Identified for Dye Testing

Site Address	Site Access	Roof Drainage	Area Drainage	Basement	Basement History of Sump Pump Flooding	Sump Pump Discharges on the Ground	Cleanout	Cleanout Cap Intact	Possible Improper Source of Lead Connection	Comments/Notes					
LAPERER AVE 945	10/11/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	5	3	8	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	COMMERCIAL SITE. DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 150499 LOCATED WEST OF RIVER CENTRE DR. NORTH SIDE OF LAPERER AVE.) PRINT AVAILABLE IN SITE OFFICE, BUT MANAGER WOULD NOT LET US BORROW PRINT TO COPY. ALTHOUGH SHE MADE A COPY OF PERTINENT AREAS ON REGULAR COPY MACHINE. 4 CATCH BASINS. NORTH CATCH BASIN HAS NORTHEAST AND SOUTH LEADS. EAST CATCH BASIN HAS A 6" NORTHEAST PVC LEAD. SOUTHEAST CATCH BASIN HAS AN 8" NORTH PVC LEAD. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.
LAPERER AVE 945	10/11/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	1	1	6	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	COMMERCIAL SITE. DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 150499 LOCATED WEST OF RIVER CENTRE CR. NORTH SIDE OF LAPERER AVE.) AN UNKNOWN PVC PIPE EXISTS EAST SIDE OF BLDG AND DISCHARGES INTO PIPE IN THE GROUND. CATCH BASIN HAS A NORTH LEAD AND DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.

DA = Denied Access
 NOH = No One Home
 DTC = Dye Test Confirmed
 IRD = Interior Roof Drain
 ERD = Exterior Roof Drain
 DDS = Disappearing Downspouts
 DDG = Downspout Discharge on Ground
 MDS = Missing Downspouts
 BWWD = Basement Windows Wall Drain
 DWD = Driveway Drain
 SWD = Stairwell Drain
 PD = Porch Drain
 CB = Catch Basin
 TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix A

Properties Identified for Dye Testing

Site Address	Site Access	Roof Drainage	Area Drainage	Basement	Basement History of Sump Pump Discharges on the Ground	External Cleanout	Cleanout Cap Intact	Possible Improper Source or Lead Connection	Comments/Notes
OAK ST 802	9/21/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	0	0	0	<input checked="" type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE EAST PIPE INTO MH 2925.
OAK ST 840	10/10/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	1	0	0	<input checked="" type="checkbox"/>	APARTMENTS, DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 2912. MH 2925 CHECKED NEGATIVE FOR DYE. 9/26/00 LEFT LETTER.
OAK ST 903	8/23/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	4	0	0	<input type="checkbox"/>	NO ONE HOME. 10/10/00 AND 9/26/00 LEFT LETTER.
OAK ST 937	9/25/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	2	0	4	0	COMMERCIAL SITE. DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 2879.
PINE ST 705	10/25/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	REFER TO 721 PINE ST.

DA = Denied Access
 NOH = No One Home
 DTC = Dye Test Confirmed
 IRD = Interior Roof Drain
 ERD = Exterior Roof Drain
 DDS = Disappearing Downspouts
 DDG = Downspout Discharge on Ground
 MDS = Missing Downspouts
 BWWD = Basement Window Well Drain
 DWD = Driveway Drain
 SWD = Stairwell Drain
 PD = Patio Drain
 CB = Catch Basin
 TD = Tada Drain

City of Port Huron
7th and 9th Street
**Dye Testing and Private Property
Inflow Source Investigation**
Appendix A

Properties Identified for Dye Testing

Site Address	Site Access	Roof Drainage	Area Drainage	Basement	Sump Pump Discharges on the Ground	Cleanout	Clean-out Cap Intact	Possible Improper Source or Lead Connection	Comments/Notes
710 PINE ST	DA NOH DTC	IRD ERD DDS DDG MDS	BWWD DWD SWD PD CB TD	ment	History of Flooding	Basement	History of Flooding	History of Flooding	CHURCH BUILT IN 1864 #1 TEST DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MAH 17903 #2 TEST DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MAH 17903 #3 TEST DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MAH 17903. PIPES CLEANED YEARLY. MAH 17903 DOES HAVE A SOUTH LAD GOING DIRECTLY TO THE CHURCH. POSSIBLE SERVICES DISAPPEARING DOWNSPOUTS. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED. PRINT IS FOR RENOVATION OF ENTRANCE WAY. NO PLUMBING DETAILS.

DA = Denied Access
NOH = No One Home
DTC = Dye Test Confirmed
IRD = Interior Roof Drain
ERD = Exterior Roof Drain

MDS = Missing Downspouts
DDG = Downspout Discharge on Ground
BWWD = Basement Window Well Drain
DWD = Downspout Drain

SWD = Stairwell Drain
PD = Pullin Drain
CB = Catch Basin
TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix A

Properties Identified for Dye Testing

Site Address	Site Access	Roof Drainage	Area Drainage	Basement	Basement Sump Pump Dis- charges on the Ground	Cleanout	Clean- out Cap Intact	Possible Improper Source or Lead Connection	Comments/Notes
PINE ST 721	10/24/00 <input type="checkbox"/> DA <input type="checkbox"/> NOH <input checked="" type="checkbox"/> DTC	<input type="checkbox"/> IRD <input type="checkbox"/> ERD <input type="checkbox"/> DDS <input type="checkbox"/> DDG <input type="checkbox"/> MDS	<input type="checkbox"/> BWWD <input type="checkbox"/> DWD <input type="checkbox"/> SWD <input type="checkbox"/> PD <input type="checkbox"/> CB <input checked="" type="checkbox"/> TD	<input type="checkbox"/> 0 <input type="checkbox"/> 8 <input type="checkbox"/> 31 <input type="checkbox"/> 10 <input type="checkbox"/> 0	<input type="checkbox"/> 8	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	PORT HURON HOUSING COMMISSION COMBINED WITH 705 PINE ST, 735 PINE ST, 919 7TH ST, AND 920 8TH ST. FIVE (5) DYE TESTS WERE PERFORMED (1 ON EACH WING) 2 TESTS DYE WAS OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 17857. 3RD TEST DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 15937. 4TH TEST DYE OBSERVED DISCHARGING FROM THE SOUTHEAST PIPE INTO MH 15937. 5TH TEST DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 15544. MH 17903, MH 1773 AND MH AT EAST LAWN CHECKED AND FOUND NEGATIVE FOR DYE. DRAINS CONSIST OF 2 PARKING LOT CATCH BASINS, 1 TRENCH DRAIN LOCATED IN THE NORTHEAST SIDEWALK AND 5 LAWN CATCH BASINS. THERE ARE 6 CLEANOUTS, 4 ARE LOCATED ON THE SOUTHWEST CORNER OF THE BUILDING AND 2 ARE LOCATED AT THE INTERSECTION OF THE NORTH SIDE OF THE BUILDING. ALL CATCH BASINS CONNECT TO SANITARY LEADS. (SEE DIAGRAMS) RE TEST DONE AT NORTH AND EAST WINGS. DYE WAS NOT OBSERVED AT EITHER OF THE MANHOLES LOCATED ON THE PROPERTY.

DA = Denied Access
NOH = No One Home
IRD = Interior Roof Drain
ERD = Exterior Roof Drain

DDS = Disappearing Downspouts
DDG = Downspout Discharge on Ground
MDS = Missing Downspouts
BWWD = Basement Window Well Drain
DWD = Downspout Drain

SWD = Storm Sewer Drain
PD = Patio Drain
CB = Catch Basin
TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix A

Properties Identified for Dye Testing

Street Name and No.	Inspect. Date	DA	NOH	DTC	Roof Drainage							Basement			Cleanout	Possible Improper Source or Lead Connection	Comments/Notes			
					IRD	ERD	DDS	DDG	MDS	BWWD	DWD	SWD	PD	CB				TD	Basement	Sump Pump Discharges on the Ground
PINE ST 735	10/5/00	<input checked="" type="checkbox"/>																		REFER TO 721 PINE ST.
PINE ST 742	8/10/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>			0	2	0	2	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH# 17903. 8/9/00 LEFT LETTER.
PINE ST 803	8/15/00	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	2	0	0	2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	COMBINED WITH 803.5 PINE ST. DYE UNCONFIRMED IN MH 16110, MH 16316, MH 16330 AND THREE (3) OTHER MANHOLES GOING NORTH ON 7TH ST. ALSO CHECKED THE MANHOLE LOCATED ON PINE ST. AT EAST SIDE OF 7TH ST. PRES CLEANED EVERY SIX MONTHS FOR ROOT REMOVAL.
PINE ST 803.5	5/17/00	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>						<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	REFER TO 803 PINE ST.	
PINE ST 815	5/17/00	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	5	3	3	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	UNCONFIRMED AT MH 13. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.	
PINE ST 832	8/15/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	COMBINED WITH 1002 9TH ST. DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 16330. 8/15/00 LEFT LETTER.	

DA = Denied Access
 NOH = No One Home
 DTC = Dye Test Confirmed
 IRD = Inferior Roof Drain
 ERD = Exterior Roof Drain
 DDS = Disappearing Downspouts
 DDG = Downspout Discharge on Ground
 MDS = Missing Downspouts
 BWWD = Basement Window Wall Drain
 DWD = Downspout
 SWD = Sumpwell Drain
 PD = Patio Drain
 CB = Catch Basin
 TD = Total Drain
 DWD = Downspout

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix A

Properties Identified for Dye Testing

Site Address	Site Access	Roof Drainage	Area Drainage	Basement	Basement History of Sump Flooding	Sump Pump Discharges on the Ground	Cleanout	Clean-out Cap Intact	Possible Improper Source or Lead Connection	Comments/Notes
Street Name and No.	Inspect. Date	DA NOH DTC	IRD ERD DDS DDG MDS	BWWD DWD SWD PD CB TD	ment					
PINE ST 833	8/15/00	<input checked="" type="checkbox"/>	0 0 0 0	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 16110.
PINE ST 903	8/15/00	<input checked="" type="checkbox"/>	0 4 0 2	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	5 APARTMENTS COMBINED WITH 927 9TH ST. DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 16110.
PINE ST 939	8/23/00	<input checked="" type="checkbox"/>	0 1 0 1	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 16110. PIPES CLEANED IX WITHIN THE PAST 5 YEARS FOR ROOT REMOVAL.
PINE ST 940	9/22/00	<input type="checkbox"/>	0 2 1 1	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	UNCONFIRMED IN MH 16269N AND MH 7522. OCCUPANT ADMITS TERRED DYE DISAPPEARING DOWNSPOUT HEADS TO BE CHECKED.
UNION ST 602	9/19/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	REFER TO 1303 6TH ST.

DA = Denied Access
 NOH = No One Home
 DTC = Dye Test Confirmed
 IRD = Interior Roof Drain
 ERD = Exterior Roof Drain
 DDS = Disappearing Downspouts
 DDG = Downspout Discharge on Ground
 MDS = Missing Downspouts
 BWWD = Basement Window Wall Drain
 DWD = Driveway Drain
 SWD = Stairwell Drain
 PD = Patio Drain
 CB = Catch Basin
 TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix A

Properties Identified for Dye Testing

Site Address	Site Access	Roof Drainage						Area Drainage				Basement	Sump Pump Discharges on the Ground	Cleanout	Clean-out Cap Intact	Possible Improper Source or Lead Connection	Comments/Notes		
		DA	NOH	DTC	IRD	ERD	DDS	DDG	MDS	BWWD	DWD							SMD	PD
UNION ST 630	8/18/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	1	2	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 17027 NEW CLEANOUT LEAD. 8/18/09 DAVE SMITH FROM THE CITY OF PORT HURON CALLED FIELD OFFICE AND ASKED THAT SOMEONE CONTACT RESIDENT IS CALLED RESIDENT AND DISCUSSED INFLOW/SOURCES. DISAPPEARING DOWNSCOURTS NEED TO BE CHECKED.
UNION ST 838	9/13/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	1	0	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 16947 9/13/00, 8/14/00 AND 8/11/00 LEFT LETTER.
UNION ST 839	9/20/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 16893 9/13/00 AND 8/11/00 LEFT LETTER.
UNION ST 904	9/13/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	COMBINED WITH 906 UNION ST. DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 16947 9/13/00, 8/17/00, 8/14/00 LEFT LETTER.
UNION ST 905	8/11/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	COMBINED WITH 1227 9TH ST. DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 16893.

DA = Denied Access
 NOH = No One Home
 DTC = Dye Test Confirmed
 IRD = Interior Roof Drain
 ERD = Exterior Roof Drain

DDG = Disappearing Downspouts
 DDS = Downspout Discharge on Ground
 DDC = Downspout Discharge on Ground
 MDS = Missing Downspouts
 BWWD = Basement Window Well Drain
 DWD = Driveway Drain

SWD = Stairwell Drain
 PD = Patio Drain
 CB = Catch Basin
 TD = Tidal Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix A

Properties Identified for Dye Testing

Site Address	Site Access	Roof Drainage	Area Drainage	Basement	Basement History of Sump Flooding	Sump Dis- charges on the Ground	Cleanout	Clean- out Cap Intact	Possible Improper Source or Lead Connection	Comments/Notes
Street Name and No.	Inspect. Date	DA NOH DTC	IRD ERD DDS DDG MDS	BWWD DWD SMD PD CB TD	ment		External Cleanout	Intact		
UNION ST 906	9/13/00	<input checked="" type="checkbox"/>								REFER TO 904 UNION ST.
WALL ST 703	9/27/00	<input checked="" type="checkbox"/>	0 0 0 0		<input checked="" type="checkbox"/>					APARTMENTS. DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INFO MH 17686.
WALL ST 804	5/22/00	<input type="checkbox"/>	0 1 0 1 0		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>				UNCONFIRMED IN MH 1881.
WALL ST 835	8/14/00	<input checked="" type="checkbox"/>	0 0 0 0 0		<input checked="" type="checkbox"/>					DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 16369. PIPES CLEANED IN LAST YEAR FOR ROOT REMOVAL. 8/11/00 LEFT LETTER.
WALL ST 838	8/14/00	<input checked="" type="checkbox"/>	0 0 0 0 0		<input checked="" type="checkbox"/>					CONFINED WITH 1110 9TH ST. DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 16395 8/14/00 LEFT LETTER.
WALL ST 901	8/24/00	<input type="checkbox"/>	0 4 0 0 3 1		<input checked="" type="checkbox"/>					DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 16269. OCCUPANTS HAVE BEEN IN HOME ONE MONTH.

DA = Denied Access
 NOH = No One Home
 DTC = Dye Test Confirmed
 IRD = Interior Roof Drain
 ERD = Exterior Roof Drain
 DDS = Disappearing Downspouts
 DDG = Downspout Discharge on Ground
 MDS = Missing Downspouts
 BWWD = Basement Window W/Ch Drain
 DWD = Driveway Drain
 SMD = Sump Drain
 PD = Patio Drain
 CB = Catch Basin
 TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix A

Properties Identified for Dye Testing

Site Address	Site Access	Roof Drainage	Area Drainage	Basement	Basement Pump Discharges on the Ground	Cleanout	Clean-out Cap Intact	Possible Improper Source or Lead Connection	Comments/Notes
Street Name and No.	Inspect. Date	DA NOH DTC	IRD ERD DDS DCG MDS	BWWD DWD SWD PD CB TD	ment	Flooding	Pump		
WALL ST 904	8/14/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0 3 1 2 0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	CONFINED WITH 1111 9TH ST. DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 16395. PIPES ARE CLEANED 3X PER YEAR. DISAPPEARING DOWNSPOUT NEEDS TO BE CHECKED.
WALL ST 913	9/11/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0 3 0 4 0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	THREE (3) APARTMENTS DYE OBSERVED. DISCHARGING FROM THE WEST PIPE INTO MH 16269. EXTERNAL CLEANOUT IS NOT PROPERLY CAPPED, BUT IT IS LOCATED UNDER A DECK AND IS NOT AN INFLOW SOURCE. 8/24/00 LEFT LETTER.
WALL ST 919	8/24/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0 0 0 0 0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 16269.
WALL ST 929	9/28/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0 3 0 4 0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 16269. 9/22/00 LEFT LETTER.
WALL ST 931	8/23/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0 4 0 3 1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 16512.
WHITE ST 618	6/7/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0 2 0 2 0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO ONE HOME. APPEARS VACANT. 10/11/00 AND 8/18/00 LEFT LETTER.

DA = Denied Access
 NOH = No One Home
 DTC = Dye Test Confirmed
 IRD = Interior Roof Drain
 ERD = Exterior Roof Drain
 DDS = Disappearing Downspouts
 DDCG = Downspout Discharge on Ground
 MDS = Missing Downspouts
 BWWD = Basement Window Well Drain
 DWD = Downspout
 SWD = Stairwell Drain
 PD = Patio Drain
 CB = Catch Basin
 TD = Tidal Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix A

Properties Identified for Dye Testing

Site Address	Site Access	Roof Drainage	Area Drainage	Basement	Basement Pump Discharges on the Ground	Cleanout	Clean-out Cap Intact	Possible Improper Source or Lead Connection	Comments/Notes														
Street Name and No.	Inspect. Date	DA	NOH	DTC	IRD	ERD	DDS	DDG	MDS	BWWD	DWD	SWD	PD	CB	TD	ment	Flooding	Pump	Ground	Cleanout	Intact	Connection	Comments/Notes
WHITE ST 632	8/1/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 4689. PIPES CLEANED 2X WITHIN THE PAST 5 YEARS FOR ROOT REMOVAL. 8/10/00 LEFT LETTER
WHITE ST 739	8/10/00	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	1	0	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 4690.
WHITE ST 740	6/8/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	0	4	0	4	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	COMBINED WITH 742 WHITE ST. AND 1502 8TH ST. NO ONE HOME. LEFT LETTER 8/10/00
WHITE ST 742	6/8/00	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	REFER TO 740 WHITE ST.

DA = Denied Access
 NOH = No One Home
 DTC = Dye Test Confirmed
 IRD = Interior Roof Drain
 ERD = Exterior Roof Drain
 DDS = Disappearing Downspouts
 DDG = Downspout Discharge on Ground
 MDS = Missing Downspouts
 BWWD = Basement Window Well Drain
 DWD = Driveway Drain
 SWD = Stairwell Drain
 PD = Patio Drain
 CB = Catch Basin
 TD = Total Drain

APPENDIX B

Properties Not Needing Dye Testing

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix B

Properties not Needing Dye Testing

Site Address	Roof Drainage					Area Drainage					Basement				Cleanup		Possible Improper Source or Lead Connection	Comments/Notes
	IRD	ERD	DDS	DDG	MDS	BWWD	DWD	SWD	PD	CB	Total Drains	Basement Flooding	History of Sump Pump Discharges on the Ground	External Clean-out	Clean-out Cap Intact			
10TH ST 912	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.	
10TH ST 916	0	3	2	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	NO DYE TESTING NEEDED. DISCONNECTED DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.	
10TH ST 1014	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.	
10TH ST 1018	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.	
10TH ST 1102	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.	
10TH ST 1122	0	0	0	0	0	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	COMMERCIAL SITE. NO DYE TESTING NEEDED. UNABLE TO LOCATE EXITING PIPES FROM THE BASEMENT WINDOW WELL DRAINS.NEED TO BE CHECKED.	
10TH ST 1316	0	1	0	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.	
6TH ST 1307	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.	
6TH ST 1315	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.	
6TH ST 1317	0	2	0	2	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.	

IRD = Interior Roof Drain
ERD = Exterior Roof Drain
DDS = Disappearing Downspouts
DDG = Downspout Discharge on Ground
MDS = Missing Downspouts
BWWD = Basement Window Well Drain
DWD = Driveway Drain
SWD = Sideload Drain
PD = Patio Drain
CB = Catch Basin
TD = Total Drains

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix B

Properties not Needing Dye Testing

Site Address	Roof Drainage						Area Drainage						Basement			Cleanout		Possible Improper Source or Lead Connection	Comments/Notes
	IRD	ERD	DDS	DDG	MDS		BWWD	DWD	SWD	PD	CB	Total Drains	Basement Flooding	History of Pump	Sump Pump Discharges on the Ground	External Cleanout Intact	Cleanout Cap Intact		
6TH ST 1321	6/14/00	0	1	0	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
6TH ST 1325	6/14/00	0	1	0	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
6TH ST 1403	6/14/00	0	4	0	4	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
6TH ST 1407	6/14/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
6TH ST 1411	6/14/00	0	3	0	3	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
6TH ST 1417	8/21/00						<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	REFER TO 1419 6TH ST.
6TH ST 1419	6/14/00	0	1	0	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	COMBINED WITH 1417 6TH ST. NO DYE TESTING NEEDED.
6TH ST 1421	6/14/00	0	6	0	6	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	COMBINED WITH 1421.5 6TH ST. AND 1423 6TH ST. NO DYE TESTING NEEDED.
6TH ST 1421.5	8/21/00						<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	REFER TO 1421 6TH ST.
6TH ST 1423	8/21/00						<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	REFER TO 1421 6TH ST.
6TH ST 1431	8/21/00						<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	REFER TO 1433 6TH ST.

IRD = Interior Roof Drain DWD = Driveway Drain
 ERD = Exterior Roof Drain SVD = Stairwell Drain
 DDS = Disappearing Downspouts PD = Patio Drain
 DDG = Downspout Discharge on Ground CB = Catch Basin
 MDS = Missing Downspouts TD = Total Drains
 BWWD = Basement Window Well Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix B

Properties not Needing Dye Testing

Site Address	Roof Drainage					Area Drainage					Basement			Cleanup		Possible Improper Source or Lead Connection	Comments/Notes		
	IRD	ERD	DDS	DDG	MDS	BWWD	DWD	SWD	PD	CB	Total Drains	Basement	History of Flooding	Pump	Sump Discharges on the Ground			External Clean-out	Clean-out Cap Intact
6TH ST 1433	6/14/00	0	3	1	2	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	COMBINED WITH 1431 6TH ST. NO DYE TESTING NEEDED. DISAPPEARING DOWNSPOUT NEEDS TO BE CHECKED.
6TH ST 1509	6/14/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
6TH ST 1511	6/14/00	0	1	0	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
6TH ST 1603	8/23/00	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	REFER TO 616 GRIFFWOLD ST.
7TH ST 920	11/6/00	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	REFER TO 924 7TH ST.
7TH ST 924	11/6/00	0	3	0	8	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	COMMERCIAL SITE. COMBINED WITH 920 7TH ST. NO DYE TESTING NEEDED. PER PRINT, TWO 6" SANITARY LEADS EXT THE SOUTH SIDE OF BLDG, JOIN, AND THEN TURN EAST TO CONNECT TO ALLEY. *TWO STORM LEADS EXT SOUTH SIDE OF BLDG CONNECTING TO CATCH BASIN IN PARKING LOT, THEN CONTINUING EAST TO CONNECT TO SAN. SEWER IN ALLEY. *CATCH BASIN INVESTIGATION SHOWS THAT THERE IS NO NORTH LEAD FROM THE CATCH BASIN AND THE CATCH BASIN DOES NOT CONNECT TO THE SANITARY SEWER IN THE ALLEY. CB BELONGS TO 615 PINE ST.

IRD = Interior Roof Drain
 ERD = Exterior Roof Drain
 DDS = Disappearing Downspouts
 DDG = Downspout Discharge on Ground
 MDS = Missing Downspouts
 BWWD = Basement Window Well Drain
 DWD = Driveway Drain
 SWD = Stairwell Drain
 PD = Pade Drain
 CB = Catch Basin
 TD = Total Drain

City of Port Huron
7th and 9th Street

Dye Testing and Private Property
Inflow Source Investigation
Appendix B

Properties not Needing Dye Testing

Site Address	Roof Drainage					Area Drainage					Basement				Cleanout		Possible Improper Source or Lead Connection	Comments/Notes
	IRD	ERD	DDS	DDG	MDS	BWMD	DWD	SWD	PD	CB	Total Drains	Basement Flooding	History of Pump	Sump Pump Discharges on the Ground	External Clean-out	Clean-Cap Intact		
7TH ST 1003						<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	CHURCH AND HOUSE. NO DYE TESTING NEEDED. NO PLUMBING OR DRAINAGE DETAILS ON PRINT.
7TH ST 1013	6/9/00	1	11	16	1	0	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	7	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	CHURCH AND HOUSE. NO DYE TESTING NEEDED. DISAPPEARING DOWNSPOUTS AND BASEMENT WINDOW WELL DRAINS NEED TO BE CHECKED.
7TH ST 1017	6/9/00	0	4	0	4	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
7TH ST 1021	6/9/00	0	4	4	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	NO DYE TESTING NEEDED. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.
7TH ST 1208	6/9/00	0	2	2	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	NO DYE TESTING NEEDED. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.
7TH ST 1308	6/9/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
7TH ST 1312	6/9/00	0	3	0	3	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED. COMBINED WITH 1314 7TH ST.
7TH ST 1314	6/9/00						<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	REFER TO 1312 7TH ST.
7TH ST 1317	6/9/00	1	13	11	2	0	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	CHURCH AND HOUSE. NO DYE TESTING NEEDED. DISAPPEARING DOWNSPOUTS AND BASEMENT WINDOW WELL DRAINS NEED TO BE CHECKED.

IRD = Interior Roof Drain
ERD = Exterior Roof Drain
DDS = Disappearing Downsouts
DDG = Downspout Discharge on Ground
MDS = Missing Downsouts
BWMD = Basement Window Well Drain
DWD = Downspout Drain
PD = Patio Drain
CB = Catch Basin
TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix B

Properties not Needing Dye Testing

Site Address	Roof Drainage						Area Drainage						Basement			Cleanout		Possible Improper Source or Lead Connection	Comments/Notes	
	IRD	ERD	DDS	DDG	MDS		BWWD	DWD	SWD	PD	CB	Total Drains	Basement Flooding	History of Pump	Sump Discharges on the Ground	External Clean-out	Clean-out Cap Intact			
7TH ST 1320	6/9/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	COMMERCIAL SITE. NO DYE TESTING NEEDED.
7TH ST 1322	8/21/00						<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	REFER TO 1324 7TH ST.
7TH ST 1324	6/9/00	0	1	0	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	COMBINED WITH 1322 7TH ST. NO DYE TESTING NEEDED.
7TH ST 1332	6/9/00	0	1	0	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
7TH ST 1403	6/12/00	1	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	SCHOOL COMBINED WITH 718 CHESTNUT ST. NO DYE TESTING NEEDED. PART OF THE BUILDING HAS DRAIN THAT DISCHARGES AT THE BASE.
7TH ST 1505	6/12/00	0	1	0	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
7TH ST 1508	6/12/00	0	2	0	2	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
7TH ST 1511	6/12/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
7TH ST 1512	6/12/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
7TH ST 1514	6/12/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
7TH ST 1515	6/12/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.

IRD = Interior Roof Drain
ERD = Exterior Roof Drain
DDS = Disappearing Downspouts
DDG = Downspout Discharge on Ground
MDS = Missing Downspouts
BWWD = Basement Window Weir Drain

DWD = Driveway Drain
SWD = Slatwell Drain
PD = Patio Drain
CB = Catch Basin
TD = Total Drain

City of Port Huron
7th and 9th Street

Dye Testing and Private Property
Inflow Source Investigation
Appendix B

Properties not Needing Dye Testing

Site Address	Roof Drainage					Area Drainage					Basement			Cleanout		Possible Improper Source or Lead Connection	Comments/Notes		
	Street Name and No.	Inspect Date	IRD	ERD	DDS	DDG	MDS	BMWD	DWD	SWD	PD	CB	Total Drains	Basement Flooding	History of Pump			Sump Pump Discharges on the Ground	External Clean-out
7TH ST 1318	6/12/00	0	6	0	6	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
8TH ST 821	5/22/00	0	3	2	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED
8TH ST 921	5/22/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	NO DYE TESTING NEEDED.
8TH ST 1004	5/18/00	0	2	0	2	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
8TH ST 1033	8/23/00	0	10	4	10	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	CHURCH COMBINED WITH 811 WALL ST. NO DYE TESTING NEEDED. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.
8TH ST 1113	5/18/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
8TH ST 1215	8/21/00	0	2	2	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	NO DYE TESTING NEEDED. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.
8TH ST 1219	8/21/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	NO DYE TESTING NEEDED.
8TH ST 1228	8/21/00	0	7	0	9	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
8TH ST 1315	5/24/00	0	1	1	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	NO DYE TESTING NEEDED. DISAPPEARING DOWNSPOUT NEEDS TO BE CHECKED.

IRD = Interior Roof Drain
ERD = Exterior Roof Drain
DDS = Disappearing Downsports
DDG = Downspout Discharge on Ground
MDS = Missing Downsports
BMWD = Basement Window Well Drain

DWD = Downspout Drain
SWD = Stairwell Drain
PD = Patio Drain
CB = Catch Basin
TD = Total Drain

City of Port Huron
7th and 9th Street
**Dye Testing and Private Property
Inflow Source Investigation**
Appendix B

Properties not Needing Dye Testing

Site Address	Roof Drainage					Area Drainage					Basement			Cleanout		Possible Improper Source or Lead Connection	Comments/Notes	
	IRD	ERD	DDS	DDG	MDS	BMWd	DWD	SWD	PD	CB	Total Drains	Basement Flooding	History of Sump Pump	Sump Pump Discharges on the Ground	External Clean-out			Clean-out Cap Intact
87TH ST 1321 5/24/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
87TH ST 1406 5/24/00	1	8	1	7	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	NO DYE TESTING NEEDED, DISAPPEARING DOWNSPOUT NEEDS TO BE CHECKED
87TH ST 1422 5/24/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
87TH ST 1512 8/23/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	REFER TO 731 GRISWOLD ST.
87TH ST 1521 5/24/00	1	3	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
97TH ST 823 5/18/00	0	2	0	2	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
97TH ST 833 5/18/00	0	5	0	5	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
97TH ST 835 5/18/00	0	1	0	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
97TH ST 920 5/18/00	0	1	2	2	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	NO DYE TESTING NEEDED, DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED
97TH ST 1011 8/21/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
97TH ST 1113 5/23/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.

IRD = Interior Roof Drain
ERD = Exterior Roof Drain
DDS = Disappearing Downspouts
DDG = Downspout Discharge on Ground
MDS = Missing Downspouts

DWD = Downspout Drain
SWD = Stairwell Drain
PD = Patio Drain
CB = Catch Basin
TD = Toilet Drain
BMWd = Basement Window Well Drain

City of Port Huron
7th and 9th Street

Dye Testing and Private Property
Inflow Source Investigation
Appendix B

Properties not Needing Dye Testing

Street Name and No.	Inspect Date	Roof Drainage					Area Drainage					Basement			Cleanup		Possible Improper Source or Lead Connection	Comments/Notes	
		IRD	ERD	DDS	DDG	MDS	BWWD	DWD	SWD	PD	CB	Total Drains	Base-ment	History of Flooding	Sump Pump Discharges on the Ground	Exter-nal Clean-out			Clean-out Cap Intact
9TH ST 1209	5/23/00	3	0	3	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
9TH ST 1506	5/26/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
9TH ST 1511	5/26/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
9TH ST 1513	5/26/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
9TH ST 1515	5/26/00	0	1	0	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
9TH ST 1611	8/21/00						<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	HOUSE HAS BEEN RAZED.
9TH ST 1612	5/30/00	0	3	0	3	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
9TH ST 1823	5/30/00	0	2	0	2	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED. NO CAP ON EXTERNAL CLEANOUT.
9TH ST 1902	5/30/00	0	3	0	3	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
9TH ST 1903	5/30/00	0	1	0	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
9TH ST 1906	5/30/00	0	4	0	4	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
9TH ST 1909	5/30/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.

IRD = Interior Roof Drain
ERD = Exterior Roof Drain
DDS = Downspout Discharge on Ground
DDG = Downspout Discharge on Ground
MDS = Missing Downspouts
BMWWD = Basement Window Well Drain

DWD = Downspout Drain
SWD = Stairwell Drain
PD = Patio Drain
CB = Catch Basin
TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix B

Properties not Needing Dye Testing

Site Address	Roof Drainage					Area Drainage					Basement			Cleanout		Possible Improper Source or Lead Connection	Comments/Notes			
	Street Name and No.	Inspect. Date	IRD	ERD	DDS	DDG	MDS	BWWD	DWD	SWD	PD	CB	Total Drains	Basement Flooding	History of Pump			Sump Pump Discharges on the Ground	External Clean-out Intact	Clean-out Cap Intact
9TH ST 1915	5/30/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
9TH ST 1916	5/30/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
9TH ST 1919	5/30/00	0	2	0	2	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
9TH ST 1920	5/30/00	0	3	0	3	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
9TH ST 1925	5/30/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
BANCROFT ST 909	9/6/00	0	3	0	3	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
BANCROFT ST 913	9/6/00	0	4	0	3	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
BANCROFT ST 921	9/6/00	0	4	2	4	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	NO DYE TESTING NEEDED. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.
BANCROFT ST 923	9/6/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
BANCROFT ST 925	9/6/00	0	1	0	1	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
CHESTNUT ST 613	6/6/00	0	1	0	1	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
CHESTNUT ST 617	6/6/00	0	3	0	3	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.

IRD = Interior Roof Drain DWD = Downspout Drain
 ERD = Exterior Roof Drain SWD = Stairwell Drain
 DDS = Disappearing Downspouts PD = Patio Drain
 DDG = Downspout Discharge on Ground CB = Catch Basin
 MDS = Missing Downspouts TD = Total Drain
 BWWD = Basement Window Well Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix B

Properties not Needing Dye Testing

Site Address	Roof Drainage					Area Drainage					Basement		Cleanout		Possible Improper Source or Lead Connection	Comments/Notes	
	IRD	ERD	DDS	DDG	MDS	BWWD	DWD	SWD	PD	CB	Total Drains	Basement Flooding	Sump Pump Discharges on the Ground	External Clean-out			Clean-out Cap Intact
CHESTNUT ST 718	8/21/00																REFER TO 1403 7TH ST.
CHESTNUT ST 725	6/6/00	0	4	0	4	0					0						NO DYE TESTING NEEDED.
CHESTNUT ST 727	6/6/00	0	6	1	5	0					0						NO DYE TESTING NEEDED. DISAPPEARING DOWNPOUT NEEDS TO BE CHECKED.
CHESTNUT ST 732	6/16/00	0	0	0	0	0					0						NO DYE TESTING NEEDED.
CHESTNUT ST 733	6/6/00	0	1	0	1	0					0						NO DYE TESTING NEEDED.
CHESTNUT ST 739	6/6/00	0	1	0	1	0					0						NO DYE TESTING NEEDED.
CHESTNUT ST 819	6/5/00	0	1	0	1	0					0						NO DYE TESTING NEEDED.
CHESTNUT ST 823	6/5/00	0	6	0	6	0					0						NO DYE TESTING NEEDED.
CHESTNUT ST 825	6/5/00	0	0	0	0	0					0						NO DYE TESTING NEEDED.
CHESTNUT ST 827	6/5/00	0	4	0	2	0					0						NO DYE TESTING NEEDED.
CHESTNUT ST 831	6/5/00	0	0	0	0	0					0						NO DYE TESTING NEEDED.

IRD = Interior Roof Drain
ERD = Exterior Roof Drain
DDS = Disappearing Downspouts
DDG = Downspout Discharge on Ground
MDS = Missing Downspouts
BWWD = Basement Window Well Drain

DWD = Downspout Drain
SWD = Subswell Drain
PD = Patio Drain
CB = Catch Basin
TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix B

Properties not Needing Dye Testing

Site Address	Roof Drainage					Area Drainage					Basement			Cleanout		Possible Improper Source or Lead Connection	Comments/Notes			
	Street Name and No.	Inspect. Date	IRD	ERD	DDS	DDG	MDS	BWWD	DWD	SWD	PD	CB	Total Drains	Base-ment	History of Flooding			Sump Pump Dis-charges on the Ground	Exter-nal Clean-out	Clean-out Cap Intact
CHESTNUT ST 834	10/13/00	1	3	2	2	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	CB	8	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	SCHOOL. NO DYE TESTING NEEDED. 3 CATCH BASINS IN NORTH PARKING LOT, WITH A CLEANOUT LOCATED IN ONE, AND ANOTHER 4" LEAD IN ANOTHER. 4 CATCH BASINS AND A MANHOLE ARE LOCATED IN THE ADJACENT PLAYGROUND, ALL OF THEM CONNECT, WITH A SINGLE LEAD GOING EAST, AND CONNECTING TO A SEWER LINE FLOWING NORTH. ALSO, ONE OF THE CATCH BASINS HAS A 4" EAST LEAD AND A 4" WEST LEAD. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.
CHESTNUT ST 909	6/5/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
CHESTNUT ST 913	6/5/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
CHESTNUT ST 917	6/5/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
CHESTNUT ST 923	6/5/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
CHESTNUT ST 925	8/21/00	0	0	1	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	NO DYE TESTING NEEDED. DISCONNECTED DISAPPEARING DOWNSPOUTS NOT PROPERLY CAPPED.
CHESTNUT ST 927	6/5/00	0	1	0	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	COMBINED WITH 929 CHESTNUT ST. NO DYE TESTING NEEDED.

IRD = Interior Roof Drain
ERD = Exterior Roof Drain
DDS = Disappearing Downspouts
DDG = Downspout Discharge on Ground
MDS = Missing Downspouts
BWWD = Basement Window Well Drain

DWD = Driveway Drain
SWD = Sidewalk Drain
PD = Patio Drain
CB = Catch Basin
TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix B

Properties not Needing Dye Testing

Site Address	Roof Drainage						Area Drainage						Basement			Cleanout		Possible Improper Source or Lead Connection	Comments/Notes	
	IRD	ERD	DDS	DDG	MDS	Total Drains	BWWD	DWD	SWD	PD	CB	Drains	Basement Flooding	History of Sump Pump	Sump Pump Discharges on the Ground	External Clean-out Intact	Clean-out Cap Intact			
CHESTNUT ST 929	6/5/00																			REFER TO 927 CHESTNUT ST.
CHESTNUT ST 931	6/5/00	0	3	0	3	0						0								NO DYE TESTING NEEDED.
COURT ST 628	6/1/00	0	1	0	1	0						0								NO DYE TESTING NEEDED.
COURT ST 714	6/1/00	0	2	0	2	0						0								NO DYE TESTING NEEDED.
COURT ST 718	6/1/00	0	1	0	1	0						0								NO DYE TESTING NEEDED.
COURT ST 722	6/1/00	0	4	3	1	0						0								COMBINED WITH 724 COURT ST. NO DYE TESTING NEEDED. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.
COURT ST 724	6/1/00																			REFER TO 722 COURT ST.
COURT ST 726	6/1/00	0	3	0	3	0						0								NO DYE TESTING NEEDED. COMBINED WITH 728 COURT ST.
COURT ST 728	6/1/00																			REFER TO 726 COURT ST.
COURT ST 734	6/1/00	0	0	0	0	0						0								NO DYE TESTING NEEDED.

IRD = Interior Roof Drain
 ERD = Exterior Roof Drain
 DDS = Disappearing Downspouts
 DDG = Downspout Discharge on Ground
 MDS = Missing Downspouts
 BWWD = Basement Window Vell Drain
 DWD = Driveway Drain
 SWD = Stairwell Drain
 PD = Patio Drain
 CB = Catch Basin
 TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix B

Properties not Needing Dye Testing

Street Name and No.	Inspect Date	Roof Drainage						Area Drainage					Basement			Cleanout		Possible Improper Source of Lead Connection	Comments/Notes	
		IRD	ERD	DDS	DDG	MDS		BWWD	DWD	SWD	PD	CB	Total Drains	Base-ment	History of Flooding	Sump Pump Dis-charges on the Ground	Exter-nal Clean-out Intact			Clean-out Cap Intact
COURT ST 803	6/1/00	0	4	1	3	0		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	COMBINED WITH 806 COURT ST AND 807 COURT ST. NO DYE TESTING NEEDED. DISAPPEARING DOWNSPOUT NEEDS TO BE CHECKED.
COURT ST 805	6/1/00						<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	REFER TO 803 COURT ST.
COURT ST 807	6/1/00						<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	REFER TO 803 COURT ST.
COURT ST 808	6/1/00	0	3	0	3	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
COURT ST 809	6/1/00	0	5	3	2	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	COMBINED WITH 811 COURT ST, 813 COURT ST AND 815 COURT ST. NO DYE TESTING NEEDED. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.
COURT ST 811	6/1/00						<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	REFER TO 809 COURT ST.
COURT ST 813	6/1/00						<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	REFER TO 809 COURT ST.
COURT ST 815	6/1/00						<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	REFER TO 809 COURT ST.
COURT ST 816	6/1/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
COURT ST 819	6/1/00	0	3	1	2	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	NO DYE TESTING NEEDED. DISAPPEARING DOWNSPOUT NEEDS TO BE CHECKED.

IRD = Interior Roof Drain
 ERD = Exterior Roof Drain
 DDS = Disappearing Downsports
 DDG = Downspout Discharge on Ground
 MDS = Missing Downsports
 BWWD = Basement Window Well Drain

DWD = Downspout Drain
 SWD = Stairwell Drain
 PD = Patio Drain
 CB = Catch Basin
 TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix B

Properties not Needing Dye Testing

Site Address	Roof Drainage					Area Drainage					Basement			Cleanup		Possible Improper Source or Lead Connection	Comments/Notes			
	Street Name and No.	Inspect. Date	R/D	ERD	DDS	DDG	MDS	BWWD	DWD	SWD	PD	CB	Total Drains	Base-ment	History of Flooding			Sump Pump Dis-charges on the Ground	Exter-nal Clean-out	Clean-out Cap Intact
COURT ST 822	6/1/00	0	5	4	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	NO DYE TESTING NEEDED DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED
COURT ST 825	6/1/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED
COURT ST 826	6/1/00	0	3	0	3	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	COMBINED WITH 828 COURT ST NO DYE TESTING NEEDED
COURT ST 828	6/1/00						<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	REFER TO 826 COURT ST.
COURT ST 831	6/1/00	0	3	0	3	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED
COURT ST 832	6/1/00	0	5	0	5	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED
COURT ST 833	6/2/00	0	5	2	3	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	NO DYE TESTING NEEDED, DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED
COURT ST 909	8/23/00						<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	THIS BUILDING HAS BEEN RAZED AND IS NOW BEING UTILIZED AS A PARKING LOT FOR 903 COURT ST.
COURT ST 911	8/21/00	0	3	1	2	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	COMBINED WITH 913 COURT ST. NO DYE TESTING NEEDED, DISAPPEARING DOWNSPOUT NEEDS TO BE CHECKED.
COURT ST 913	8/21/00						<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	REFER TO 911 COURT ST.

IRD = Interior Roof Drain
ERD = Exterior Roof Drain
DDS = Disappearing Downspouts
DDG = Downspout Discharge on Ground
MDS = Missing Downspouts
BWWD = Basement Window Well Drain

DWD = Downspout Drain
SWD = Stairwell Drain
PD = Pade Drain
CB = Catch Basin
TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix B

Properties not Needing Dye Testing

Site Address	Roof Drainage					Area Drainage					Basement			Cleanout		Possible Improper Source or Lead Connection	Comments/Notes	
	IRD	ERD	DDS	DDG	MDS	BWWD	DWD	SWD	PD	CB	Total Drains	Base-ment	History of Flooding	Sump Pump Dis-charges on the Ground	Exter-nal Clean-out			Clean-out Cap Intact
COURT ST 919	6/2/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
COURT ST 921	6/2/00	0	4	2	2	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	NO DYE TESTING NEEDED. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.
COURT ST 927	6/2/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
COURT ST 929	6/2/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
DIVISION ST 810	9/7/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
DIVISION ST 820	10/26/00	0	4	0	5	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED. RENOVATIONS BEING DONE ON THE BOWEL.
GILBERT ST 810	8/23/00	0	2	0	0	2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	APARTMENTS. NO DYE TESTING NEEDED.
GRISWOLD ST 607	8/23/09	0	1	0	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	COMBINED WITH 607 S GRISWOLD ST. NO DYE TESTING NEEDED.
GRISWOLD ST 607.5	8/23/00						<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	REFER TO 607 GRISWOLD ST.
GRISWOLD ST 616	8/23/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	COMBINED WITH 1603 6TH ST. NO DYE TESTING NEEDED.
GRISWOLD ST 619	8/23/00	0	5	0	4	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.

IRD = Interior Roof Drain
 ERD = Exterior Roof Drain
 DDS = Disappearing Downspouts
 DDG = Downspout Discharge on Ground
 MDS = Missing Downspouts
 BWWD = Basement Window Well Drain
 DWD = Driveway Drain
 SWD = Stairwell Drain
 PD = Patio Drain
 CB = Catch Basin
 TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix B

Properties not Needing Dye Testing

Site Address	Roof Drainage						Area Drainage						Basement			Cleanup		Possible Improper Source or Lead Connection	Comments/Notes
	IRD	ERD	DDS	DDG	MDS	BWWD	DWD	SWD	PD	CB	Total Drains	Base-ment	History of Flooding	Sump Pump Dis- charges on the Ground	Exter- nal Clean- out	Clean- out Cap Intact			
GRISWOLD ST 630	8/23/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED
GRISWOLD ST 622	8/23/00	0	3	1	1	2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	NO DYE TESTING NEEDED, BUT DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED
GRISWOLD ST 636	8/23/00	0	0	2	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	NO DYE TESTING NEEDED, BUT DISCONNECTED DISAPPEARING DOWNSPOUT LOCATED AT THE SOUTHWEST CORNER OF THE HOME IS NOT PROPERLY CAPPED.
GRISWOLD ST 709	8/23/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED
GRISWOLD ST 711	8/23/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED
GRISWOLD ST 713	8/23/00	0	2	0	1	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED
GRISWOLD ST 717	8/23/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED
GRISWOLD ST 721	8/23/00	0	6	0	6	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	COMBINED WITH 721 S GRISWOLD ST. NO DYE TESTING NEEDED
GRISWOLD ST 721.5	8/23/00						<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	REFER TO 721 GRISWOLD ST.
GRISWOLD ST 727	8/23/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.

IRD = Interior Roof Drain
ERD = Exterior Roof Drain
DDS = Disappearing Downspouts
DDG = Downspout Discharge on Ground
MDS = Missing Downspouts
BWWD = Basement Window Wall Drain

DWD = Driveway Drain
SWD = Stairwell Drain
PD = Patio Drain
CB = Catch Basin
TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix B

Properties not Needing Dye Testing

Site Address	Roof Drainage						Area Drainage						Basement			Cleanout		Possible Improper Source or Lead Connection	Comments/Notes		
	IRD	ERD	DDS	DDG	MDS	Total	BWWD	DWD	SWD	PD	CB	Drains	Base-ment	History of Flooding	Sump Pump on the Ground	Exter-nal Clean-out	Clean-out Cap Intact				
GRISWOLD ST 731	8/23/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	COMMERICAL SITE CONCERNED WITH 1512 8TH ST. NO DYE TESTING NEEDED, BUT CLEANOUT IS NOT PROPERLY CAPPED.
GRISWOLD ST 802	8/23/00	0	1	1	0	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	NO DYE TESTING NEEDED, BUT DISCONNECTED DISAPPEARING DOWNSPOUT IS NOT PROPERLY CAPPED.
GRISWOLD ST 809	8/23/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	COMBINED WITH 811 GRISWOLD ST. NO DYE TESTING NEEDED.
GRISWOLD ST 811	8/23/00						<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	REFER TO 809 GRISWOLD ST.
GRISWOLD ST 812	8/23/00	0	4	5	0	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	NO DYE TESTING NEEDED, BUT DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.
GRISWOLD ST 815	8/23/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
GRISWOLD ST 817	8/23/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
GRISWOLD ST 820	8/23/00	0	5	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
GRISWOLD ST 821	8/23/00	0	2	0	2	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
GRISWOLD ST 825	8/23/00	0	4	0	3	2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.

IRD = Interior Roof Drain
ERD = Exterior Roof Drain
DDS = Disappearing Downspouts
DDG = Downspout Discharge on Ground
MDS = Missing Downspouts
BWWD = Basement Window Well Drain

DWD = Downspout Drain
SWD = Stairwell Drain
PD = Pile Drain
CB = Catch Basin
TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix B

Properties not Needing Dye Testing

Site Address	Roof Drainage					Area Drainage					Basement		Cleanout		Possible Improper Source or Lead Connection	Comments/Notes		
	Street Name and No.	Inspect Date	IRD	ERD	DDS	DDG	MDS	BWMD	DWD	SMD	PD	CB	Total Drains	Basement Flooding			History of Pump on the Ground	External Clean-out Intact
GRISWOLD ST 826	8/23/00	0	2	0	1	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	APARTMENTS. NO DYE TESTING NEEDED.
GRISWOLD ST 904	8/23/00	0	2	0	1	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	APARTMENTS. NO DYE TESTING NEEDED.
GRISWOLD ST 906	8/23/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	APARTMENTS. NO DYE TESTING NEEDED.
GRISWOLD ST 909	8/23/00	0	2	0	1	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	COMBINED WITH 911 GRISWOLD ST. NO DYE TESTING NEEDED.
GRISWOLD ST 911	8/23/00						<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	REFER TO 909 GRISWOLD ST.
GRISWOLD ST 914	8/23/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	APARTMENTS COMBINED WITH 916 GRISWOLD ST. NO DYE TESTING NEEDED.
GRISWOLD ST 916	8/23/00						<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	REFER TO 914 GRISWOLD ST.
GRISWOLD ST 919	8/23/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
GRISWOLD ST 922	8/23/00	0	2	0	0	3	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
GRISWOLD ST 923	8/23/00	0	3	0	3	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
GRISWOLD ST 926	8/23/00	0	2	0	1	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.

IRD = Interior Roof Drain
 ERD = Exterior Roof Drain
 DDS = Downspout Discharge on Downspouts
 DDG = Downspout Discharge on Ground
 MDS = Missing Downspouts
 BWMD = Basement Window Well Drain
 DWD = Driveway Drain
 SMD = Storm Drain
 PD = Patio Drain
 CB = Catch Basin
 TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix B

Properties not Needing Dye Testing

Site Address	Roof Drainage							Area Drainage					Basement			Cleanup		Possible Improper Source or Lead Connection	Comments/Notes
	IRD	ERD	DDS	DDG	MDS	BWWD	DWD	SWD	PD	CB	Total Drains	Basement Flooding	History of Sump Pump	Sump Pump Discharges on the Ground	External Clean-out	Clean-out Cap Intact			
GELSWOLD ST 936	5/30/00	0	1	0	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
HOWARD ST 816	5/16/00	0	1	0	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
HOWARD ST 820	5/16/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
HOWARD ST 822	5/16/00	0	1	0	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
HOWARD ST 824	5/16/00	0	1	0	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
HOWARD ST 826	8/21/00	0	1	0	0	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
HOWARD ST 828	5/16/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
HOWARD ST 832	5/16/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
HOWARD ST 910	5/16/00	0	2	0	4	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
HOWARD ST 914	5/16/00	0	2	0	2	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
HOWARD ST 917	5/16/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
HOWARD ST 918	5/16/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.

IRD = Interior Roof Drain
 ERD = Exterior Roof Drain
 DDS = Disappearing Downspouts
 DDG = Downspout Discharge on Ground
 MDS = Missing Downspouts
 BWWD = Basement Window Weir Drain
 DWD = Downspout Drain
 SVD = Stairwell Drain
 PD = Patio Drain
 CB = Catch Basin
 TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix B

Properties not Needing Dye Testing

Site Address	Roof Drainage					Area Drainage					Basement		Cleanup		Possible Improper Source of Lead Connection	Comments/Notes		
	IRD	ERD	DDS	DDG	MDS	BWWD	DWD	SWD	PD	CB	Total Drains	Basement Flooding	History of Sump Pump	Sump Pump Discharges on the Ground			External Clean-out Intact	Clean-out Cap Intact
HOWARD ST 929	5/16/00	0	3	0	2	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
HOWARD ST 935	5/16/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
HOWARD ST 937	5/16/00	0	3	0	3	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
HOWARD ST 941	5/16/00	0	2	0	0	2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
LAPIER AVE 726	8/23/00	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	BUILDING HAS BEEN RAZED AND NO LONGER EXISTS ON THIS SITE.
LAPIER AVE 736	9/27/00	0	2	0	3	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	COMMERCIAL SITE. NO DYE TESTING NEEDED. CATCH BASIN LOCATED AT THE SOUTHEAST CORNER OF SITE CONNECTS TO A SEWER FLOWING NORTH TO LAPIER AVE.

IRD = Interior Roof Drain
 ERD = Exterior Roof Drain
 DDS = Downspout Discharge on Ground
 DDG = Missing Downspouts
 MDS = Basement Window Well Drain
 BWWD = Stormwater Drain
 DWD = Downspout Discharge on Ground
 SWD = Sumpwell Drain
 PD = Radio Drain
 CB = Catch Basin
 TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix B

Properties not Needing Dye Testing

Site Address	Roof Drainage						Area Drainage						Basement			Cleanout		Possible Improper Source or Lead Connection	Comments/Notes	
	IRD	ERD	DDS	DDG	MDS	BWMD	DWD	SWD	PD	CB	Total Drains	Base-ment Flooding	History of Sump Pump	Sump Pump Dis-charges on the Ground	Exter-nal Clean-out	Clean-out Cap Intact				
LAPERRE AVE 828	11/9/00	1	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	CERCHI NO DYE TESTING NEEDED. PRINT SHOWS ADDITION CONSTRUCTED OVER DEMOLISHED HOME AND GARAGE. HALL ALSO TO BE RAZED. SEPARATE SANITARY AND STORM LEADS EXH WEST SIDE OF STRUCTURE. BOTH LEADS FLOW TO MON EAST SIDE OF PROPERTY. COMBINED SEWER RUNS NORTH FROM MH TOWARDS LAPERRE. BELOW INVESTIGATION CONFRIMS PRINT INFORMATION. INVESTIGATION ALSO SHOWS SOUTHERNMOST STORM MH HAS A 4" CLAY NORTH LEAD. BUT CONNECTION TO CATCH BASIN, LOCATED DIRECTLY NORTH OF MR. COLELD NOT BE CONFIRMED. CATCH BASIN AT SOUTHEAST END OF SITE HAS A 4" SOUTH LEAD AND A 4" NORTH LEAD WHICH CONNECTS TO MH LOCATED NORTH OF CATCH BASIN. MH NORTH OF CATCH BASIN HAS A 4" SOUTH LEAD. AN EAST LEAD AND A WESTERN LEAD FLOW IS TO THE WEST AND CONNECTS TO CATCH BASIN LOCATED AT 9TH ST. IT SHOULD BE NOTED THAT A CLEANOUT EXISTS AT THE NORTH SIDE OF OLD BUILDING. NO DYE TESTING DONE ON THIS BLDG BECAUSE OF TRAFFIC VOLUME AT 7TH ST AND LAPERRE AVE.
MINNIE ST 910	9/7/00	0	3	0	4	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.

IRD = Interior Roof Drain
 ERD = Exterior Roof Drain
 DDS = Downspout Discharge on Ground
 DDG = Downspout Discharge on Ground
 MDS = Missing Downspouts
 BWMD = Basement Window Well Drain
 DWD = Driveway Drain
 SWD = Sidelwell Drain
 PD = Patio Drain
 CB = Catch Basin
 TD = Total Drains

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix B

Properties not Needing Dye Testing

Site Address	Roof Drainage					Area Drainage					Basement			Cleanup		Possible Improper Source or Lead Connection	Comments/Notes
	IRD	ERD	DDS	DDG	MDS	BWWD	DWD	SWD	PD	CB	Total Drains	Base-ment Flooding	History of Sump Pump	Sump Pump Dis-charges on the Ground	Exter-nal Clean-out		
MINNIE ST 919	0	1	0	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED
MINNIE ST 920	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED
MINNIE ST 921	0	6	0	6	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED
MINNIE ST 930	0	3	0	3	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED
MINNIE ST 931	0	6	0	4	2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED
OAK ST 806	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED
OAK ST 808	0	2	0	3	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED
OAK ST 809	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED
OAK ST 810	0	7	0	7	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED
OAK ST 811	0	1	0	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED
OAK ST 814	0	1	0	0	2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED
OAK ST 816	0	3	0	2	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED

IRD = Interior Roof Drain
 ERD = Exterior Roof Drain
 DDS = Downspout Discharge on Ground
 DDG = Downspout Discharge on Ground
 MDS = Missing Downspouts
 BWWD = Basement Window Well Drain
 DWD = Downspout Drain
 SWD = Stairwell Drain
 PD = Porch Drain
 CB = Catch Basin
 TD = Toilet Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix B

Properties not Needing Dye Testing

Site Address	Roof Drainage						Area Drainage						Basement			Cleanout		Possible Improper Source or Lead Connection	Comments/Notes
	IRD	ERD	DDS	DDG	MDS		BWWD	DWD	SWD	PD	CB	Total Drains	Basement Flooding	History of Sump Pump	Sump Pump Discharges on the Ground	External Clean-out Intact	Clean-out Cap Intact		
OAK ST 819	9/7/00	0	2	0	2	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
OAK ST 820	9/7/00	0	1	0	0	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
OAK ST 821	9/7/00	0	1	0	0	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
OAK ST 825	9/7/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
OAK ST 826	9/7/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
OAK ST 829	9/7/00	0	4	0	5	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
OAK ST 832	9/7/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
OAK ST 833	9/7/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
OAK ST 909	8/23/00	0	2	0	1	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
OAK ST 910	8/23/00	0	4	0	4	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
OAK ST 914	8/23/00	0	1	0	0	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
OAK ST 915	8/23/00	0	1	0	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.

IRD = Interior Roof Drain
 ERD = Exterior Roof Drain
 DDS = Disappearing Downspouts
 DDG = Downspout Discharge on Ground
 MDS = Missing Downspouts
 BWWD = Basement Window Well Drain
 DWD = Driveway Drain
 SWD = Sitarwell Drain
 PD = Patio Drain
 CB = Catch Basin
 TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix B

Properties not Needing Dye Testing

Site Address	Roof Drainage					Area Drainage					Basement			Cleanout		Possible Improper Source or Lead Connection	Comments/Notes	
	IRD	ERD	DDS	DDG	MDS	BWWD	DWD	SWD	PD	CB	Total Drains	Basement Flooding	History of Pump	Sump Pump Discharges on the Ground	External Clean-out Intact			Clean-out Cap Intact
OAK ST 919	8/23/00	0	3	0	3	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
OAK ST 922	8/23/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
OAK ST 923	8/23/00	0	3	0	4	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
OAK ST 926	8/23/00	0	3	0	3	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
OAK ST 929	8/23/00	0	1	0	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	APARTMENTS. NO DYE TESTING NEEDED.
OAK ST 930	8/23/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.

IRD = Interior Roof Drain
 ERD = Exterior Roof Drain
 DDS = Dissipating Downspouts
 DDG = Downspout Discharge on Ground
 MDS = Missing Downspouts
 BWWD = Basement Window Well Drain
 DWD = Driveway Drain
 SWD = Stairwell Drain
 PD = Patio Drain
 CB = Catch Basin
 TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix B

Properties not Needing Dye Testing

Site Address	Roof Drainage							Area Drainage					Basement			Cleanout		Possible Improper Source or Lead Connection	Comments/Notes
	IRD	ERD	DDS	DDG	MDS	BWWD	DWD	SWD	PD	CB	Drains	Total	Basement Flooding	History of Sump Pump	Sump Pump Discharges on the Ground	External Clean-out	Clean-out Cap Intact		
PINE ST 615	11/3/00	0	1	5	7	0	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	5	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	COMMERCIAL SITE. NO DYE TESTING NEEDED. PRINT SHOWS ONE 8" SANITARY LEAD EXITS EAST SIDE OF BLDG. CONNECTING TO 12" SANITARY SEWER IN ALLEY. 2ND PRINT (FOR 924 7TH ST.) ALSO SHOWS A SANITARY LEAD EXITING THE NORTH SIDE OF THE BLDG AND FLOWING TO SEWER IN ALLEY. INFLOW INVESTIGATION SHOWS CATCH BASIN #1 AND CATCH BASIN #2. LOCATED AT SOUTH END OF SITE, JOIN VIA 10" PVC AND FLOW TO 7TH ST. CATCH BASIN #3. LOCATED AT NORTH SIDE OF SITE, CONNECTS TO DISAPPEARING DOWNSPOUT. CATCH BASIN #4 AND CATCH BASIN #5 JOIN TO CONNECT TO DISAPPEARING DOWNSPOUT AND PATTO DRAIN.
PINE ST 732	5/17/00	0	1	0	0	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED
PINE ST 740	5/17/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED
PINE ST 811	5/17/00	0	4	1	5	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	NO DYE TESTING NEEDED, BUT DISAPPEARING DOWNSPOUT NEEDS TO BE CHECKED.
PINE ST 814	5/17/00	0	3	0	3	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.

IRD = Interior Roof Drain
ERD = Exterior Roof Drain
DDS = Disappearing Downspouts
DDG = Downspout Discharge on Ground
MDS = Missing Downspouts
BWWD = Basement Window Well Drain

DWD = Downspout Drain
SWD = Stairwell Drain
PD = Patio Drain
CB = Catch Basin
TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix B

Properties not Needing Dye Testing

Site Address	Roof Drainage					Area Drainage					Basement		Cleanout		Possible Improper Source or Lead Connection	Comments/Notes	
	IRD	ERD	DDS	DDG	MDS	BMWVD	DWD	SWD	PD	CB	Total Drains	Base-ment Flooding	Sump Pump Dis-charges on the Ground	Exter-nal Clean-out Intact			Clean-out Cap Intact
PINE ST 821	8/21/00	0	1	1	0	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	NO DYE TESTING NEEDED, BUT DISCONNECTED DISAPPEARING DOWNSPOUT IS NOT PROPERLY CAPPED.
PINE ST 822	5/17/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
PINE ST 826	5/17/00	0	3	0	2	2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
PINE ST 827	5/16/00	0	1	0	0	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
PINE ST 829	5/16/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
PINE ST 908	5/17/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
PINE ST 909	5/16/00	0	4	0	6	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
PINE ST 911	5/16/00	0	2	0	0	2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
PINE ST 912	5/17/00	0	2	0	2	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
PINE ST 916	5/17/00	0	2	0	1	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	COMBINED WITH 918 PINE ST. NO DYE TESTING NEEDED.
PINE ST 917	5/16/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.

IRD = Interior Roof Drain
 ERD = Exterior Roof Drain
 DDS = Disappearing Downspouts
 DDG = Downspout Discharge on Ground
 MDS = Missing Downspouts
 BMWVD = Basement Window Well Drain
 DWD = Driveway Drain
 SWD = Stairwell Drain
 PD = Patio Drain
 CB = Catch Basin
 TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix B

Properties not Needing Dye Testing

Site Address	Roof Drainage						Area Drainage						Basement			Cleanup		Possible Improper Source or Lead Connection	Comments/Notes
	IRD	EKD	DDS	DDG	MDS	Total Drains	BWWD	DWD	SWD	PD	CB	Basement Flooding	History of Sump Pump	Sump Pump Discharges on the Ground	External Clean-out	Clean-out Cap Intact			
PINE ST 918	8/21/00																	REFER TO 916 PINE ST.	
PINE ST 923	5/16/00	0	0	0	0	0												NO DYE TESTING NEEDED.	
PINE ST 924	5/17/00	0	0	0	0	0												NO DYE TESTING NEEDED.	
PINE ST 926	5/17/00	0	0	0	0	0												NO DYE TESTING NEEDED.	
PINE ST 929	5/16/00	0	3	0	3	0												NO DYE TESTING NEEDED.	
PINE ST 930	5/17/00	0	2	0	3	0												NO DYE TESTING NEEDED.	
PINE ST 931	5/16/00	0	1	0	1	0												NO DYE TESTING NEEDED.	
PINE ST 933	5/16/00	0	0	0	0	0												NO DYE TESTING NEEDED.	
PINE ST 936	5/17/00	0	1	0	0	1												NO DYE TESTING NEEDED.	
UNION ST 616	6/5/00	0	4	0	4	0												NO DYE TESTING NEEDED.	
UNION ST 711	6/5/00	0	4	0	4	0												NO DYE TESTING NEEDED.	

IRD = Interior Roof Drain
 EKD = Exterior Roof Drain
 DDS = Disappearing Downspouts
 DDG = Downspout Discharge on Ground
 MDS = Missing Downspouts
 BWWD = Basement Window Well Drain
 DWD = Driveway Drain
 SWD = Stairwell Drain
 PD = Pade Drain
 CB = Catch Basin
 TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix B

Properties not Needing Dye Testing

Site Address	Roof Drainage						Area Drainage						Basement			Cleanup		Possible Improper Source or Lead Connection	Comments/Notes	
	Street Name and No.	Inspect. Date	R/D	ER/D	DD/S	DDG	MDS	B/WWD	DWD	S/WD	PD	CB	Total Drains	Base-ment	History of Flooding	Sump Pump on the Ground	Ext-er-nal Clean-out			Clean-out Cap Intact
UNION ST 719	6/5/00	0	4	4	0	0	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	3	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	NO DYE TESTING NEEDED, BUT DISAPPEARING DOWNSPOUTS AND BASEMENT WINDOW WELL DRAINS NEED TO BE CHECKED.
UNION ST 720	6/5/00	0	3	3	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	NO DYE TESTING NEEDED, BUT DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.
UNION ST 723	6/5/00	0	3	0	3	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
UNION ST 729	6/5/00	0	3	2	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	NO DYE TESTING NEEDED, BUT DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.
UNION ST 730	6/5/00	0	1	0	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
UNION ST 733	6/5/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
UNION ST 734	6/5/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
UNION ST 811	6/6/00	0	2	2	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	NO DYE TESTING NEEDED, BUT DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.
UNION ST 812	6/6/00	0	1	0	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
UNION ST 815	6/6/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.

R/D = Interior Roof Drain
 ER/D = Exterior Roof Drain
 DD/S = Disappearing Downspouts
 DDG = Downspout Discharge on Ground
 MDS = Missing Downspouts
 B/WWD = Basement Window Well Drain
 DWD = Driveway Drain
 S/WD = Slatwell Drain
 PD = Patio Drain
 CB = Catch Basin
 TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix B

Properties not Needing Dye Testing

Street Name and No.	Inspect Date	Roof Drainage					Area Drainage					Basement			Cleanout		Possible Improper Source of Lead Connection	Comments/Notes	
		IRD	ERD	DDS	DDG	MDS	BWMD	DWD	SWD	PD	CB	Total Drains	Basement Flooding	History of Pump	Sump Discharges on the Ground	External Clean-out Intact			Clean Cap Intact
UNION ST 816	6/6/00	0	1	1	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	NO DYE TESTING NEEDED, BUT DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.
UNION ST 819	6/6/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
UNION ST 822	6/6/00	0	1	0	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
UNION ST 825	6/6/00	0	6	0	6	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
UNION ST 827	6/6/00	0	2	1	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	NO DYE TESTING NEEDED, BUT DISAPPEARING DOWNSPOUT NEEDS TO BE CHECKED.
UNION ST 828	6/6/00	0	3	0	3	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	NO DYE TESTING NEEDED, BUT EXTERNAL CLEANOUT IS NOT PROPERLY CAPPED.
UNION ST 833	6/6/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
UNION ST 834	6/6/00	0	4	0	4	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
UNION ST 909	6/6/00	0	1	0	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
UNION ST 910	6/6/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
UNION ST 911	6/6/00	0	1	0	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.

IRD = Interior Roof Drain
ERD = Exterior Roof Drain
DDS = Disappearing Downspouts
DDG = Downspout Discharge on Ground
MDS = Missing Downspouts
BWMD = Basement Window Well Drain

DWD = Driveway Drain
SWD = Stairwell Drain
PD = Patio Drain
CB = Catch Basin
TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix B

Properties not Needing Dye Testing

Site Address	Roof Drainage					Area Drainage					Basement			Cleanout		Possible Improper Source or Lead Connection	Comments/Notes	
	IRD	ERD	DDS	DDG	MDS	BWMD	DWD	SWD	PD	CB	Total Drains	Basement Flooding	History of Pump	Sump Discharges on the Ground	External Clean-out Intact			Clean-out Cap Intact
UNION ST 913	6/6/00	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
UNION ST 916	6/6/00	0	1	0	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
UNION ST 917	6/6/00	0	2	1	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	NO DYE TESTING NEEDED, BUT DISAPPEARING DOWNSPOUT NEEDS TO BE CHECKED.
UNION ST 920	6/6/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
UNION ST 925	6/6/00	0	1	0	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
UNION ST 926	6/6/00	0	2	0	2	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
UNION ST 930	6/6/00	0	3	0	3	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
WALL ST 709	5/17/00	0	1	0	2	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
WALL ST 713	5/17/00	0	1	0	0	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
WALL ST 719	5/17/00	0	3	0	3	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
WALL ST 727	5/17/00	0	4	0	4	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.

IRD = Interior Roof Drain
 ERD = Exterior Roof Drain
 DDS = Dispersing Downspouts
 DDG = Downspout Discharge on Ground
 MDS = Mixing Downspouts
 BWMD = Basement Window Well Drain
 DWD = Driveway Drain
 SWD = Stormwell Drain
 PD = Pile Drain
 CB = Catch Basin
 TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix B

Properties not Needing Dye Testing

Site Address	Roof Drainage					Area Drainage					Basement			Cleanout		Possible Improper Source or Lead Connection	Comments/Notes			
	Street Name and No.	Inspect. Date	IRD	ERD	DDS	DDG	MDS	BWWD	DWD	SWD	PD	CB	Total Drains	Base-ment Flooding	History of Sump Pump			Sump Pump Dis-charges on the Ground	Exter-nal Clean-out Infract	Clean-out Cap Infract
WALL ST 729	5/17/00	0	1	1	0	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	NO DYE TESTING NEEDED, BUT DISAPPEARING DOWNSPOUT NEEDS TO BE CHECKED.
WALL ST 733	5/17/00	0	3	0	3	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
WALL ST 735	5/17/00	0	3	1	1	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	NO DYE TESTING NEEDED, BUT DISAPPEARING DOWNSPOUT NEEDS TO BE CHECKED.
WALL ST 739	5/17/00	0	1	0	2	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
WALL ST 808	5/18/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
WALL ST 811	8/23/00						<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	REFER TO 1033 8TH ST.
WALL ST 812	5/18/00	0	6	0	6	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
WALL ST 818	5/12/00	0	2	0	2	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
WALL ST 822	5/18/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
WALL ST 828	5/18/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
WALL ST 829	5/17/00	0	2	0	2	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.

IRD = Interior Roof Drain DWD = Driveway Drain
 ERD = Exterior Roof Drain SWD = Sidel-Weil Drain
 DDS = Disappearing Downspouts PD = Pate Drain
 DDG = Downspout Discharge on Ground CB = Catch Basin
 MDS = Missing Downspouts TD = Total Drain
 BWWD = Basement Window Well Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix B

Properties not Needing Dye Testing

Site Address	Roof Drainage					Area Drainage					Basement	Sump Pump Discharges on the Ground	Cleanout		Possible Improper Source or Lead Connection	Comments/Notes		
	IRD	ERD	DDS	DDG	MDS	BWWD	DWD	SWD	PD	CB			Drains	Total			Base-ment Flooding	History of Pump
WALL ST 832	5/18/00	0	4	0	4	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
WALL ST 833	5/17/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
WALL ST 910	5/18/00	0	1	0	0	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
WALL ST 914	5/18/00	0	3	0	2	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
WALL ST 918	8/28/00	0	1	0	2	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
WALL ST 921	8/28/00	0	3	0	5	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
WALL ST 924	5/18/06	0	3	0	4	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
WALL ST 930	5/18/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
WALL ST 934	5/18/00	0	1	0	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
WALL ST 938	5/18/00	0	3	0	2	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
WALL ST 942	5/18/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.

IRD = Interior Roof Drain
 ERD = Exterior Roof Drain
 DDS = Downspout Discharge on Ground
 DDG = Missing Downspouts
 MDS = Basement Window Well Drain
 DWD = Driveway Drain
 SWD = Saturated Drain
 PD = Patio Drain
 CB = Catch Basin
 TB = Total Drains

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix B

Properties not Needing Dye Testing

Site Address	Roof Drainage					Area Drainage					Basement			Cleanup		Possible Improper Source or Lead Connection	Comments/Notes	
	IRD	ERD	DDS	DDG	MDS	BWMD	DWD	SWD	PD	CB	Total Drains	Basement Flooding	History of Pump	Sump Pump Discharges on the Ground	External Clean-out			Clean-out Cap Intact
WATER ST 600	9/27/00	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	4	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	COMMERCIAL SITE. NO DYE TESTING NEEDED. 4 CATCH BASINS IN THE PARKING AREA. 6" SANITARY LEAD EXITS THE SOUTH SIDE OF THE BUILDING AND THEN TURNS EAST. CATCH BASIN AT SOUTH END HAS A NORTHWEST LEAD. CATCH BASIN AT NORTH END HAS AN 8" NORTHEAST LEAD.
WATER ST 605	8/28/00	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	THESE ARE DOCKS. NO BUILDING ON SITE. THERE IS A DISCHARGE PIPE IN THE STRAWALL ON THE EAST SIDE OF THE DOCKS. THERE IS ALSO A MANHOLE LOCATED ON THIS SITE.
WHITE ST 613	6/7/00	0	3	0	3	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
WHITE ST 614	6/7/00	0	4	0	4	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	COMBINED WITH 614.5 WHITE ST. NO DYE TESTING NEEDED.
WHITE ST 614.5	6/7/00	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	REFER TO 614 WHITE ST.
WHITE ST 617	6/7/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
WHITE ST 622	6/7/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
WHITE ST 626	6/7/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.

IRD = Interior Roof Drain DWD = Downspout Drain
 ERD = Exterior Roof Drain SVD = Stormwater Drain
 DDS = Downspout Discharge PD = Pad Drain
 DDG = Downspout Discharge on Ground CB = Catch Basin
 MDS = Missing Downspouts TD = Total Drain
 BWMD = Basement Window Well Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix B

Properties not Needing Dye Testing

Site Address	Roof Drainage							Area Drainage					Basement			Cleanout		Possible Improper Source or Lead Connection	Comments/Notes
	IRD	ERD	DDS	DDG	MDS	BWWD	DWD	SWD	PD	CB	Total Drains	Basement Flooding	History of Sump Pump	Sump Pump Discharges on the Ground	External Clean-out	Clean-out Cap Intact			
WHITE ST 709	6/8/00	1	3	2	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	NO DYE TESTING NEEDED, BUT DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.	
WHITE ST 714	6/8/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.	
WHITE ST 719	6/8/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.	
WHITE ST 720	6/8/00	0	1	0	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.	
WHITE ST 723	6/8/00	0	3	0	3	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.	
WHITE ST 724	6/8/00	0	2	0	2	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.	
WHITE ST 725	6/8/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.	
WHITE ST 729	6/8/00	0	2	0	2	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.	
WHITE ST 730	6/8/00	0	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.	
WHITE ST 733	6/8/00	0	1	1	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	NO DYE TESTING NEEDED, BUT DISAPPEARING DOWNSPOUT NEEDS TO BE CHECKED.	
WHITE ST 734	6/8/00	0	1	0	1	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	APARTMENTS COMBINED WITH 736 WHITE ST. NO DYE TESTING NEEDED.	

IRD = Interior Roof Drain
 ERD = Exterior Roof Drain
 DDS = Disappearing Downsouts
 DDG = Downspout Discharge on Ground
 MDS = Missing Downsouts
 BWWD = Basement Window Wall Drain
 DWD = Downspout Drain
 SWD = Stairwell Drain
 PD = Pade Drain
 CB = Catch Basin
 TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix B

Properties not Needing Dye Testing

Site Address	Roof Drainage					Area Drainage					Basement			Cleanout		Possible Improper Source or Lead Connection	Comments/Notes	
	IRD	ERD	DDS	DDG	MDS	BWWD	DWD	SWD	PD	CB	Total Drains	Base-ment	History of Flooding	Sump Pump Dis- charges on the Ground	Exter- nal Clean- out Intact			Clean- out Cap Intact
WHITE ST 736	8/24/00																	REFER TO 75A WHITE ST
WHITE ST 737	6/8/00	0	1	0	1	0					0							NO DYE TESTING NEEDED
WHITE ST 804	6/8/00	0	0	0	0	0					0							NO DYE TESTING NEEDED
WHITE ST 810	6/8/00	0	0	0	0	0					0							NO DYE TESTING NEEDED
WHITE ST 814	6/8/00	0	3	3	0	0					0							NO DYE TESTING NEEDED, BUT DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED
WHITE ST 818	6/8/00	0	0	0	0	0					0							NO DYE TESTING NEEDED
WHITE ST 822	6/8/00	0	0	0	0	0					0							NO DYE TESTING NEEDED
WHITE ST 828	6/8/00	0	0	0	0	0					0							NO DYE TESTING NEEDED
WHITE ST 832	6/8/00	0	4	0	4	0					0							NO DYE TESTING NEEDED
WHITE ST 910	6/8/00	0	3	0	3	0					0							NO DYE TESTING NEEDED
WHITE ST 914	6/8/00	0	0	0	0	0					0							NO DYE TESTING NEEDED
WHITE ST 918	6/8/00	0	0	0	0	0					0							NO DYE TESTING NEEDED

IRD = Interior Roof Drain
ERD = Exterior Roof Drain
DDS = Disappearing Downspouts
DDG = Downspout Discharge on Ground
MDS = Missing Downspouts
BWWD = Basement Window Well Drain

DWD = Downspout Drain
SWD = Slatwell Drain
PD = Patio Drain
CB = Catch Basin
TD = Total Drain

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix B

Properties not Needing Dye Testing

Site Address	Roof Drainage					Area Drainage					Basement			Cleanup		Possible Improper Source or Lead Connection	Comments/Notes	
	IRD	ERD	DDS	DDG	MDS	BWWD	DWD	SWD	PD	CB	Total Drains	Base-ment	History of Flooding	Sump Pump Dis- charges on the Ground	Exter- nal Clean- out			Clean- out Cap Intact
WHITE ST 922	6/8/00	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED
WHITE ST 924	6/8/00	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED
WHITE ST 928	6/8/00	0	0	0	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED

IRD = Interior Roof Drain
 ERD = Exterior Roof Drain
 DDS = Disappearing Downspouts
 DDG = Downspout Discharge on Ground
 MDS = Missing Downspouts
 BWWD = Basement Window Well Drain
 DWD = Driveway Drain
 SWD = Subwell Drain
 PD = Pade Drain
 CB = Catch Basin
 TD = Total Drain

APPENDIX C

Properties with Suspected Improper Connections

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix C

Properties with Suspected Improper Connections

Street Name and No.	Inspect. Date	Disappearing Downspouts	Basement					Sump Pump Does Not Discharge on the Ground	Cleanout Cap Not Intact	Comments/Notes
			Window Well Drains	Driveway Drains	Stairwell Drains	Patio Drains	Catch Basin			
10TH ST 916		2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED. DISCONNECTED DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.	
10TH ST 1122	9/27/00	0	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	COMMERCIAL SITE. NO DYE TESTING NEEDED. UNABLE TO LOCATE EXITING PIPES FROM THE BASEMENT WINDOW WELL DRAINS, NEED TO BE CHECKED.	
10TH ST 1232	11/1/00	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	COMMERCIAL SITE. DAP #1 UNCONFIRMED IN MH 16893 AND MH 7523. DAP #2 AND DAP #3 UNCONFIRMED IN MH 16893, MH 7523. MH LOCATED AT CENTERLINE OF UNION ST. AND 10TH ST., MH LOCATED AT CENTERLINE OF 10TH ST. NW OF MH 7523. MH LOCATED WEST SIDE OF 10TH ST. W OF MH 7523. CATCH BASINS, LOCATED AT THE NORTH END OF SITE, CONNECT AND FLOW TO 10TH ST. CURB CATCH BASIN LOCATED AT THE EAST SIDE OF 10TH ST. N OF MH 7523.	
10TH ST 1364	8/21/00	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	VACANT CHURCH PREVIOUSLY USED AS CLEAR CHOICES BUILDING. SITE HAS 2 CLEANOUTS, ONE CAP IS BROKEN. 9/13/00 LEFT LETTER.	
10TH ST 1308	10/11/00	2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE TEST UNCONFIRMED IN MH 6271. OCCUPANT SAYS LEAD GOES TO ALLEY. PIPES CLEANED EVERY 6 MONTHS. DISCONNECTED DISAPPEARING DOWNSPOUTS ARE NOT PROPERLY CAPPED. 9/13/00 LEFT LETTER.	
10TH ST 1914	8/1/00	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 242A. PIPES CLEANED IN WITHIN THE LAST 4 YEARS. DISAPPEARING DOWNSPOUT DRAINS INTO PERFORATED DRAIN TILE. 7/27/00 LEFT LETTER.	
10TH ST 1928	7/27/00	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	COMMERCIAL SITE. CITY PERFORMED FIRST DYE TEST WITH THE RESULT OF "BANCROFT ST. SEWER" RETEST DONE AND DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 1176. INFLOW INVESTIGATION PERFORMED AND FOUND THAT CATCH BASIN IS IN EXTREMELY POOR CONDITION, FILLED WITH DEBRIS, UNKNOWN CONNECTION. CATCH BASIN APPEARS TO BE AN OLD FLOOR DRAIN FROM A RECENTLY DEMOLISHED PORTION OF THE BUILDING. GRATE DRAIN LOCATED NEXT TO THE NORTH SIDE OF BUILDING IS FILLED WITH DEBRIS. UNKNOWN CONNECTION. ADVISED OWNER OF POOR CONDITION OF CATCH BASIN.	

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix C

Properties with Suspected Improper Connections

Street Name and No.	Inspect. Date	Disappearing Downspouts	Basement			Total Discharge on the Ground	Sump Pump Does Not Discharge on the Cap Not Intact	Cleanout Intact	Comments/Notes
			Window Well Drains	Driveway Drains	Stairwell Drains				
6TH ST 919	10/13/00	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	1	<input type="checkbox"/>	<input type="checkbox"/>	COMMERCIAL SITE CONCERNED WITH 923 6TH ST. 10/13/00 LEFT LETTER CONTACTED AMERTECH SECURITY TO GAIN ACCESS WITH NO SUCCESS. CATCH BASIN LOCATED AT THE NORTH SIDE OF SITE WEST WALL OF CATCH BASIN HAS A 6" LEAD WITH UNIDENTIFIED CONNECTION.
6TH ST 927	11/1/00	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 7568 SPOKE WITH PAUL AND SHERIE WHO ADVISE THAT FIRE QUITTED BLDG SEVERAL YEARS AGO AND EVERYTHING HAD TO BE REDONE. ALL PLUMBING GOES TO SAME LEAD. DISAPPEARING DOWNSPOUT NEEDS TO BE CHECKED.
6TH ST 1213	11/7/00	0	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	1	<input type="checkbox"/>	<input type="checkbox"/>	CHURCH DYE OBSERVED DISCHARGING FROM THE NORTH PIPE INTO MH 17019. ALL FACILITIES WERE PUT IN AT THE SAME TIME. STAIRWELL DRAIN IS FILLED WITH DEBRIS.
6TH ST 1433	6/14/00	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	COMBINED WITH 1431 6TH ST. NO DYE TESTING NEEDED. DISAPPEARING DOWNSPOUT NEEDS TO BE CHECKED.
7TH ST 821	9/27/00	0	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	2	<input type="checkbox"/>	<input type="checkbox"/>	VACANT SENIOR CENTER GOING TO BE DEMOLISHED. CATCH BASIN LOCATED AT THE EAST SIDE OF SITE CONNECTS TO MH AT NORTHWEST CORNER OF PROPERTY. MH FLOWS NORTH TO LADDER. STAIRWELL DRAIN NEEDS TO BE CHECKED.
7TH ST 905	10/3/00	1	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	2	<input type="checkbox"/>	<input type="checkbox"/>	COMMERCIAL SITE CONCERNED WITH 911 7TH ST. DYE TESTED BOTH SETS OF FACILITIES AND DYE WAS OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 17877. CATCH BASINS AND DISAPPEARING DOWNSPOUT NEEDS TO BE CHECKED.
7TH ST 1013	6/9/00	16	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	7	<input type="checkbox"/>	<input type="checkbox"/>	CHURCH AND HOUSE. NO DYE TESTING NEEDED. DISAPPEARING DOWNSPOUTS AND BASEMENT WINDOW WELL DRAINS NEED TO BE CHECKED.
7TH ST 1016	11/20/00	0	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	4	<input type="checkbox"/>	<input type="checkbox"/>	A TOTAL OF 6 DYE TESTS WERE PERFORMED. DAP #1 - #4 DYE OBSERVED DISCHARGING FROM THE NORTH PIPE INTO MH 17593. DAP #5, #6 DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 17877. CATCH BASIN LOCATED AT THE EAST SIDE OF SITE. CATCH BASINS ON EAST PROPERTY CONNECT WITH ONE CATCH BASIN HAVING AN EAST LEAD WITH UNKNOWN CONNECTION. 2 CATCH BASINS (WITH MULTIPLE LEADS) LOCATED ON THE SOUTH SIDE OF SITE CONNECT AND FLOWS TO MH ON 7TH ST. 2 CATCH BASINS (WITH MULTIPLE LEADS) AT NORTH SIDE OF PROPERTY CONNECT TO MH ON 7TH ST.

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation

Appendix C

Properties with Suspected Improper Connections

Street Name and No.	Inspect. Date	Disappearing Downspouts	Basement					Total Discharge on the Ground	Does Not Discharge on the Ground	Cleanout Cap Not Intact	Comments/Notes
			Window Well Drains	Driveway Drains	Stairwell Drains	Patio Drains	Catch Basin Drains				
7TH ST 1021	6/9/00	4	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	NO DYE TESTING NEEDED. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.	
7TH ST 1208	6/9/00	2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	NO DYE TESTING NEEDED. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.	
7TH ST 1229	8/10/00	5	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	COMMERCIAL SITE. DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 6436. PIPES HAVE BEEN CLEANED 3X WITHIN THE PAST 5 YEARS FOR ROOT REMOVAL. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.	
7TH ST 1304	6/9/00	2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	APARTMENTS. 9/19/00 AND 8/10/00 LEFT LETTER. TENANT DENIED ACCESS. DISCONNECTED DISAPPEARING DOWNSPOUT IS NOT PROPERLY CAPPED.	
7TH ST 1317	6/9/00	11	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	2	<input type="checkbox"/>	CHURCH AND HOUSE. NO DYE TESTING NEEDED. DISAPPEARING DOWNSPOUTS AND BASEMENT WINDOW WELL DRAINS NEED TO BE CHECKED.	
7TH ST 1331	10/13/00	11	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	CHURCH BUILT IN 1889. INSPECTORS CALLED 985-9616 TO GAIN ACCESS TO CHURCH. DYE TEST UNCONFIRMED IN MH 6491, MH 6493 AND MH 6436. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.	
7TH ST 1402	8/14/00	0	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	1	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE EAST PIPE INTO MH 6491. PIPES CLEANED YEARLY.	
7TH ST 1408	6/12/00	2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	APARTMENTS. NO ONE HOME. 10/30/01 8/18/00 AND 8/24/00 LEFT LETTER. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.	
7TH ST 1428	8/24/00	2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 6315. NEW SEWER LEAD INSTALLED IN 1998. PIPES CLEANED EVERY SIX MONTHS FOR ROOT REMOVAL. 8/18/00 LEFT LETTER. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.	
7TH ST 1521	8/18/00	5	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 4689. 8/10/00 LEFT LETTER. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.	
8TH ST 821	5/22/00	2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input checked="" type="checkbox"/>	NO DYE TESTING NEEDED. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.	

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix C

Properties with Suspected Improper Connections

Street Name and No.	Inspect. Date	Disappearing Downspouts	Basement					Sump Pump			Cleanout Intact	Comments/Notes
			Window Well Drains	Driveway Drains	Stairwell Drains	Patio Drains	Catch Basin Drains	Total Discharge on the Ground	Does Not Cap	Not Intact		
8TH ST 825	8/22/00	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE SOUTHEAST PIPE INTO MH 15328. DISAPPEARING DOWNSPOUT NEEDS TO BE CHECKED.
8TH ST 913	8/22/00	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE NORTH PIPE INTO MH 1897. DISAPPEARING DOWNSPOUT NEEDS TO BE CHECKED.
8TH ST 1033	8/23/00	4	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	CHURCH COMBINED WITH 811 WALL ST. NO DYE TESTING NEEDED. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.
8TH ST 1215	8/21/00	2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.
8TH ST 1225	10/13/00	4	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE EAST PIPE INTO MH 16895. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.
8TH ST 1315	5/24/00	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED. DISAPPEARING DOWNSPOUT NEEDS TO BE CHECKED.
8TH ST 1330	9/6/00	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 6491. MH 5244 WAS NEGATIVE FOR DYE. 8/18/01 LEFT LETTER. FRONT DISAPPEARING DOWNSPOUT NEEDS TO BE CHECKED.
8TH ST 1406	5/24/00	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED. DISAPPEARING DOWNSPOUT NEEDS TO BE CHECKED.
8TH ST 1418	8/18/00	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE NORTHEAST PIPE INTO MH 5312. PIPES ARE CLEANED 3X - 4X PER YEAR FOR ROOT REMOVAL. DISAPPEARING DOWNSPOUT NEEDS TO BE CHECKED.
8TH ST 1524	8/9/00	5	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	COMBINED WITH 735 GRISWOLD ST. DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 3791. UNUSHD DISAPPEARING DOWNSPOUT NOT CAPPED.
8TH ST 1609	10/10/00	0	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE EAST PIPE INTO MH 2879. 10/6/00 AND 9/25/00 LEFT LETTER. BASEMENT WINDOW WELL DRAIN NEEDS TO BE CHECKED.
9TH ST 920	5/18/00	2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix C

Properties with Suspected Improper Connections

Street Name and No.	Inspect. Date	Disappearing Downspouts	Basement					Total Discharge on the Ground	Does Not Discharge on the Ground	Cleanout Cap Not Intact	Comments/Notes
			Window Well Drains	Driveway Drains	Stairwell Drains	Patio Drains	Catch Basin Drains				
9TH ST	1512 9/14/00	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE EAST PIPE INTO MAH 5444 DISAPPEARING DOWNSPOUT NEED TO BE CHECKED.
9TH ST	1819 10/26/00	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	NO ONE HOME. EXTERNAL CLEANOUT CAP NOT PROPERLY CAPPED.
9TH ST	1823 5/30/00	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	NO DYE TESTING NEEDED. NO CAP ON EXTERNAL CLEANOUT.
BANCROFT ST	921 9/6/00	2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.
CHESTNUT ST	727 6/6/00	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED. DISAPPEARING DOWNSPOUT NEEDS TO BE CHECKED.
CHESTNUT ST	805 9/13/00	4	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	9	<input type="checkbox"/>	<input type="checkbox"/>	CHURCH DYE OBSERVED DISCHARGING FROM THE EAST PIPE INTO MAH 6271. MR. CAMPBELL, FROM CHURCH, INDICATED THAT THE DISAPPEARING DOWNSPOUTS ARE CONNECTED TO THE SANITARY LEAD. THIS IS ALSO POSSIBLY THE CASE WITH THE BASEMENT WINDOW WELL DRAINS.
CHESTNUT ST	834 10/13/00	2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	8	<input type="checkbox"/>	<input type="checkbox"/>	SCHOOL. NO DYE TESTING NEEDED. 3 CATCH BASINS IN NORTH PARKING LOT WITH A CLEANOUT LOCATED IN ONE, AND A NORTHEAST 4" LEAD IN ANOTHER. 4 CATCH BASINS AND A MANHOLE ARE LOCATED IN THE ADJACENT PLAVOROUND. ALL OF THEM CONNECT, WITH A SINGLE LEAD GOING EAST, AND CONNECTING TO A SEWER LINE FLOWING NORTH. ALSO, ONE OF THE CATCH BASINS HAS A 4" EAST LEAD AND A 4" WEST LEAD. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.
CHESTNUT ST	925 8/21/00	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED. DISCONNECTED DISAPPEARING DOWNSPOUT IS NOT PROPERLY CAPPED.
COURT ST	722 6/1/00	3	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	COMBINED WITH 74 COURT ST. NO DYE TESTING NEEDED. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.
COURT ST	801 6/1/00	3	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	NO ONE HOME. 9/22/00, 8/17/00 AND 8/16/00 LEFT LETTER DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.
COURT ST	803 6/1/00	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	COMBINED WITH 805 COURT ST AND 807 COURT ST. NO DYE TESTING NEEDED. DISAPPEARING DOWNSPOUT NEEDS TO BE CHECKED.

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation

Appendix C

Properties with Suspected Improper Connections

Street Name and No.	Inspect. Date	Disappearing Downspouts	Basement					Total Discharge on the Ground	Sump Pump Does Not Discharge on the Ground	Cleanout Cap Not Intact	Comments/Notes
			Window Well Drains	Driveway Drains	Stairwell Drains	Patio Drains	Catch Basin Drains				
COURT ST 809	6/1/00	3	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	COMBINED WITH 811 COURT ST, 813 COURT ST AND 815 COURT ST. NO DYE TESTING NEEDED. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.
COURT ST 819	6/1/00	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED. DISAPPEARING DOWNSPOUT NEEDS TO BE CHECKED.
COURT ST 822	6/1/00	4	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.
COURT ST 833	6/2/00	2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.
COURT ST 903	6/2/00	4	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	CHURCH BUILDING. NO ONE HOME. 10/9/99, 10/4/00 AND 9/22/00 LEFT LETTER. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.
COURT ST 911	8/21/00	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	COMBINED WITH 913 COURT ST. NO DYE TESTING NEEDED. DISAPPEARING DOWNSPOUT NEEDS TO BE CHECKED.
COURT ST 921	6/2/00	2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.
GRISWOLD ST 603	10/11/00	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	COMMERCIAL SITE. DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 5614. PIPES CLEANED 10/00. DISAPPEARING DOWNSPOUT NEEDS TO BE CHECKED.
GRISWOLD ST 622	8/23/00	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED, BUT DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.
GRISWOLD ST 636	8/23/00	2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED, BUT DISCONNECTED DISAPPEARING DOWNSPOUT LOCATED AT THE SOUTHWEST CORNER OF THE HOME IS NOT PROPERLY CAPPED.
GRISWOLD ST 731	8/23/00	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input checked="" type="checkbox"/>	<input type="checkbox"/>	COMMERCIAL SITE COMBINED WITH 1312 8TH ST. NO DYE TESTING NEEDED, BUT CLEANOUT IS NOT PROPERLY CAPPED.
GRISWOLD ST 802	8/23/00	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED, BUT DISCONNECTED DISAPPEARING DOWNSPOUT IS NOT PROPERLY CAPPED.

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix C

Properties with Suspected Improper Connections

Street Name and No.	Inspect. Date	Disappearing Downspouts	Basement					Sump Pump		Cleanout Cap Not Intact	Comments/Notes
			Window Well Drains	Driveway Drains	Stairwell Drains	Patio Drains	Catch Basin Drains	Total Drains	Does Not Discharge on the Ground		
GRISWOLD ST	8/23/00	5	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	NO DYE TESTING NEEDED, BUT DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.	
HOWARD ST	10/11/00	2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	2	<input type="checkbox"/>	COMMERCIAL SITE - VACANT BUILDING. DYE TESTING CANNOT BE PERFORMED BECAUSE OF TRAFFIC AT INTERSECTION OF LABREER AVE. AND 7TH ST. CB #1 HAS A NORTHEAST LEAD WHICH IS JOINED BY CB #2 AND CONTINUING TO MH IN PARKING LOT. THIS MH FLOWS NORTH TO LABREER.	
HOWARD ST	8/21/00	2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 16110. OCCUPANTS HAVE BEEN IN HOME ONE YEAR. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.	
LABREER AVE	9/27/00	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	1	<input type="checkbox"/>	COMMERCIAL SITE COMBINED WITH 710, 712, 714, 716 LABREER AVE. CANNOT PERFORM DYE TEST BECAUSE OF TRAFFIC VOLUME AT THE INTERSECTION OF LABREER AVE. AND 7TH ST. CATCH BASIN HAS A 4" NORTHEAST LEAD WITH UNKNOWN CONNECTION. INSPECTORS LEFT CARD W/BARTENDER AT ACTIVE LOUNGE. INSPECTORS SPOKE WITH OCCUPANT OF ANTIQUE STORE AND WERE ADVISED THAT HE ONLY RENTS THE SPACE AND HE DOES NOT HAVE ACCESS TO THE BASEMENT. CATCH BASIN NEEDS TO BE CHECKED.	
LABREER AVE	9/27/00	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	1	<input type="checkbox"/>	COMMERCIAL SITE. NO DYE TESTING NEEDED. CATCH BASIN LOCATED AT THE SOUTHEAST CORNER OF SITE CONNECTS TO A SEWER FLOWING NORTH TO LABREER AVE.	
LABREER AVE	8/23/00	2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	COMMERCIAL SITE COMBINED WITH 804, 806, 808, 810 AND 812 LABREER AVE. DYE TEST COULD NOT BE PERFORMED BECAUSE OF TRAFFIC VOLUME AT THE INTERSECTION OF 7TH ST. AND LABREER AVE. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.	

**City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix C**

Properties with Suspected Improper Connections

Street Name and No.	Inspect. Date	Disappearing Downspouts	Basement			Sump Pump			Cleanout Cap Not Intact	Comments/Notes
			Window Well Drains	Driveway Drains	Stairwell Drains	Patio Drains	Catch Basin Drains	Total Discharge on the Ground		
LAPERER AVE 828	11/9/00	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	1	<input type="checkbox"/>	<input type="checkbox"/>	CHURCH. NO DYE TESTING NEEDED. PRINT SHOWS ADDITION CONSTRUCTED OVER DEMOLISHED HOME AND GARAGE. HALL ALSO TO BE RAZED. SEPARATE SANITARY AND STORM LEADS EXIT WEST SIDE OF STRUCTURE. BOTH LEADS FLOW TO MH ON EAST SIDE OF PROPERTY. COMBINED SEWER RUNS NORTH FROM MH TOWARDS LAPERER. INFLOW INVESTIGATION CONFIRMS PRINT INFORMATION. INVESTIGATION ALSO SHOWS SOUTHERNMOST STORM MH HAS A 4" CLAY NORTH LEAD, BUT CONNECTION TO CATCH BASIN, LOCATED DIRECTLY NORTH OF MH, COULD NOT BE CONFIRMED. CATCH BASIN AT SOUTH END OF SITE HAS A 4" SOUTH LEAD AND A 4" NORTH LEAD WHICH CONNECTS TO MH LOCATED NORTH OF CATCH BASIN. MH NORTH OF CATCH BASIN HAS A 4" SOUTH LEAD, AN EAST LEAD AND A WESTERN LEAD. FLOW IS TO THE WEST AND CONNECTS TO CATCH BASIN LOCATED AT 9TH ST. IT SHOULD BE NOTED THAT A CLEANOUT EXISTS AT THE NORTH SIDE OF OLD BUILDING; NO DYE TESTING DONE ON THIS BLDG BECAUSE OF TRAFFIC VOLUME AT 7TH ST AND LAPERER AVE.
LAPERER AVE 912	9/11/00	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	4	<input type="checkbox"/>	<input type="checkbox"/>	COMMERCIAL SITE COMBINED WITH 912 GILLETTE ST. DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 1528. PRINT SHOWS THREE CBS, ALTHOUGH THERE ARE ACTUALLY FOUR CBS ON THE PROPERTY. ALL CBS JOIN TOGETHER AND EXIT THE PROPERTY VIA ONE LEAD, CONNECTING TO MH 1528.
LAPERER AVE 930	9/18/00	1	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	COMMERCIAL SITE. DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 997. ROOF DRAIN POSSIBLY CONNECTS TO MH 997 FROM A DIRECT 3" LEAD. THIS NEEDS TO BE CHECKED.
LAPERER AVE 933	10/11/00	3	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	4	<input type="checkbox"/>	<input type="checkbox"/>	COMMERCIAL SITE. DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 150699 (LOCATED WEST OF RIVER CENTRE DR., NORTH SIDE OF LAPERER AVE.) PRINT AVAILABLE IN SITE OFFICE, BUT MANAGER WOULD NOT LET US BORROW PRINT TO COPY. ALTHOUGH SHE MADE A COPY OF PERTINENT AREAS ON REGULAR COPY MACHINE. 4 CATCH BASINS. NORTH CATCH BASIN HAS NORTHEAST AND SOUTHWEST LEADS. EAST CATCH BASIN HAS A 6" NORTHEAST PVC LEAD. SOUTHEAST CATCH BASIN HAS AN 8" NORTH PVC LEAD. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.
LAPERER AVE 945	10/11/00	6	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	1	<input type="checkbox"/>	<input type="checkbox"/>	COMMERCIAL SITE. DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 150499 (LOCATED WEST OF RIVER CENTRE CR., NORTH SIDE OF LAPERER AVE.) AN UNKNOWN PVC PIPE EXISTS EAST SIDE OF BLDG AND DISCHARGES INTO PIPE IN THE GROUND. CATCH BASIN HAS A NORTH LEAD AND DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.

**City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix C**

Properties with Suspected Improper Connections

Street Name and No.	Inspect. Date	Disappearing Downspouts	Basement				Patio Drains	Catch Basin	Total Drains	Sump Pump		Cleanout Intact	Comments/Notes
			Window Well Drains	Driveway Drains	Stairwell Drains	Does Not Discharge on the Ground				Cap Not Intact			
PINE ST 615	11/3/00	5	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	5	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	COMMERCIAL SITE. NO DYE TESTING NEEDED. PRINT SHOWS ONE 8" SANITARY LEAD EXITS EAST SIDE OF BLDG. CONNECTING TO 12" SANITARY SEWER IN ALLEY. 2ND PRINT (FOR 924 7TH ST.) ALSO SHOWS A SANITARY LEAD EXITING THE NORTH SIDE OF THE BLDG AND FLOWING TO SEWER IN ALLEY. INFLOW INVESTIGATION SHOWS CATCH BASIN #1 AND CATCH BASIN #2 LOCATED AT SOUTH END OF SITE. JOIN VIA 10" PVC AND FLOW TO 7TH ST. CATCH BASIN #3, LOCATED AT NORTH SIDE OF SITE, CONNECTS TO DISAPPEARING DOWNSPOUT. CATCH BASIN #4 AND CATCH BASIN #5 JOIN TO CONNECT TO DISAPPEARING DOWNSPOUT AND PATIO DRAIN.	
PINE ST 710	10/10/00	13	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	CHURCH BUILT IN 1864. #1 TEST DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 17903. #2 TEST DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 17903. #3 TEST DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 17903. PIPES CLEANED YEARLY. MH 17903 DOES HAVE A SOUTH LEAD GOING DIRECTLY TO THE CHURCH, POSSIBLY SERVICES DISAPPEARING DOWNSPOUTS. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED. PRINT IS FOR RENOVATION OF ENTRANCE WAY. NO PLUMBING DETAILS.	
PINE ST 721	10/24/00	31	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	8	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	PORT HURON HOUSING COMMISSION COMBINED WITH 705 PINE ST, 755 PINE ST, 919 7TH ST. AND 920 8TH ST. FIVE (5) DYE TESTS WERE PERFORMED (1 ON EACH WING). 2 TESTS DYE WAS OBSERVED DISCHARGING FROM THE WEST PIPE INTO MH 17857. 3RD TEST DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 15937. 4TH TEST DYE OBSERVED DISCHARGING FROM THE SOUTHEAST PIPE INTO MH 15937. 5TH TEST DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 15544. MH 17903, MH 17703 AND MH AT EAST LAWN CHECKED AND FOUND NEGATIVE FOR DYE. DRAINS CONSIST OF 2 PARKING LOT CATCH BASINS, 1 TRENCH DRAIN LOCATED IN THE NORTHEAST SIDEWALK AND 5 LAWN CATCH BASINS. THERE ARE 6 CLEANOUTS, 4 ARE LOCATED ON THE SOUTHWEST CORNER OF THE BUILDING AND 2 ARE LOCATED AT THE INTERSECTION OF THE NORTH SIDE OF THE BUILDING. ALL CATCH BASINS CONNECT TO SANITARY LEADS (SEE DIAGRAMS). RETEST DONE AT NORTH AND EAST WINGS. DYE WAS NOT OBSERVED AT EITHER OF THE MANHOLES LOCATED ON THE PROPERTY.	
PINE ST 811	5/17/00	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED, BUT DISAPPEARING DOWNSPOUT NEEDS TO BE CHECKED.	
PINE ST 815	5/17/00	3	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	UNCONFIRMED AT MH 13. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.	

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix C

Properties with Suspected Improper Connections

Street Name and No.	Inspect. Date	Disappearing Downspouts	Basement					Total Discharge on the Ground	Sump Pump Does Not Cleanout	Catch Basin Drains	Cleanout Intact	Comments/Notes
			Window Well Drains	Driveway Drains	Stairwell Drains	Patio Drains	Drains					
PINE ST 821	8/21/00	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED, BUT DISCONNECTED DISAPPEARING DOWNSPOUT IS NOT PROPERLY CAPPED.	
PINE ST 940	9/22/00	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	UNCONFIRMED IN MH 16269N AND MH 7522. OCCUPANT ADMINISTERED DYE. DISAPPEARING DOWNSPOUT NEEDS TO BE CHECKED.	
UNION ST 620	8/18/00	2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO MH 17927. NEW CLEANOUT LEAD. 8/18/00 DAVE SMITH FROM THE CITY OF PORT HURON CALLED FIELD OFFICE AND ASKED THAT SOMEONE CONTACT RESIDENT IS CALLED RESIDENT AND DISCUSSED INFLOW SOURCES. DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.	
UNION ST 719	6/5/00	4	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED, BUT DISAPPEARING DOWNSPOUTS AND BASEMENT WINDOW WELL DRAINS NEED TO BE CHECKED.	
UNION ST 720	6/5/00	3	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED, BUT DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.	
UNION ST 729	6/5/00	2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED, BUT DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.	
UNION ST 811	6/6/00	2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED, BUT DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.	
UNION ST 816	6/6/00	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED, BUT DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.	
UNION ST 827	6/6/00	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED, BUT DISAPPEARING DOWNSPOUT NEEDS TO BE CHECKED.	
UNION ST 828	6/6/00	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	NO DYE TESTING NEEDED, BUT EXTERNAL CLEANOUT IS NOT PROPERLY CAPPED.	
UNION ST 917	6/6/00	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED, BUT DISAPPEARING DOWNSPOUT NEEDS TO BE CHECKED.	
WALL ST 729	5/17/00	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED, BUT DISAPPEARING DOWNSPOUT NEEDS TO BE CHECKED.	

City of Port Huron
7th and 9th Street
Dye Testing and Private Property
Inflow Source Investigation
Appendix C

Properties with Suspected Improper Connections

Street Name and No.	Inspect Date	Disappearing Downspouts	Basement				Sump Pump			Cleanout Cap Not Intact	Comments/Notes
			Window Well Drains	Driveway Drains	Stairwell Drains	Patio Drains	Catch Basin Drains	Total Drains	Does Not Discharge on the Ground		
WALL ST 735	5/17/00	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED, BUT DISAPPEARING DOWNSPOUT NEEDS TO BE CHECKED.
WALL ST 904	8/14/00	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	CONFINED WITH 11 1/2" 9TH ST. DYE OBSERVED DISCHARGING FROM THE SOUTH PIPE INTO 4TH 16395. PIPES ARE CLEANED 3X PER YEAR. DISAPPEARING DOWNSPOUT NEEDS TO BE CHECKED.
WALL ST 913	9/11/00	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	THREE (3) APARTMENTS. DYE OBSERVED DISCHARGING FROM THE WEST PIPE INTO 4TH 16269. EXTERNAL CLEANOUT IS NOT PROPERLY CAPPED, BUT IT IS LOCATED UNDER A DECK AND IS NOT AN INFLOW SOURCE. 8/24/00 LEFT LETTER.
WATER ST 600	9/27/00	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	COMMERCIAL SITE. NO DYE TESTING NEEDED. 4 CATCH BASINS IN THE PARKING AREA. 6" SANITARY LEAD EXITS THE SOUTH SIDE OF THE BUILDING AND THEN TURNS EAST. CATCH BASIN AT SOUTH END HAS A NORTHWEST LEAD. CATCH BASIN AT NORTH END HAS AN 8" NORTHEAST LEAD.
WHITE ST 709	6/8/00	2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED, BUT DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.
WHITE ST 733	6/8/00	1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED, BUT DISAPPEARING DOWNSPOUT NEEDS TO BE CHECKED.
WHITE ST 737	6/8/00	0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED.
WHITE ST 814	6/8/00	3	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NO DYE TESTING NEEDED, BUT DISAPPEARING DOWNSPOUTS NEED TO BE CHECKED.

